arXiv:1109.6640v2 [physics.class-ph] 1 May 2012

Self-oscillation

Alejandro Jenkins*
High Energy Physics, 505 Keen Building, Florida State University, Tallahassee, FL 32306-4350, USA

Physicists are very familiar with forced and parametric resonance, but usually not with self-oscillation, a property of certain dynamical systems that gives rise to a great variety of vibrations, both useful and destructive. In a self-oscillator, the driving force is controlled by the oscillation itself so that it acts in phase with the velocity, causing a negative damping that feeds energy into the vibration: no external rate needs to be adjusted to the resonant frequency. A little-known paper from 1830 by G. B. Airy provides us with the opening to introduce self-oscillation as a sort of "perpetual" motion responsible for the human voice. The famous collapse of the Tacoma Narrows bridge in 1940, often attributed by introductory physics texts to forced resonance, was actually a self-oscillation, as was the swaying of the London Millennium Footbridge in 2000. Clocks are self-oscillators, as are bowed and wind musical instruments. The heart is a "relaxation oscillator," i.e., a non-sinusoidal self-oscillator whose period is determined by sudden, nonlinear switching at thresholds. We review the general criterion that determines whether a linear system can self-oscillate. We then describe the limiting cycles of the simplest nonlinear self-oscillators. We characterize the operation of motors as self-oscillation and prove a general theorem about their limit efficiency, of which Carnot's theorem for heat engines appears as a special case. We also briefly discuss how self-oscillation applies to servomechanisms, Cepheid variable stars, lasers, and the macroeconomic business cycle, among other applications.

Keywords: positive feedback, negative damping, linear instability, relaxation oscillations, limit cycles, entrainment, motors, limit efficiency

PACS: 46.40.Ff, 02.30.Yy, 45.20.dg, 01.65.+g

Contents

I. Introduction 3

II. Perpetual motion 4
A. Energy conservation 4
B. Irreversibility 4
C. Overbalanced wheels 4
D. Voice as perpetual motion 5
E. Delayed action 6
F. Negative damping 7

III. Self-oscillation versus resonance 8
A. Forced resonance 8
B. Work on oscillator 8
C. Flow-induced instabilities 9
D. Active versus passive devices 11
E. Violin versus æolian harp 11
F. Parametric resonance 13

IV. Feedback systems 15
A. Clocks 15
B. Relaxation oscillations 16
C. Van der Pol oscillator 17
D. The heart is a self-oscillator 18
E. Entrainment 20

---

*Electronic address: jenkins@hep.fsu.edu

F. Chaos 21

V. Control theory 21
A. General linear systems 21
1. Stability criterion 22
2. Gyroscopic systems 23
B. Limit cycles 24
1. Van der Pol's equation 25
2. Asymmetric oscillations 27
3. Forced self-oscillators 28
4. FitzHugh-Nagumo model 29
5. Poincaré-Lyapunov stability analysis 31

VI. Motors 32
A. Turbines 32
B. Heat engines 32
C. Limit efficiency 33
1. Carnot's theorem revisited 34
2. Minimal friction in mechanisms 37

VII. Other applications 40
A. Servomechanisms 40
B. Thermoacoustic self-oscillators 40
1. Putt-putt boat 40
2. Rijke tube 42
3. Rayleigh criterion 43
4. Cepheid variables 43
C. Lasers 45
D. Business cycle 45

VIII. Summary and discussion 47

Acknowledgments 48

Appendices 48

A. Josephson effect 48

B. Historical aperçu 49

C. Note on sources 51

References 51

I. INTRODUCTION

> My pulse, as yours, doth temperately keep time,
> And makes as healthful music: it is not madness
> That I have utter'd
>
> —*Hamlet*, act 3, scene 4

Self-oscillation is the generation of a periodic motion from a source of power that lacks a corresponding periodicity: the oscillation itself controls the phase with which the source of power acts on it. Self-oscillation is also known as "maintained," "sustained," "self-excited," "self-induced," "spontaneous," "autonomous," and (in certain contexts) "hunting" or "parasitic" vibration.[1] The main purpose of this article is to bring self-oscillation to the attention of theoretical physicists, to whom it is not usually taught in any systematic way. We shall, therefore, emphasize not only its practical importance, including its applications in mechanical engineering, acoustics, electronics, and biomechanics (perhaps even in finance and macroeconomics) but also why it is conceptually fascinating.

Section II introduces the subject by revisiting the hoary question of perpetual motion. The earliest mathematical treatment of self-oscillation (at least as far as we have been able to determine) appears in a brief paper published in 1830 by G. B. Airy, in which he characterized the vibration of the human vocal chords as a form of "perpetual" motion compatible with the laws of Newtonian physics. A discussion of Airy's paper gives us the opportunity to introduce the key concepts of *positive feedback* and *negative damping*.

Section III stresses, both theoretically and through concrete examples, the distinction between self-oscillation and the phenomena —more familiar to theoretical physicists— of forced and parametric resonance. Meanwhile, Sec. IV underlines the role of feedback in self-oscillators and illustrates important qualitative features of their performance. Sections II – IV form a self-contained presentation in which the main features of self-oscillation are reviewed at a level that should be accessible and interesting to an advanced undergraduate physics student.

Section V characterizes self-oscillation with greater mathematical precision, covering both the linear instability at equilibrium and the nonlinear limiting cycles. Although it is also self-contained, the purpose of this section is not to provide a thorough recapitulation of the mathematical theory of self-oscillating systems, but rather to illuminate the close connection of the study of self-oscillation with *control theory*, a rich field in applied mathematics of enormous relevance to modern technology.

Section VI treats motors as self-oscillators, focusing on their ability to convert energy energy inputted at one frequency (often zero) into work outputted at another frequency. We state and prove a general result about the maximum efficiency attainable by motors, of which Carnot's theorem for heat engines is a special case. The arguments made in Sec. VI C 1 are, as far as we know, largely original and might provide a somewhat novel perspective on some aspects of thermodynamics.

Section VII covers other specific instances of self-oscillation. This is an eclectic selection, intended to underline the broad applicability of the concepts covered in this article. The description of lasers as self-oscillators in Sec. VII C, opens questions about the extension of self-oscillation and related concepts to quantum systems (one such system, the Josephson junction, is discussed in Appendix A). Section VII D explores the use of the concept of self-oscillation in economics and raises broader issues concerning the use of physics-inspired models to describe markets and other human organizations.

Though the presentation is intended to be largely self-contained, important results that are available in standard texts are only referenced. The emphasis is on bringing out and organizing key concepts, especially when these are not stressed in the literature. We pay particular attention to the flow of energy that powers self-oscillators. This will be useful in developing a more concrete physical understanding of self-oscillation than what can be gathered from the mathematical treatment usually applied to such phenomena in the theory of nonlinear dynamical systems.

This is not a historically-oriented review, though historical episodes and curiosities will be discussed when useful in guiding or illustrating the conceptual treatment of self-oscillation. Appendix B gives a brief overview of the history proper. This might help some readers to place the subject in context and to better understand why it has not made it into physics textbooks, at least not in the form in which we approach it. Appendix C points out the sources most useful to a physics student wishing to learn the subject systematically.

---

[1] The variants "self-maintained," "self-sustained," "self-sustaining," and "self-exciting", also occur. This diversity of terminology probably reflects the lack of an authoritative textbook treatment of the subject from the point of view of elementary classical physics and wave mechanics (see Appendix C), so that researchers tend to use whichever term is more prevalent in their own field. The term "self-oscillation" (also translated as "auto-oscillation") was coined by Soviet physicist Aleksandr Aleksandrovich Andronov (1901–1952) [1–3]. Andronov, a student of Leonid Mandelstam, was a professor at Gorky State University and, later in life, a deputy of the Supreme Soviet of the USSR. He and his associates made important contributions to the mathematical theory of the stability of nonlinear dynamical systems [4].

II. PERPETUAL MOTION

A. Energy conservation

Let us begin by considering the old chimera of perpetual motion. The state of a classical system (i.e., of an arbitrary machine) may be characterized by an N-dimensional, generalized-coordinate vector $\mathbf{q}$, with components q_i. In the Euler-Lagrange formalism of classical mechanics, the equation of motion for the system is expressed as

$$\frac{d}{dt}\left(\frac{\partial L}{\partial \dot{q}_i}\right) = \frac{\partial L}{\partial q_i} \tag{1}$$

where the overdot indicates the derivative of q_i with respect to time t, and $L \equiv T - V$ is the system's Lagrangian (where T is kinetic and V the potential energy, expressed as functions of $\dot{\mathbf{q}}$, $\mathbf{q}$, and t). If L is not an explicit function of time, then, by Eq. (1), the energy

$$H \equiv \sum_i \dot{q}_i \frac{\partial L}{\partial \dot{q}_i} - L \tag{2}$$

is a constant of the motion, $dH/dt = 0$ (see [5] for the conditions under which $H = T + V$). A perpetual motion machine "of the first kind," which would have greater energy every time it comes to a configuration characterized by the same $\mathbf{q}^{(0)}$, therefore requires a time-dependent Lagrangian. The fundamental laws of Nature are believed to be time-independent and energy conservation is the reason usually given why perpetual motion of the first kind is impossible.

B. Irreversibility

That same argument, however, implies that the machine should run forever, but no machine that runs with constant energy has ever been built. The reason is that, even though the Lagrangian of a closed system (such as the Universe as a whole) is believed to be time-independent, the Lagrangian of an open system (such as any conceivable machine that could be built by humans) will be time-dependent: mechanical energy is lost as heat leaks into the environment, causing the machine to wind down.[2]

A cyclic machine that runs merely by absorbing heat from the environment and converting it into useful work is called a perpetual motion device "of the second kind" [7]. According to Lord Kelvin's formulation of the second law of thermodynamics, such a machine is impossible, but this is just the systematic statement of an observed fact (see [7, 8]).[3] The underlying reason why work can be entirely converted into heat, but heat cannot be purely converted into work, concerns the fascinating problem of the "arrow of time," which we cannot deal with here except to say that it still presents conceptual difficulties for theoretical physics (cf. [10–13]).

Evidently, energy from the environment *may* flow into the machine and cause it to do useful work. For instance, the water in a stream turns the wheel of a mill and heat from burning coal powers a steam engine. This article shall focus on self-oscillation, an important type of externally-powered motion. As we shall explain, self-oscillators are characterized by the fact that *their own motion* controls the phase with which the external power source drives them. They are therefore, in a certain sense, self-driven (although not, of course, self-powered).

C. Overbalanced wheels

A perennially popular idea for a perpetual motion machine is the "overbalanced wheel," in which weights are attached to a wheel in such a way that the turning is supposed to shift the weights and keep the left and right half of the wheel persistently unbalanced. Early examples of such proposed devices appear in the work of Indian astronomer

---

[2] A device whose mechanical energy is exactly conserved is sometimes called a perpetual-motion machine "of the third kind," though more commonly the term perpetual motion is reserved for machines that can do useful work, such as pulling up a weight. On the history of the concept of "perpetual motion," see [6].

[3] In the same spirit, Stevinus, the 16th century Flemish mathematician and military engineer, correctly derived the forces acting on masses rolling on inclined planes from the assumption that perpetual motion is impossible. He was so proud of his argument that he had it inscribed on his tombstone. Feynman jokes that "if you get an epitaph like that on your gravestone, you are doing fine." [9]



FIG. 1: "Overbalanced" wheel conceived by Edward Somerset, 2nd Marquess of Worcester, *circa* 1640 [15]. Though the weights on the right always hang farther from the center than the weights on the left, in equilibrium two weights hang vertically in line with the wheel's center, while the twenty weights on the left balance the torque exerted by the eighteen weights on the right. The drawing is by R. T. Gould (Fig. 14 in [19]) and is used here with permission of his heirs.

Bhāskara II and French draughtsman Villard de Honnecourt, in the 12th and 13th centuries CE respectively [14]. Figure 1 shows another such a wheel, conceived in the 17th century by the Marquess of Worcester [15].

That a device of this kind cannot possibly work should be obvious to a modern student, since a machine powered by gravity alone must keep lowering its center of mass in order to accelerate or to maintain its velocity in the presence of friction.[4] Nonetheless, efforts to construct overbalanced wheels persist even today.[5]

A curious episode was the exhibition of such a machine by German inventor J. E. E. Bessler, *alias* Orffyreus, in the early 18th century, before various political and scientific dignitaries. Orffyreus's mechanism was hidden from view by the wheel's casing, but no observer was able to detect a fraud before the inventor himself destroyed the wheel in 1727, drifting thereafter into obscurity. In an essay on the subject, Rupert T. Gould (a 20th century English naval officer and amateur scholar, best remembered for his work on John Harrison's marine chronometers) admits that such a device would have required —contrary to its inventor's claims— an external source of power other than gravity, but also deems compelling the surviving testimonies of the wheel's successful operation [19].[6]

D. Voice as perpetual motion

Towards the end of his discussion of Orffyreus's wheel, Gould quotes extensively from an 1830 paper by mathematician and astronomer George Biddell Airy (who succeeded a few years later to the post of Astronomer Royal), rather alarmingly titled "On certain Conditions under which a Perpetual Motion is possible" [24]. In fact, Airy's brief paper has nothing to do with overbalanced wheels, but is rather an early attempt to understand the operation of the human

---

[4] See [16] for an explanation of the non-operation of Worcester's wheel in terms of explicit computation of the torques.

[5] The documentary *A Machine to Die For: The Quest for Free Energy*, released in 2003 and broadcast by Australian television [17], credulously showcases the work of various fringe researchers, while the few skeptics interviewed fail to adequately communicate any of the relevant physical concepts. One of the devices featured is a large overbalanced wheel built by French retired mechanic Aldo Costa outside his home in Villiers-sur-Morin [18]. That wheel seems notable only for being so large that it can be turned by the wind.

[6] Gould is co-protagonist of the remarkable TV adaptation of Dava Sobel's *Longitude* [20], itself a modern classic of the history of science for a general audience. Onscreen, Gould is portrayed as a sensitive man whose life is disrupted by nervous breakdowns and his consuming obsession with restoring Harrison's historic timepieces [21]. The circumstances of the scandal that cost Gould his marriage and his employment in the Royal Navy —which are inevitably more complex than what is represented in the miniseries— are explored in detail in [22]. Gould's credulity about such things as Nostradamus's prophecies (see [19]) might disappoint some admirers of the TV character. In an essay on the novels of Charles Reade, George Orwell wrote, not without admiration, that their appeal is "the same as one finds in R. Austin Freeman's detective stories or Lieutenant-Commander Gould's collections of curiosities —the charm of useless knowledge." [23]



(a) (b)

FIG. 2: An open tube, shaped like a a rectangular prism, with one of the sides at its end replaced by a flexible membrane (drawn in gray). In the lateral view (a) the air flows from left to right, while in the head-on view (b) the air flows out of the page. When the air flow starts, the membrane is initially deflected in, away from the horizontal position H. For steady flow, the membrane is in equilibrium at A. At B the air pushes it out, while at C the membrane is pulled in. Images adapted from Fig. 22 of [25].

voice, motivated by Robert Willis's pioneering research on that subject [25].[7]

Consider a long tube, open at both ends, in the form of a rectangular prism, much longer than it is wide and much wider than it is tall, with a side at one of the ends replaced by a taut, flexible membrane, as shown in Fig. 2. Without air flowing through the tube, the membrane sits flat and horizontal, as represented in the illustration by position H. Willis found experimentally that, for a steady airflow past the membrane, there is a position A, slightly below H, at which the membrane is in equilibrium. If it sits below that, as in B, the air will push the membrane out. If the membrane sits above the equilibrium, as in C, it will be pulled in.[8] It would seem, therefore, that turning on the airflow could cause the membrane to oscillate about the stable equilibrium at A.

If we picture the vocal chords as twin membranes vibrating in a steady air current, how do they draw energy in order to sustain that vibration and produce a persistent sound? Why is the vibration not damped out by friction and the resistance of the air? Both Willis and Airy noted that the answer must lie in the *delay* with which the stream of air exerts the restorative force that would act if the displacement were fixed. According to Airy,

> Mr. Willis explains this [sustained vibration] by supposing that *time* is necessary for the air to assume the state and exert the force corresponding to any position of the [membrane]: which is nearly the same as saying that the force depends on the position of the [membrane] at some previous time. [24]

Airy therefore modeled the vocal chords as a harmonic oscillator in which part of the restoring force depends on the displacement q at an earlier time:

$$\ddot{q}(t) = -a \cdot q(t) - b \cdot q(t - c) \tag{3}$$

He then showed, using first-order perturbation theory, that for $0 < b \ll a$ and $0 < c\sqrt{a} < \pi$, the amplitude of the oscillation grows after each period. This is what he identified as "perpetual motion."

Clearly, the energy of the oscillator described by Eq. (3) is not conserved, because the time-delayed force, $-bq(t-c)$, cannot be expressed as the derivative of any potential $V(q)$. This is why the kinetic energy of the oscillator can be greater each successive time it passes through the equilibrium position $q = 0$, as in a perpetual motion machine of the first kind.

E. Delayed action

If $b = 0$ in Eq. (3) then the force always pulls the oscillator back to its equilibrium position. But if $0 < b \ll a$ and $0 < c\sqrt{a} < \pi$, then as the oscillator passes through $q = 0$ the delayed force does not reverse its sign for a while, and therefore pushes the oscillator *away* from equilibrium. The bigger the amplitude of the oscillation, the stronger this pushing grows. Thus, the motion of the delayed oscillator may be understood as an instance of *positive feedback*: the oscillator drives itself, leading to an exponentially growing amplitude.[9]

---

[7] The Rev. Robert Willis (1800–1875) was the first English university professor to do significant research in mechanical engineering, as well as a distinguished architectural historian. He was the grandson of Dr. Francis Willis, the eccentric physician who attended King George III during his madness. [26]

[8] It is tempting to explain this pulling in by invoking Bernoulli's theorem, as many elementary texts do when discussing the lift on an airplane wing, but such an argument is flawed, for reasons that are clearly explained in [27].

Note that this positive feedback is greatest for $c\sqrt{a} = \pi/2$. This is both because $|q(t-c)|$ is at its maximum when $q = 0$ and because the time-delayed force always pushes in the same direction in which the oscillator is moving.

In the mid-19th century, Helmholtz invented a "fork-interrupter," in which a steel tuning fork rings persistently as the movement of one of its prongs switches an electromagnet on and off [29]. Lord Rayleigh, who appears to have been unaware of the work by Willis and Airy that we have summarized in Sec. II D, echoes their insight early in his monumental treatise on acoustics, *The Theory of Sound* (first published in 1877), when he explains that Helmholtz's fork-interrupter is a "self-acting instrument," whose operation is "often imperfectly apprehended," and that "any explanation which does not take account of the retardation of the [magnetic force with respect to the position of the prong] is wholly beside the mark." [30] Doorbell buzzers work on this same principle.[10]

Green and Unruh point out in [33] an even more elementary example of a self-oscillation associated with a time-delay: the audible tone produced by blowing air across the mouth of a bottle. The resulting tone is sustained because of the delay in the adjustment of the airflow in the neck of the bottle to the oscillating pressure inside. This allows more air to be drawn in when the internal pressure is high and less air to be drawn in when the internal pressure is low, thus feeding energy into the oscillation of the pressure.[11]

F. Negative damping

For small c (i.e., $0 < c\sqrt{a} \ll 1$), Eq. (3) can be written as a *negatively damped* linear oscillation:

$$\ddot{q} - \gamma \dot{q} + \omega^2 q = 0 \ , \tag{4}$$

where $\omega^2 = a + b$ and $\gamma = bc$. Negative damping corresponds to a component of the force acting *in phase with the velocity* $\dot{q}$. The faster the oscillator moves, the more it is pushed along the direction of its motion. The oscillator thus keeps drawing energy from its surroundings.[12] The amplitude of the oscillation grows exponentially with time, until it becomes so large that nonlinear effects become relevant and somehow determine a limiting amplitude. It is this which gives a regular self-oscillation.

At the end of Sec. II D we pointed out that the positive feedback in Eq. (3) is maximal when $c\sqrt{a} = \pi/2$. In that case, even though c is not small, the resulting motion may be described by Eq. (4), with $\gamma = b$ and $\omega^2 = a$, since for sinusoidal motion $-\dot{q}$ has a phase of $-\pi/2$ relative to q.

Self-oscillation describes not just the human voice, but also clocks, bowed and wind musical instruments, the heart, motors, and the theory of lasers, among other important kinds of mechanical, acoustic, and electromagnetic oscillations. Surprisingly, one searches the modern textbook literature in theoretical physics (both elementary and advanced) largely in vain for discussion of this interesting and important phenomenon.[13]

---

[9] Feedback is commonly thought of as the process of taking the output of a system (in this case, the displacement q), subjecting it to some processing (in this case, delaying it by c), and then inputting the result back into the system (as represented in this instance by the term proportional to $q(t-c)$ in Eq. (3)). Pippard suggests that, in general, it might be better to think of feedback as a series of cross-links between the elements that compose a dynamical system, which forces the system to behave in the only way consistent with the relations dictated by those linkages [28]. Feedback is said to be "positive" when it encourages the deviation of the system from some initial state or trajectory, "negative" when it discourages that deviation.

[10] An electrical circuit analogy for the self-oscillation of the vocal chords was worked out in [31], though without reference to the early work of Willis and Airy. For a more recent and detailed discussion of tuning fork self-oscillators, see, e.g., [32].

[11] In 1942, Minorsky pioneered the systematic mathematical study of the stability of dynamical systems with finite delays [34]. Bateman reviews the history of the subject in sec. 3.1 of [35], though he is unaware of the early work of Willis and Airy. Recently, Atiyah and Moore have speculated on the possible use of time-shifted equations of motion in relativistic field theories [36].

[12] Note that Eq. (4) is the equation of motion for the time-dependent Lagrangian $L = (\dot{q}^2 - \omega^2 q^2) \cdot \exp(-\gamma t)$.

[13] Most elementary physics textbooks treat only undamped, damped, and forced linear oscillations. More advanced texts often discuss parametric resonance as well (cf. [37–40]), but when self-oscillation is treated at all it is usually only in the context of a mathematical discussion of the limit cycles of the van der Pol equation (cf. [41–43]), a topic that we shall review in Sec. V B 1.



FIG. 3: Diagram of an RLC electric circuit used as a bandpass filter. The amplitude of $V_{\rm out}$ is maximized when the angular frequency of $V_{\rm in}$ is close to $1/\sqrt{LC}$. [45]

III. SELF-OSCILLATION VERSUS RESONANCE

A. Forced resonance

Self-oscillation is distinct from the conceptually more familiar phenomenon of forced resonance. In the case of a forced resonance, the damping is positive and there is a time-dependent driving term on the right-hand side of the equation of motion:

$$\ddot{q} + \gamma \dot{q} + \omega_0^2 q = \frac{F_0}{m} \cos\left(\omega_d t\right) \ . \tag{5}$$

The driving force produces a maximum amplitude of oscillation when the driving frequency ω_d is tuned to match the natural frequency ω_0 of the undriven oscillator. Even in the linear regime, the amplitude of a resonant oscillator diverges only if the damping vanishes. Furthermore, the amplitude of an undamped forced resonator diverges *linearly* with time (see [44]), not exponentially like the amplitude of a linear self-oscillator.

A popular classroom demonstration of forced resonance is to shatter a wine glass by playing its resonant note loudly enough on a nearby speaker. An ordinary radio tuner works by having the listener adjust the resonant frequency of an LC circuit to match the frequency at which the desired radio station is being broadcast, so that the corresponding signal drives the circuit resonantly. The radio tuner is an example of a bandpass filter (i.e., a device that allows only frequencies in a narrow band to pass through it), as represented by Fig. 3.

B. Work on oscillator

In general, the net energy that an oscillator gains over a complete period τ of its motion is

$$W_{\rm net} = \int_0^\tau dt\, \dot{q} F \ , \tag{6}$$

where F is the external force. Thus, if

$$F = F_0 \cos\left(\omega_d t\right) \tag{7}$$

and

$$q = A \cos\left(\omega_d t - \phi\right) \tag{8}$$

then

$$W_{\rm net} = \pi A F_0 \sin\phi \ , \tag{9}$$

so that energy can steadily flow into the oscillator only if the relative phase between the external force and the oscillation is $0 < \phi < \pi$. The most efficient transfer of power occurs when $\phi = \pi/2$, when F leads q by a quarter of a period. For a forced resonator this *only* happens when $\omega_d = \omega_0$. Moreover, if $\gamma = 0$ in Eq. (5), then $\sin\phi = 0$ for



FIG. 4: Photograph of the first suspension bridge over the Tacoma Narrows (part of Washington state's Puget Sound) showing the large twisting motion of the bridge's central span just before it collapsed on November 7, 1940. Even during construction, the bridge had earned the nickname "Galloping Gertie" because of its oscillation during the frequent high-wind conditions of the Narrows. The picture is from [50] and is used here with the permission of the University of Washington's Department of Civil and Environmental Engineering.

all $\omega_d \neq \omega_0$ (see [46]). On the other hand, for a self-oscillating equation of motion such as Eq. (4) the phase shift is automatically $\phi = \pi/2$ by virtue of the form of the negative damping term $-\gamma\dot{q}$. We will have much more to say in this article about how such a negative damping can arise in an actual physical system.

For an undamped forced resonator, the magnitude of F_0 in Eq. (9) is fixed, as given by the inhomogeneous term in Eq. (5). Thus, by Eq. (9) and using the fact that the energy E is proportional to the square of the amplitude A,

$$\dot{A} \propto \frac{\dot{E}}{\sqrt{E}} \propto \frac{W_{\rm net}\,\omega_d}{A} \propto A^0 \;, \tag{10}$$

which implies that A grows linearly in time. On the other hand, in a self-oscillator as described by Eq. (4), $F_0 = \gamma m \omega_d A$ scales linearly with A, so that

$$\dot{A} \propto A \;, \tag{11}$$

giving an exponential growth of the amplitude. Thus, the exponential increase of A in a linear self-oscillator reflects the fact that the motion drives itself.[14]

C. Flow-induced instabilities

Many physics texts and popular accounts attribute to forced resonance phenomena that are actually self-oscillatory. The most notorious case is the large torsional oscillation ("galloping") that led to the collapse of the suspension bridge over the Tacoma Narrows, in the state of Washington, in 1940 (see Fig. 4). When it fell, the bridge was exposed to steady winds of 68 km/h (42 mph). At that wind speed and given the dimensions of the bridge, the Strouhal frequency of turbulent vortex shedding was about 1 Hz and therefore could not have been forcing the bridge into an oscillation with the frequency observed (and documented in film) of about 0.2 Hz.[15]

---

[14] Note also that the solutions to Eq. (4) must be expressible as the real part of a complex exponential, because of linearity and time-translation invariance (see [47]); those conditions are broken by the inhomogeneous term in Eq. (5).

[15] The Strouhal frequency, at which a steady flow hitting a solid obstacle sheds turbulent vortices, will be discussed in Sec. III E.



FIG. 5: Time-lapse pictures of a garden hose self-oscillating. Images by Olivier Doaré (ENSTA) and Emmanuel de Langre (École Polytechnique) [58, 59], used here with the authors' permission.

It has been known to engineers, since the earliest investigations of the subject by F. B. Farquharson[16] at the University of Washington, and by T. von Kármán and L. G. Dunn at Caltech [50], that the catastrophic oscillation of the bridge was a *flow-induced instability*, meaning that it resulted from the coupling between the solid's motion and the dynamics of the fluid driving the motion. This is quite unlike a forced resonator, for which there would be no back-reaction of the oscillator (the bridge) on the forcing term (the wind). This distinction, as it applies to the Tacoma Narrows bridge collapse, is lucidly made by Billah and Scanlan in [51], and also by Green and Unruh in [33].

Like the actual fluid mechanics responsible for the vibration of the vocal chords, the dynamics of the oscillation seen in Fig. 4 is rather complicated and involves turbulent flows; Païdoussis, Price, and de Langre give a thorough and modern review of this subject in [52]. For our purposes, it will suffice to note that the "galloping" resulted from a feedback between the oscillation of the bridge and the formation of turbulent vortices in the surrounding airflow. Those vortices, in turn, drove the the bridge's motion, causing a negative damping of small oscillations, like that of Eq. (4).[17]

A more recent case of large and unwanted oscillation of a bridge was the lateral swaying of the London Millennium Footbridge after it opened in 2000. This was also a self-oscillation: as pedestrians attempt to walk straight along a swaying bridge, they move (relative to the bridge) *against* the sway, thus exerting a force on the bridge that is in phase with the velocity of oscillation. Footbridges with low-frequency, sideways modes of vibration, and a sufficiently large ratio of pedestrian load to total mass, are generally susceptible to this instability [54]. The mechanism of the back-reaction of the bridge's oscillation on the sideways motion of the pedestrians has been investigated mathematically by Strogatz et al. [55, 56]

Similar instances of flow-induced self-oscillation include the fluttering of power transmission lines and other thin solid objects in high winds [57] and the vibration of an unsupported garden hose when it runs at full blast, as pictured in Fig. 5 (see [58, 59]). We will also see how self-oscillation explains the operation of the violin and other bowed string musical instruments, wind instruments, the human heart, and motors. Notice that in these cases the medium must supply enough energy to sustain the oscillation, but no external rate needs to be tuned in order to produce a large periodic motion: *the oscillator itself sets the frequency and phase with which it is driven.* For instance, when playing a note on the violin, there is some minimum velocity at which the bow must be drawn, but drawing it faster only makes the same note louder. For the hose of Fig. 5, self-oscillation occurs as long as the velocity of water flow exceeds some threshold [60].

---

[16] In the film footage taken on the day that the bridge fell [48] a man is seen walking away from an abandoned car, pipe in hand, shortly before the bridge collapses under the car. This was Prof. Farquharson, who had come from Seattle that morning to monitor the bridge's oscillation. At the last moment he had attempted to rescue a black spaniel, Tubby, that had been left behind in the car when its owner had fled on foot. The dog, terrified by the violent motion, merely bit Farquharson in the finger and later perished with the bridge [49].

[17] In 1907, Rayleigh had reported a similar case of a tuning fork being driven at its resonant frequency by a steady cross-flow of air, even though the Strouhal frequency of vortex shedding by that flow did not match the fork's resonant frequency. For this he could find "no adequate mechanical explanation" at the time. [53]

Ocean waves are another form of self-oscillation, since they have a well-defined wavelength but are generated by the action of a steady wind.[18] Helmholtz [61] and Kelvin [62] showed that when the relative velocity of two fluids moving in parallel directions exceeds a certain threshold, the surface of separation between them becomes linearly unstable. Lamb reviews this "Kelvin-Helmholtz instability" in [63]. Perturbations of the surface of separation along the normal direction then grow exponentially until limited by nonlinearities, as in the other negatively-damped systems that we have mentioned. This is how the wind generates waves on the surface of a body of water. [64]

D. Active versus passive devices

In the parlance of electronics, a forced resonator is a *passive* device: it merely responds to the external forcing term, the response being maximal when the forcing frequency matches the resonant frequency. A self-oscillator, on the other hand, is an *active* device, connected to a source from which it may draw power in order to amplify small deviations from equilibrium and maintain them in the presence of dissipation. (The issues of power consumption and efficiency in active devices will be treated in detail in Sec. VI.)

Passive devices (such as a mechanical resonator or an electrical transformer) can multiply the amplitude of an oscillation. But only an active device can multiply its *power*, and therefore only an active device can maintain, through feedback, a steady alternating output without an alternating input [65]. Passive devices are, for most purposes, well described by linear differential equations, whereas a practical description of active devices requires taking nonlinearities into account, as it is the nonlinearities that determine the limiting amplitude of the self-oscillation.

In general, active devices can be thought of as involving an *amplification*. For a given input signal $q_{\rm in}$, the amplifier produces an output

$$q_{\rm out} = g \cdot q_{\rm in} \ , \tag{12}$$

where $g > 1$ is called the "gain." The power to generate $q_{\rm out}$ does not come from the signal $q_{\rm in}$, but rather from an external source. An ideal amplifier has a constant g, independent of frequency or amplitude. In practice, amplifiers always fail at large amplitudes and frequencies, causing a distortion of the output relative to the input.

According to Horowitz and Hill,

> devices with power gain [i.e., active devices] are distinguishable by their ability to make oscillators, by feeding some output signal back into the input. [65]

In other words, active devices can be identified by their ability to self-oscillate.

E. Violin versus æolian harp

Helmholtz was the first to study systematically the physics of violin strings and his results are covered in *Tonempfindungen*, his groundbreaking treatise on the scientific theory of music [66]. The key point is that the friction between the bow and the violin string varies with the relative velocity between them. When the relative velocity is zero or small, the friction is large. As the relative velocity increases, the friction decreases. Thus, the frictional force exerted by the bow on the string is modulated in phase with the string's velocity, allowing the bow to do net work over a complete period of the string's oscillation (see Eq. (6)).

When the bow is drawn over a violin string, the amplitude of the vibration grows exponentially until it reaches a limiting, nonlinear "stick-slip" regime. As Helmholtz observed experimentally, in this regime the waveform for the displacement of the violin string is triangular.[19] First, the violin string sticks to the bow and moves at the same velocity at which the bow is being drawn. This is represented in Fig. 6 by the motion between A and B. At B the string unsticks and moves back to equilibrium, which it passes at C. It continues moving with nearly the same velocity until at D it again becomes stuck to the bow. Between A and B the frictional force exerted by the bow on the string is positive and large, while between B and D the frictional force is still positive but small. Figure 6 also

---

[18] I thank John McGreevy for bringing this point to my attention.

[19] Helmholtz measured the waveform of Fig. 6 by applying the bow very precisely at a node of a harmonic and observing the displacement at another node of that same harmonic, so that the string would vibrate appreciably only at the fundamental frequency.



FIG. 6: Waveform for the displacement $q(t)$ of a violin string in the limiting "stick-slip" regime, as first measured by Helmholtz [66]. Between A and B the string moves with the bow, while between B and D it moves against the bow. The dashed curve shows the waveform that results from increasing the bow's velocity. Image adapted from Fig. 22 in [67].



FIG. 7: Illustration of the turbulent vortices generated by a flow of velocity v as it hits a circular obstacle of diameter d, on the left. These form a "Kármán vortex street" [75]. The frequency with which the vortices are shed was experimentally found by Strouhal to obey Eq. (13). This image is by Cesareo de la Rosa Siqueira; an animated version is available at `http://en.wikipedia.org/wiki/File:Vortex-street-animation.gif`.

shows that if the bow is drawn faster, the string plays the same note, but with a greater amplitude. Within certain limits, the amplitude of the vibration is proportional to the speed of the bow.[20]

In an "æolian harp," one or more wires are stretched and their ends attached to an open frame, which is then placed in a location where a strong wind may pass through it. This causes the wires to vibrate and emit audible tones. Strouhal [69] and Rayleigh [70, 71] demonstrated that in an æolian harp the wind does *not* act like a violin bow. For starters, the string's motion is perpendicular to the direction of the wind. Furthermore, the tone produced does *not* depend on the length, density, or tension of the wire (which determine its resonant frequency), but only on the wire's diameter d and the wind speed v. Strouhal found experimentally that the frequency f of the tone produced by the wire was approximately given by

$$f \simeq 0.2 \cdot \frac{v}{d} , \tag{13}$$

the so-called Strouhal frequency of the shedding of turbulent vortices as a steady wind passes around a circular obstacle (see Fig. 7).[21] Evidently, the æolian harp *is* just a forced resonator, in which the frequency of the forcing term is given by Eq. (13). Only when the wind produces an f that happens to be close to the fundamental frequency of the corresponding wire —or one of its harmonics— does the æolian harp ring loudly.

Unfortunately, the conceptual distinction between the æolian harp as a forced resonator and self-oscillating musical instruments like the flute and the flue-pipe organ is not often made clearly in the literature. For instance, in his classic work of scientific popularization, *Science & Music*, Sir James Jeans describes the operation of a flue-pipe organ as a forced resonator driven by the Strouhal vortex-shedding of the air hitting a sharp edge [76]. This cannot be a complete description of its operation, because the Strouhal frequency of Eq. (13) depends on the velocity of the air, which would have to be tuned to the resonant frequency for the corresponding note to be sustained (recall that when the forcing and resonant frequencies are different, a forced resonator with non-zero damping vibrates only transiently at the resonant frequency, before reaching a steady state in which it moves with the forcing frequency; see [46]).

---

[20] The generation of a tone when a moist finger is dragged along the rim of a brandy glass works by the same stick-slip mechanism as the violin. A very similar phenomenon is seen in traditional Tibetan "singing bowls," which ring audibly when a leather-covered mallet is rubbed against the rim; see [68] and references therein.

[21] For a general flow, the number 0.2 in Eq. (13) is replaced by a Maclaurin series in the inverse Reynolds number, $R^{-1} = \nu/(vd)$ (where ν is the fluid's kinematic viscosity). The ratio $fd/v \simeq 0.2 + 4/R + \mathcal{O}(1/R^2)$ is called the "Strouhal number" (see [70, 72, 73]).

Jeans explains that such wind instruments work because there is a back-reaction of the oscillation of the pressure of the air within the pipe upon the Strouhal forcing term, which after some delay causes both of them to move in phase. But this back-reaction, which is essential to the operation of the wind instruments in question, is precisely what makes them self-oscillators, rather than forced resonators. On the details of the operation of flue-pipe organs, see [78, 79].

Note that the vortex shedding of Fig. 7 it itself a self-oscillation, since a regular periodic motion, with frequency f given by Eq. (13), is generated by the steady flow moving past the solid obstacle. The key difference between an æolian harp and a flue-pipe organ is that in the former there is no appreciable back-reaction of the string's vibration on the vortex-shedding, whereas in the organ (just as in the galloping of the Tacoma Narrows Bridge), the oscillation feeds back on the vortex-shedding. In self-oscillating "aeroelastic flutter," including the motion of the bridge in Fig. 4, vortices are shed at the frequency of the fluttering, but the shedding frequency can differ significantly from the value of Eq. (13) because the vortices *are generated by the vibration*, rather than the other way around (see [51, 74]).[22]

F. Parametric resonance

Consider an equation of motion of the form

$$\ddot{q} + \omega^2(t) q = 0 \ , \tag{14}$$

where $\omega^2(t)$ is a periodic function. Even though Eq. (14) ("Hill's equation" [80]) is linear, it is evidently not time-translation invariant, and analytic solutions can be obtained only by approximation. For ω^2 of the form

$$\omega^2(t) = \omega_0^2 \left(1 + a \cos(\gamma t)\right) \ , \tag{15}$$

with $a \ll 1$, small oscillations are seen to grow exponentially in time if the angular frequency γ is close to $2\omega_0/n$, where n is a positive integer. This is the phenomenon of *parametric resonance*, which is strongest for $n = 1$. (Equation 14 with an ω^2 of the form of Eq. (15) is called the "Mathieu equation," after Mathieu's investigations in [81].)

Parametric resonance resembles self-oscillation in that the growth of the amplitude of small oscillations is exponential in time, as long as there is some initial perturbation away from the unstable equilibrium at $q = 0$. On the other hand, as in the case of forced resonance, the equation of motion for parametric resonance has an explicit time-dependence. A parametric resonator requires the tuning of γ in Eq. (15) to $2\omega_0/n$, and it fails altogether for $\gamma \to 0$.

An analysis of the flow of energy into a parametric resonator is instructive and will be useful to our discussion of the efficiency of self-oscillating motors in Sec. VI. As the simplest instance of parametric resonance, consider a mass m hanging from a string of length ℓ_0. Let θ be the angle between the string and the vertical. For small angles, the motion of the pendulum is described by

$$\ddot{\theta} + \frac{g}{\ell_0} \theta = 0 \ , \tag{16}$$

where g is the gravitational acceleration. Suppose that the string is threaded through a hole in a solid plate above the pendulum and that one end of the string is attached to the rim of a wheel with radius $r_0 \ll \ell_0$, turned by a motor, as shown in Fig. 8. When the motor runs, the length ℓ of the string varies with time, giving an equation of motion of the form of Eq. (14).

Why is the pendulum driven most efficiently when this motor turns with *twice* the angular frequency $\omega_0 = \sqrt{g/\ell_0}$ of the pendulum's free oscillation? Note that even though the full oscillation goes as

$$\theta(t) = \theta_0 \cos(\omega_0 t) \tag{17}$$

---

[22] Even Pippard, who was well aware of the theory of self-oscillation, fails in [77] to make a sufficiently clear distinction between the solid driven by the Strouhal vortex shedding without back-reaction on the flow (as in the æolian harp) and aeroelastic self-oscillations driven by feedback of the solid motion on the fluid (as in the galloping of the Tacoma Narrows Bridge).



FIG. 8: A string is attached to a mass m, while the other end is threaded through a hole in a solid plate above and attached to the rim of a small wheel driven by a motor. The turning of the wheel causes a variation of the length ℓ of the pendulum, around an average value ℓ_0. When the wheel moves with angular velocity $2\omega_0$, where $\omega_0 = \sqrt{g/\ell_0}$, the system achieves parametric resonance, causing the amplitude of small oscillations to grow exponentially with time. Image adapted from Fig. 5.10 in [85].

for small angular amplitude θ_0, the *vertical* component of the pendulum's position,

$$y(t) = \ell\left(1 - \cos\left(\theta_0 \cos(\omega_0 t)\right)\right) \simeq \frac{\ell\theta_0^2}{4}\left(1 + \cos(2\omega_0 t)\right) \ , \tag{18}$$

happens, simply by geometry, to move with twice the frequency ω_0 in Eq. (17). The reason why parametric resonance for this system is most efficient when driven with angular frequency $2\omega_0$ is that the motor causes a negative damping of $y(t)$, pulling up when the mass is going up and "pushing" down then the mass is going down.[23]

Note that the horizontal position of the mass, $x(t)$, moves with angular frequency ω_0. A horizontal driving force should therefore have frequency ω_0, as is familiar from the pushing of a playground swing, which corresponds to an ordinary forced resonance. It is amusing to note that Japanese children learn to use playground swings by parametric resonance: they stand up as the swing approaches its equilibrium position, at the bottom of its arc, and crouch as it reaches the top of its arc. This makes the moment of inertia of the swing-child system oscillate with twice the frequency of the swinging and causes a faster, more efficient growth of the swinging than the forced resonance method favored by Western children.[24]

Although parametric resonance is discussed mathematically in many advanced textbooks on classical mechanics (cf. [37–40]),[25] from our point of view the most instructive physical discussion is the one by Pippard in [84]. Because it is not very well known, we give here an analysis —very similar to Pippard's— of the energy flow in a simple pendulum driven by parametric resonance.

In an ordinary pendulum, the tension T of the string must obey

$$T - mg\cos\theta = m\ell\dot{\theta}^2 \ , \tag{19}$$

---

[23] It is, of course, impossible to push on a mass via a string. But if the string slackens as the mass moves radially outward, this is equivalent to pushing it out, from the point of view of energy transfer.

[24] I owe this observation to Take Okui.

[25] Rayleigh treated the subject in [82, 83].

so that, by Eq. (17) and for $\theta_0 \ll 1$,

$$T = mg\left(1 + \frac{\theta_0^2}{4} - \frac{3\theta_0^2}{4}\cos(2\omega_0 t)\right) \ . \tag{20}$$

This tension does no work in an ordinary pendulum because it is perpendicular to the mass's velocity. But when the motor turns with angular velocity $2\omega_0$, it varies the length ℓ of the string, causing an additional velocity

$$\dot{\ell} = 2\omega_0 r_0 \cos(2\omega_0 t) \tag{21}$$

parallel to the tension and in phase with the oscillating part of Eq. (20).[26] The motor therefore delivers an instantaneous power

$$P_{\text{out}} = T\dot{\ell} \tag{22}$$

to the mass. The terms in P_{out} that are linear in $\cos(2\omega_0 t)$ average to zero over a complete period of the motion, but the term quadratic in $\cos(2\omega_0 t)$ gives a total energy input

$$W_{\text{net}} = \frac{3\pi\theta_0^2}{2} mgr_0 > 0 \tag{23}$$

after a full period. Note that the fact that W_{net} is proportional to the *square* of the amplitude θ_0 of the angular oscillation (as opposed to the undamped force resonator, for which W_{net} is linear in the amplitude) explains why the amplitude grows exponentially; see Sec. III B. Eventually θ_0 becomes large enough that the small-angle approximation fails and new terms must be added to Eq. (20); these do not vary in phase with $\cos(2\omega_0 t)$ and therefore reduce the efficiency with which energy is delivered by the motor to the pendulum.

A more detailed mathematical analysis is needed to account for the parametric resonance at frequencies $2\omega_0/n$ for integers $n > 1$; see, e.g., the treatment of the Mathieu equation in [39]. At those lower frequencies, parametric resonance works by a mechanism similar to the entrainment of higher harmonics in non-linear self-oscillators, which will be mentioned in Secs. IV E and V B 3.

IV. FEEDBACK SYSTEMS

A. Clocks

Mechanical and electronic timekeepers are self-oscillators, sparing the user the need to tune an external driving frequency. Pendulum clocks and spring-driven watches, just as much as modern electronic clocks, self-oscillate by using positive feedback: the vibration of the device is amplified —using an external source of power— and fed back to it in order to drive it in phase with the velocity of the oscillation [86, 87]. In other words, clocks are *active devices*, as described in Sec. III D.

This principle may be illustrated by applying feedback to the electric bandpass filter of Fig. 3. Let

$$V_{\text{in}} = gV_{\text{out}} \ , \tag{24}$$

i.e., let us feed back the output, with a gain factor of g. If the terminal V_{out} consumes negligible current (which is possible only if the gain is effected by an active amplifier) it is easy to show that

$$\ddot{V}_{\text{out}} + \frac{1-g}{RC}\dot{V}_{\text{out}} + \frac{1}{LC}V_{\text{out}} = 0 \ . \tag{25}$$

Thus, for $g > 1$ (i.e., for *positive* feedback) the damping term is negative and the circuit will self-oscillate with angular frequency $\omega = 1/\sqrt{LC}$. The limiting amplitude of the oscillation is determined by the nonlinear saturation of the amplifier, which reduces the effective g for large voltages. This is the principle on which all electronic clocks operate [87].[27]

---

[26] Here we have simplified our analysis by imagining that the string is massless and cannot stretch, so that displacing one end causes an instantaneous displacement of the other end, without any additional force. In any case, the variation of the tension T induced by the action of the wheel will make no net contribution to the energy transfer of Eq. (23).

[27] See [88] for a thorough review of how electronic oscillators are implemented in practice.



(a) (b)

FIG. 9: A Pearson-Anson flasher, which charges the capacitor C until it reaches a threshold voltage $V_t < V_0$, whereupon the neon lamp discharges rapidly, producing a flash of light. The circuit diagram is shown in (a), while the resulting waveform $V_{\rm out}(t)$ is shown in (b).

A perplexing philosophical question about time is what *defines* the notion of regularity by which we evaluate physical clocks in order to establish how accurate they are. Why do we time the rotation of the Earth with an atomic clock[28] and not the other way around? It would take us too far afield to pursue this seriously, but I submit that any reasonable answer must depend on the theoretical concept of linear self-oscillation, as represented by Eq. (25) in the limit of unit gain, $g \to 1^+$, when the value of LC can be tied to a quantity that is presumed fixed in our accepted description of the fundamental laws of physics.

B. Relaxation oscillations

The simplest electronic oscillators are RC circuits in which the driving voltage switches between two fixed levels when the output reaches an upper and lower threshold. Conceptually, this is akin to a sandglass, turned over as soon as the upper chamber becomes empty. Such devices are known as "relaxation oscillators," because the output relaxes to a fixed value —with a time constant given by the value of RC— before the driving voltage switches. The switching is done by a "Schmitt trigger," which has $g \gg 1$, but whose output voltage is confined between fixed upper and lower limits [92, 93].

An even simpler relaxation oscillator is the Pearson-Anson flasher, which charges a capacitor until its voltage reaches a threshold, thereupon causing a neon lamp to discharge the capacitor quickly with an accompanying flash of light [94]. This is illustrated in Fig. 9. Relaxation oscillators are useful because of their simplicity, but they are not good for precision timekeeping.[29]

A relaxation oscillator like the one shown in Fig. 9 has no resonant frequency, since $L \to \infty$, implying $\omega \to 0$; the actual period of oscillation depends on the switching at the thresholds, which fix the amplitude. Relaxation oscillators with finite L and $C \to \infty$ are also common: for example, an automobile's turn signal relies on an RL circuit connected to a steady voltage. A bimetallic conducting strip (called a "thermal flasher") is connected in series with L, so that when the current reaches some threshold the strip heats to the point that it bends and opens the circuit. The strip then quickly cools and bends back, closing the circuit and starting the cycle again.

We shall see in Sec. IV C that relaxation oscillations can be understood as a particular regime of self-oscillation. This will require incorporating into the equation of motion the nonlinearity associated with the switching.

---

[28] The second is now defined as "the duration of 9,192,631,770 periods of the radiation corresponding to the transition between the two hyperfine levels of the ground state of the caesium 133 atom" [89]. In practice, this is implemented in atomic clocks by the self-oscillation of a microwave cavity whose resonant frequency (i.e., the analog of the value of $1/\sqrt{LC}$ in Eq. (25)) is adjusted to maximize the rate at which caesium atoms passing through the cavity undergo the hyperfine transition in question [90]. Note that this is *not* an adjustment of the frequency of a driving force to make it match the cavity's resonant frequency: rather, it is the value of the resonant frequency that is adjusted to ensure its constancy (see [91]).

[29] Until the development of practical pendulum clocks by Huygens in the late 17th century [95], all mechanical timekeepers were relaxation oscillators (see [96]). The most sophisticated mechanism of this sort was the "verge and foliot escapement," which became common in Europe in the 14th century [97].



(a) (b)

FIG. 10: (a): Circuit diagram for the electronic van der Pol self-oscillator. To obtain the necessary nonlinear properties of the diode current, a tunnel diode is biased to a point (V_0, I_0) along its characteristic I-V curve where the slope is negative and the concavity $I''(V_0)$ is negligible, as shown schematically in (b). Images adapted from [102].

C. Van der Pol oscillator

In the 1920s, Dutch physicist Balthasar van der Pol and his collaborators developed a model of electrical self-oscillation based on the nonlinear, ordinary differential equation

$$\ddot{V} - \left(\alpha - \beta V^2\right)\dot{V} + \omega^2 V = 0 \ , \tag{26}$$

where α, β, and ω^2 are positive constants [98–100]. This oscillator has a negative damping $-\alpha\dot{V}$ and its amplitude is limited by the nonlinear, positive damping term $\beta V^2 \dot{V}$.[30]

Van der Pol's self-oscillator may be implemented in the laboratory by using a tunnel diode to apply nonlinear feedback to an RLC bandpass.[31] Assuming that a negligible amount of electrical current flows out of the terminal $V_{\rm out}$ in the circuit of Fig. 10(a),

$$C\ddot{V}_{\rm out} + \frac{1}{L}V_{\rm out} = -\dot{I}_{\rm diode} \ . \tag{27}$$

If one can contrive to get

$$I_{\rm diode} = -\frac{\alpha C}{g}V_{\rm in} + \frac{\beta C}{3g^3}V_{\rm in}^3 + {\rm const.} \tag{28}$$

and

$$V_{\rm in} = gV_{\rm out} \ , \tag{29}$$

the equation of motion for $V_{\rm out}$ will have the form of Eq. (26), with $\omega = 1/\sqrt{LC}$.

In practice, implementing Eq. (28) requires biasing the tunnel diode with a voltage source V_0 and a current source I_0, corresponding to an inflection point along the diode's characteristic I-V curve with negative slope, as shown in Fig. 10(b) (see [102]). Meanwhile, Eq. (29) can be enforced by a simple op-amp multiplier or follower [104].

The steady-state amplitude of oscillation for Eq. (26) is

$$V_0 = 2\sqrt{\frac{\alpha}{\beta}} \ . \tag{30}$$

For that fixed amplitude, the average damping vanishes over a period of oscillation, so that the oscillation can be maintained at its natural frequency without net energy either being gained or lost (see [105]). For $\alpha \ll \omega$, small

---

[30] Rayleigh had earlier proposed an equation of the form $\ddot{q} - \alpha\dot{q} + \beta\dot{q}^3/3 + \omega^2 q = 0$ to describe self-oscillators such as clocks, violin strings, and clarinet reeds [86, 101]. Note that Eq. (26) can be obtained from Rayleigh's equation by substituting $V = \dot{q}$ and differentiating.

[31] In van der Pol's original implementation, the active element in the circuit was a triode vacuum tube. Such devices are now largely obsolete, though they are sometimes still used in high-power radio frequency (RF) amplifiers and in some audio amplifiers. For a review of triode circuits with positive feedback, see, e.g., [103].



(a)

(b)

FIG. 11: Numerical solutions to the van der Pol equation $\ddot{V} - 0.2\left(1 - V^2\right)\dot{V} + V = 0$ for initial conditions: (a) $V(0) = 0.1$, $\dot{V}(0) = 0$; and (b) $V(0) = 4$, $\dot{V}(0) = -4$.

oscillations build up to amplitude V_0, while large oscillations decay down to it, as shown respectively by the waveforms of Figs. 11(a) and (b).

On the other hand, for $\alpha \gg \omega$, small displacements grow very quickly, causing them to overshoot V_0, whereupon the nonlinear term $\beta V^2 \dot{V}$ causes the amplitude to decay back down, until it eventually shoots off in the other direction, as shown by the waveform of Fig. 12(a). This produces a cycle of rapid buildup and slower decay that van der Pol identified as a relaxation oscillation [100, 106] (see also [109]). Such an oscillation is periodic but not sinusoidal. The period is not $2\pi/\omega$, but instead is approximately proportional to α/ω^2. As shown in Fig. 12(b), large, energetic oscillations decay down to the same limit cycle to which small oscillations build up.

In electronics, one might be used to thinking of a relaxation oscillation, such as the waveform of Fig. 9(b), as a linear evolution periodically reset by an external intervention. Perhaps the most interesting conceptual feature of the van der Pol equation in the $\alpha \gg \omega$ regime is that it incorporates the nonlinear switching of a relaxation oscillator *into the solution to the equation of motion.*[32] A close-up of this switching if shown in Fig. 12(b). In Sec. V B 1 we shall return to the van der Pol equation and treat in greater detail the nature of its limit cycles.

The term "relaxation oscillation" was coined by van der Pol in [100], though the practical use of relaxation oscillators is very ancient (see, e.g., [108]). Van der Pol chose the name on account of the period of being determined by the relaxation time (RC or L/R for non-resonant linear circuits). Friedländer called the same concept *Kippschwingungen* ("tipping oscillation") [109], a term still used in Germany.

The vortex shedding illustrated in Fig. 7 is a relaxation oscillation of the point of separation of the viscous boundary layer of the flow around the solid obstacle [73]. The fact that it is a relaxation oscillation explains why the frequency depends of the velocity of the flow (see Eq. (13)).

D. The heart is a self-oscillator

Already in the second century CE, Galen noted that

> the heart, removed from the thorax, can be seen to move for a considerable time [...] a definite indication that it does not need the nerves to perform its own function. [110]

In the 15th century, Leonardo da Vinci captured the same observation succinctly and poetically:

> *Del core. Questo si move da sè, e non si ferma, se non eternal mente.* ("As to the heart, it moves itself, and doth never stop, except it be for eternity.") [111]

This corresponds, in a modern language, to the observation that the heartbeat is a self-oscillation.

The heartbeat is controlled by the electric potential in the sino-atrial node (SAN), a bundle of specialized cells that act as the heart's natural pacemaker and are located in the upper part of the right atrium. Van der Pol and his

---

[32] In the parlance of theoretical economics, the van der Pol model "endogenizes" the switching (see [107]).



(a)

(b)

(c)

FIG. 12: Numerical solution to the van der Pol equation $\ddot{V} - 5\left(1 - V^2\right)\dot{V} + V = 0$, for: (a) $V(0) = 0.1$ and $\dot{V}(0) = 0$; and (b) $V(0) = 2.2$ and $\dot{V}(0) = -12$. These show the sequence of buildups and decays that van der Pol identified as a relaxation oscillation [100, 106]. Plot (c) gives a close-up of the waveform (a) as it overshoots $V_0 = 2$ and starts to decay.

collaborator, Johannes van der Mark, developed a model of the SAN electrical potential as a relaxation oscillation [112]. By coupling three relaxation oscillators they succeeded in reproducing many of the features of electrocardiograms for both healthy and diseased hearts. The model of Eq. (26) is still relevant to the theory of the heart's electrophysiology (see, e.g., [113] and references therein).

The form of the SAN potential is shown schematically in Fig. 13. Note that, unlike the waveforms in Fig. 12, the SAN potential is not symmetric: the negative decay phase after the switching at the lower threshold (segment AB in the solid curve in Fig. 13) is slower than the positive decay phase after the switching at the upper threshold (segment CD in the same curve).[33] We will see how to accommodate this asymmetry mathematically in Sec. V B 2.

The rate of the heartbeat is now believed to be regulated primarily by the strength of the "funny current" I_f (also called, rather less bizarrely, the "hyperpolarization-activated" or "pacemaker" current) [115, 116]. This I_f is given by an inward flow of positively-charged ions across the cellular membrane. It occurs during the negative decay phase (segment AB in Fig. 13) of the relaxation oscillation of the membrane potential: this phase is known in cardiology as "pacemaker" or "diastolic" depolarization.[34]

The increase in I_f caused by a greater concentration of adrenaline is believed to account for the speeding up of the heartbeat when adrenaline is delivered to the SAN [117]. The dotted curve in Fig. 13 illustrates how this speeding up appears in the waveform for the SAN potential. Conversely, I_f may be suppressed, and the heartbeat therefore

---

[33] Throughout this article, we use the word "threshold" to refer to the level at which nonlinearity causes a rapid switching in a relaxation oscillation. This is the standard usage in electronics (see, e.g., [93]). In electrophysiology the word is usually reserved for a different concept: the level to which the cellular membrane must be depolarized to trigger the firing of an action potential (see, e.g., [114]). In Fig. 13 the "thresholds" in the electronic sense are the levels at A and C, while the "threshold" in the electrophysiological sense is the level at B.

[34] Experiments show that the activation of I_f is fairly gradual, making the switching at A less sharp than shown in Fig. 13 (see [115, 116]). We avoid this complication in the interest of conceptual clarity.



FIG. 13: The solid curve schematically represents the waveform for the heart's SAN potential. The potential switches nonlinearly at A and C. This switching is followed by slow "decay" phases (corresponding to segments AB and CD). The rest of the waveform is composed of rapid "buildup" phases. The dotted curve shows the speeding up of the negative decay phase that results from the delivery of adrenaline to the SAN. Image adapted from [115].

slowed down, by the use of drugs such as ivabradine [116].

A generalization of van der Pol's equation was proposed by FitzHugh [118] as a general model of the oscillation of the membrane potential of excitable cells (neurons and muscle fibers). Nagumo et al. then implemented FitzHugh's equations as an electrical circuit with a tunnel diode [119].[35] For a brief review of this model and its applications, see [120]. See [121] for a thorough treatment of the uses of the FitzHugh-Nagumo model in modern neuroscience. We will characterize this model in more detail in Sec. V B 4.

E. Entrainment

Two or more coupled sinusoidal self-oscillators with different ω's will end up oscillating synchronously, as long as the coupling is sufficient to overcome the difference of the ω's [122]. This "entrainment" of self-oscillators (also called frequency, phase, or mode locking) was first reported by Huygens in 1665 for a pair of adjacent pendulum clocks mounted on the same vertical support [123]. The same phenomenon was investigated experimentally by Lord Rayleigh in the early 20th century, using a pair of weakly coupled "fork interrupters" (see Sec. II E) with slightly different resonant frequencies [53].

Entrainment is possible because the frequency of a nonlinear vibration may be adjusted by varying its amplitude (we shall have more to say on this point in Sec. V B 3). The entrainment of self-oscillators is discussed in modern mathematical terms in [105, 124]. We have already mentioned, at the end of Sec. III E, how entrainment is important to the operation of wind instruments without reeds, such as flue-pipe organs and flutes.

Entrainment can also cause an oscillator to move with an integer multiple (a "harmonic") of the frequency of the other. This simply reflects the fact that the response of a nonlinear oscillator in general produces harmonics (see [125]). Self-oscillating musical instruments —like pipe organs, clarinets, or the human voice— maintain *only* harmonic overtones [126].[36] Higher, non-harmonic modes of the free oscillator are usually either not excited (as in the case of a bottle, which rings at an almost pure frequency when air is blown across the mouth) or entrained so that they become harmonic (as in pipe organs) [128].[37] Entrainment also explains why vowel sounds in human speech are relatively easy to identify and produce, since they correspond to timbres given by a few harmonics (called, in this context, "formants") produced by the vibration of air in the mouth and nasal cavities [129, 130].[38]

---

[35] FitzHugh called it the "Bonhoeffer-van der Pol model" [118] which was also the name then used by Nagumo et al. [119], but it is universally known today as "FitzHugh-Nagumo."

[36] Musical instruments that are not self-oscillators are played either by striking or plucking. Of these, string instruments have —to a good approximation— only harmonic overtones because the ends of the string are fixed and must therefore be nodes of any standing wave (see [127]). Other percussion instruments (e.g., bells, xylophones, drums, cymbals, etc.) give some non-harmonic overtones. The more pronounced those overtones are, the less clear the pitch is.

[37] There do exist certain acoustic self-oscillators, like the air horn and the vuvuzela, in which the higher overtones are not entrained, giving noisy, unmusical sounds.

Relaxation oscillators —whose period is not governed by a resonant frequency— are easier to entrain than sinusoidal oscillators. They also exhibit a unique variant of entrainment, in that they can be locked into a *subharmonic* of the driving frequency. This phenomenon was discovered by van der Pol and van der Mark, who called it "frequency demultiplication" [133]. Relaxation oscillators can also, in some circumstances, be weakly entrained at a rational fraction of the driving frequency [124], or even at an irrational multiple (this last phenomenon, called *quasiperiodicity*, will be relevant to the discussion in Sec. V B 3).

The entrainment of relaxation oscillators is immensely important in theoretical biology. It explains, for instance, why all the potentials of the individual cells in the heart's SAN oscillate in unison, how thousands of fireflies can flash synchronously, and how the daily rhythm that governs the human body is established: see [134] and references therein.

Van der Pol also pointed out in [106] the similarity between the coupling of two of his oscillators (a problem he had first treated in [135]) and the system of nonlinear equations proposed by Lotka [136] and Volterra [137] as a model of predator-prey populations; see also [105, 138–141]. For recent popular discussions of the role of entrainment in the determination of biological rhythms and other phenomena, see [142, 143]. For a thorough mathematical treatment of entrainment and its modern applications, see [144].

F. Chaos

Another interesting feature of Eq. (26) in the relaxation regime ($\alpha \gg \omega$) is that if a forcing term $F_0 \cos(\omega_d t)$ is added to the right-hand side, then the solutions may, for certain values of α, be chaotic [145–148]. That is, solutions may show sensitive dependence on initial conditions, making the precise behavior of the oscillator effectively unpredictable, even though it is governed by a deterministic equation.

Van der Pol and van der Mark, were probably the first to observe the onset of chaos in a simple nonlinear system [133], though they did not fully appreciate its significance at the time. Edward Lorenz's famous work on the "Lorenz attractor" [149], which largely inaugurated modern chaos theory, appeared more than thirty years later.

In Sec. V B 3 we shall discuss entrainment and chaos of self-oscillators again. First, however, we will introduce mathematical tools to characterize them more precisely. In the process, the close connection between the study of self-oscillation and control theory will become evident.

V. CONTROL THEORY

A. General linear systems

Let an N-dimensional system be in equilibrium for $\mathbf{q} = 0$. For small perturbations, the equation of motion may usually be approximated by the linear relation

$$\mathsf{M}\ddot{\mathbf{q}} + \mathsf{C}\dot{\mathbf{q}} + \mathsf{K}\mathbf{q} = 0 \ , \tag{31}$$

where M, C, and K are real-valued, constant $N \times N$ matrices describing, respectively, the masses (or generalized inertias), dampings, and elasticities. By linearity and time-translation invariance, the corresponding motion may be expressed as

$$\mathbf{q}(t) = \mathrm{Re}\left(\sum_{i=1}^{N} w_i e^{\alpha_i t} \mathbf{A}_i \right) \ . \tag{32}$$

The complex numbers α_i are the roots of the $2N$th-degree polynomial

$$\det\left(\alpha^2 \mathsf{M} + \alpha \mathsf{C} + \mathsf{K}\right) \ . \tag{33}$$

---

[38] The earliest work on understanding the production of vowel sounds was by the same Robert Willis mentioned in Sec. II D; see [131]. Rayleigh quotes Willis at length in [129], describing his work as "remarkable" and as leaving "little to be effected by his successors," though Helmholtz and other German scientists who investigated the problem in the mid-19th century were unaware of it. Even more unfortunately, Rayleigh's point about the entrainment of the formants was ignored by many acousticians in the 20th century. The resulting confusion is discussed in [132].

The corresponding time-independent vectors $\mathbf{A}_i$ may be found by solving for

$$\left(\alpha_i^2 \mathsf{M} + \alpha_i \mathsf{C} + \mathsf{K}\right) \mathbf{A}_i = 0 \tag{34}$$

and are called the "normal modes." The complex weights w_i in Eq. (32) are determined by the initial conditions.[39]

If α_i is a root of Eq. (33) then its conjugate α_i^* will be a root as well (the physical reason for this is that the imaginary part of α_i corresponds to a periodic motion, which will appear reversed after time-translating by the corresponding half-period). When $\mathsf{C} = 0$, conjugate α_i's correspond to the same normal mode $\mathbf{A}_i$, which can be chosen to be real-valued [150]. Otherwise, complex-conjugating Eq. (34) tells us that if $\alpha_j = \alpha_i^*$ then $\mathbf{A}_j = \mathbf{A}_i^*$.

Whenever the real part of one of the α_i's is positive, the amplitude of the corresponding mode grows exponentially with time. This means that the system can self-oscillate in that mode.

Thomson (the future Lord Kelvin) and Tait were probably the first to draw attention to the signs of the real parts of the roots of Eq. (33). In the first edition of their *Treatise on Natural Philosophy*, published in 1867, they noted that a root with a positive real part would correspond to "a motion returning again and again with continually increasing energy through the configuration of equilibrium," which they dismissed this as unphysical perpetual motion [151].

1. *Stability criterion*

Maxwell was the first to study the stability of mechanical systems by examining the conditions for the real parts of all the roots to be non-positive. His interest in this question grew out of the practical concern of understanding the possible instabilities of mechanical systems in which the rate of operation of a machine is controlled by a "governor." His 1868 paper on the subject, "On Governors" [152], is now commonly cited as a founding document of modern control theory.[40]

The general stability criterion for linear systems was worked out by Edward Routh in 1877 [156] and, independently, by Adolf Hurwitz in 1895 [157]. For a single degree of freedom with a second-order equation of motion, the Routh-Hurwitz criterion simply states that a linear system is stable if the elastic and the damping term are both non-negative. For more complicated linear systems, the criterion is expressed in terms of the non-negativity of a series of determinants built from the coefficients in the polynomial in Eq. (33). Bateman reviews the history and the mathematics of this problem in [35]. In the physics literature, this subject is discussed by Rayleigh in [158] and, more modernly, by Pippard in [159].

A consequence of the Routh-Hurwitz stability criterion is that a linear system cannot self-oscillate if the matrices M, C, and K in Eq. (31) are all symmetric (i.e., $\mathsf{M}^{\mathrm{T}} = \mathsf{M}$, etc., where the superscript T indicates matrix transposition), unless C has negative eigenvalues.

To prove this, let us define bilinear forms

$$\begin{aligned} T(\mathbf{v}, \mathbf{u}) &\equiv \mathbf{v}^{\mathrm{T}} \mathsf{M} \mathbf{u} \\ F(\mathbf{v}, \mathbf{u}) &\equiv \mathbf{v}^{\mathrm{T}} \mathsf{C} \mathbf{u} \\ V(\mathbf{v}, \mathbf{u}) &\equiv \mathbf{v}^{\mathrm{T}} \mathsf{K} \mathbf{u} \; . \end{aligned} \tag{35}$$

By Eq. (34), for any pair of normal modes $\mathbf{A}_{i,j}$,

$$\begin{aligned} \alpha_i^2 T(\mathbf{A}_j, \mathbf{A}_i) + \alpha_i F(\mathbf{A}_j, \mathbf{A}_i) + V(\mathbf{A}_j, \mathbf{A}_i) = 0 \\ \alpha_j^2 T(\mathbf{A}_i, \mathbf{A}_j) + \alpha_j F(\mathbf{A}_i, \mathbf{A}_j) + V(\mathbf{A}_i, \mathbf{A}_j) = 0 \; . \end{aligned} \tag{36}$$

For symmetric M, C, and K, the bilinear forms of Eq. (35) are also symmetric (i.e., $T(\mathbf{v}, \mathbf{u}) = T(\mathbf{u}, \mathbf{v})$, etc.) and therefore, by Eq. (36), $\alpha_{i,j}$ are the two roots of the *same* quadratic polynomial, so that

$$\alpha_i + \alpha_j = -\frac{F(\mathbf{A}_j, \mathbf{A}_i)}{T(\mathbf{A}_j, \mathbf{A}_i)} \; . \tag{37}$$

---

[39] In the modern theoretical physics literature, it is conventional to write $-i\omega$ instead of α (see, e.g., [46]).

[40] Huygens had proposed a centrifugal governor for clocks in [153]. His design was later adapted for use in windmills and water wheels (see [35]), but the interest of engineers and scientists in mechanical governors and their stability was sparked primarily by the work of James Watt, who in 1788 introduced a centrifugal governor into his steam engine design [154]. Mathematician Norbert Wiener coined the term *cybernetics* after Maxwell's 1868 paper: ϰυβεϱνήτης means "steersman" in ancient Greek and is the source of the English word "governor" [155].

As explained in the previous section, we may always choose $\alpha_j = \alpha_i^*$, $\mathbf{A}_j = \mathbf{A}_i^*$. Let $\mathbf{A}_i = \mathbf{a}_i + i\mathbf{b}_i$, for real-valued vectors $\mathbf{a}_i, \mathbf{b}_i$. The symmetry of the bilinear forms implies that

$$2\mathrm{Re}\,(\alpha_i) = -\frac{F(\mathbf{A}_i^*, \mathbf{A}_i)}{T(\mathbf{A}_i^*, \mathbf{A}_i)} = -\frac{F(\mathbf{a}_i, \mathbf{a}_i) + F(\mathbf{b}_i, \mathbf{b}_i)}{T(\mathbf{a}_i, \mathbf{a}_i) + T(\mathbf{b}_i, \mathbf{b}_i)} \; . \tag{38}$$

By the positivity of the kinetic energy, $T(\mathbf{v}, \mathbf{v}) > 0$ for any real-valued $\mathbf{v}$. It is easy to show that the minimum value of $F(\mathbf{v}, \mathbf{v})$ for unit $\mathbf{v}$ is given by the smallest eigenvalue of C [160].

By Eq. (38), a symmetric linear system can therefore only self-oscillate if C has a negative eigenvalue, which is not normally the case in mechanical systems.[41] For instance, M. Stone worked out in detail the conditions of instability on a generator-governor system and stressed that the possibility of self-oscillation depends on the asymmetry of the matrices

$$\mathsf{C} = \begin{pmatrix} c_1 & 0 \\ \gamma & c_2 \end{pmatrix} ; \quad \mathsf{K} = \begin{pmatrix} k_1 & -\kappa \\ 0 & k_2 \end{pmatrix} \; , \tag{39}$$

where $c_{1,2}$, $k_{1,2}$, γ, and κ are all positive [161, 162]. Stone also simulated such asymmetric linear systems using electrical circuits with active components [161].

2. *Gyroscopic systems*

Note that asymmetric couplings in Eq. (31) cannot be obtained directly from a time-independent Lagrangian. Such asymmetry is possible only if $\mathbf{q}$ describes perturbations about a time-dependent state (e.g., about the steady rotation of the generator considered by Stone in [161]). Asymmetric systems can self-oscillate by absorbing energy via the underlying motion at $\mathbf{q} = 0$.

A way of obtaining an anti-symmetric contribution to C is to eliminate a cyclic variable with non-zero momentum. As a simple instance of this, consider the case of the heavy symmetric top. Its motion can be described, in terms of the usual Euler angles (θ, ϕ, ψ), by the Lagrangian

$$L = \frac{I_1}{2}\left(\dot\theta^2 + \dot\phi^2 \sin^2\theta\right) + \frac{I_3}{2}\left(\dot\psi + \dot\phi\cos\theta\right)^2 - mg\ell\cos\theta \; , \tag{40}$$

where $I_{1,3}$ are moments of inertia, m the mass of the top, g the gravitational acceleration, and ℓ the distance from the top's point of contact with the ground to its center of mass. The cyclic variable ψ is associated with a conserved momentum

$$\frac{\partial L}{\partial \dot\psi} = I_3\left(\dot\psi + \dot\phi\cos\theta\right) = b \; . \tag{41}$$

By Legendre-transforming in ψ, we obtain the reduced Lagrangian (or "Routhian")

$$R = L - b\dot\psi = \frac{I_1}{2}\left(\dot\theta^2 + \dot\phi^2\sin^2\theta\right) + b\dot\phi\cos\theta - mg\ell\cos\theta - \frac{b^2}{2I_3^2} \; . \tag{42}$$

Suppose that the top starts out spinning vertically ($\theta = 0$). Changing variables to

$$\xi \equiv \sin\theta\cos\phi \; , \quad \eta \equiv \sin\theta\sin\phi \; , \tag{43}$$

and linearizing, we obtain, up to total derivatives

$$R = \frac{I_1}{2}\left(\dot\xi^2 + \dot\eta^2\right) + \frac{mg\ell}{2}\left(\xi^2 + \eta^2\right) - \frac{b}{2}\left(\xi\dot\eta - \eta\dot\xi\right) \; . \tag{44}$$

Thus, eliminating ψ introduced terms of the form

$$\gamma_{ij} q_i \dot q_j \; , \text{ with } \gamma_{ij} \neq \gamma_{ji} \tag{45}$$

---

[41] Evidently, an undamped or positively damped linear system will be unstable if K in Eq. (31) has negative eigenvalues. In that case, the corresponding roots of Eq. (33) are real-valued and the exponentially-growing solutions are not oscillatory.

into the effective Lagrangian for linear perturbations about the motion with $\theta = 0$ and $b^2 > 0$. Such terms are called "gyroscopic" and make an antisymmetric contribution to the damping matrix C. Whittaker describes the corresponding theory of vibrations about steady motion in [164].[42]

The resulting equations of motion for small tilt are

$$\left\{ \begin{array}{l} I_1 \ddot{\xi} + b\dot{\eta} - mg\ell\xi = 0 \\ I_1 \ddot{\eta} - b\dot{\xi} - mg\ell\eta = 0 \end{array} \right. . \tag{46}$$

The determinant of Eq. (33) therefore has roots

$$\pm\, i\alpha = \frac{1}{2I_1}\left(b \pm \sqrt{b^2 - 4I_1 mg\ell} \right) . \tag{47}$$

Thus, if the top spins rapidly ($b^2 > 4I_1 mg\ell$), the vertical axis is stable and the top "sleeps." For $b^2 < 4I_1 mg\ell$, the axis goes into an exponentially-increasing oscillation about the vertical, until non-linearities limit the amplitude, or the top falls down. For the nonlinear dynamics of the frictionless top see, e.g., [167].

The self-oscillation of the tilt is called *nutation* and is powered by the top's gravitational potential $mg\ell$. This non-periodic energy may be transformed into nutation because of the top's spinning, but the kinetic energy $b^2/2I_3$ associated with that spinning is conserved (unless friction is taken into account) and does not power the self-oscillation.

B. Limit cycles

Linear stability analysis determines whether small perturbation about equilibrium will decay away or grow exponentially with time. But physical oscillations cannot grow forever. In order to understand the *limiting* oscillatory regime of unstable systems it is necessary to take nonlinearities into account, as we shall do in this section for the simplest cases.[43]

Consider an equation of motion of the form

$$\ddot{x} + f(x)\dot{x} + g(x) = 0 . \tag{48}$$

It will be convenient to define a new variable $y \equiv \dot{x} + F(x)$, with $dF/dx = f(x)$, so that Eq. (48) may be re-expressed as a system of two first-order differential equations

$$\left\{ \begin{array}{l} \dot{x} = y - F(x) \\ \dot{y} = -g(x) \end{array} \right. . \tag{49}$$

This is the Liénard transformation [168], which is useful for understanding the limit cycles of self-oscillators. It is a variation of the phase space method pioneered by Poincaré for the study of nonlinear differential equations [169]; see also [170]. It may also be used to show rigorously that the van der Pol oscillator always has a unique limit cycle to which all solutions tend, regardless of initial conditions (see [171]).

The vertical isocline curve, defined by

$$\frac{dy}{dx} = \frac{\dot{y}}{\dot{x}} = \infty , \tag{50}$$

is given, for the system described by Eq. (49), by

$$y = F(x) . \tag{51}$$

Note that, for the circuit of Fig. 10, the function F corresponds to the characteristic I-V curve of the diode, with the inflection point (V_0, I_0) displaced to the origin.

---

[42] See also [165]. Older sources label terms of the form of Eq. (45) as "gyrostatic," following the usage introduced by Kelvin and Tait in [166].

[43] This section is the only one whose contents may be found in somewhat similar form in standard physics textbooks (cf. [41–43]). But the points that we wish to emphasize and to use in subsequent sections are enough unlike the ones covered in those texts that we have judged it advisable to review the subject here in some detail.



(a) (b)

FIG. 14: Solutions to the van der Pol equation $\ddot{x} - \alpha\left(1 - x^2\right)\dot{x} + x = 0$, for $\alpha = 0.2$, represented in the Liénard plane defined by the transformation of Eq. (53), for initial conditions: (a) $x(0) = 0.1$, $y(0) = -0.02$ (i.e., $\dot{x}(0) = 0$); and (b) $x(0) = 4$, $y(0) = -0.53$ (i.e., $\dot{x}(0) = -4$). The dashed blue line is the vertical isocline $dy/dx = \infty$.

1. Van der Pol's equation

Let us consider, in particular, the van der Pol oscillator of Eq. (26). For mathematical convenience, we rescale by ω to work with dimensionless quantities ($t \to t\omega$, $\alpha \to \alpha/\omega$, and $x \equiv V\sqrt{\beta/\alpha}$) so that the equation becomes

$$\ddot{x} - \alpha\left(1 - x^2\right)\dot{x} + x = 0 \ . \tag{52}$$

By Eq. (49), for this equation of motion the Liénard transformation gives

$$\begin{cases} \dot{x} = y + \alpha\left(x - x^3/3\right) \\ \dot{y} = -x \end{cases} . \tag{53}$$

The rate of change of the radius r of the trajectory in the Liénard plane is

$$\dot{r} = \frac{d}{dt}\sqrt{x^2 + y^2} = \frac{x\dot{x} + y\dot{y}}{r} \ . \tag{54}$$

Using first-order perturbation theory in $\alpha \ll 1$ and averaging over a complete period of the unperturbed system, we obtain that

$$\langle \dot{r} \rangle = \frac{\alpha r}{8}\left(4 - r^2\right) \ , \tag{55}$$

which proves that for $\alpha \ll 1$ the steady-state amplitude is $r = 2$ (see Eq. (30)). Note that Eq. (55) also establishes that for small α this limit cycle is stable and that all trajectories tend towards it.

Figures 14(a) and (b) show the Liénard trajectories corresponding to the solutions plotted in Figs. 11(a) and (b), respectively. Shown along with the trajectories is the vertical isocline curve $y = \alpha(-x + x^3/3)$.

Figure 14(a) illustrates how small oscillations spiral out towards $r = 2$, while Fig. 14(b) illustrates how large oscillations spiral in to that same limiting radius. In either case the system approaches a nearly circular trajectory, corresponding to an approximately sinusoidal limit cycle for $x(t)$.

For $\alpha \gg 1$, it is convenient to rescale $y \to \alpha y$, so that Eq. (53) becomes

$$\begin{cases} \dot{x} = \alpha\left(y + x - x^3/3\right) \\ \dot{y} = -x/\alpha \end{cases} . \tag{56}$$

For most values of x and y, we have that $|\dot{x}| \gg |\dot{y}|$, so that the flow is almost horizontal. Only for $\left|y - x + x^3/3\right| \sim \mathcal{O}(|x|/\alpha^2)$ (i.e., very close to the vertical isocline) are $|\dot{x}|$ and $|\dot{y}|$ of the same order.

For $\alpha = 5$, the Liénard trajectory is shown in Fig. 15(a): The system starts at a point A, given by $x(0) = 0.1$ and $y(0) = -0.1 + 0.1^3/3 \simeq -0.1$ (i.e., $\dot{x}(0) = 0$). It soon develops a large negative $\dot{x}$ and shoots off almost



(a) (b)

(c)

FIG. 15: Solutions to the van der Pol equation $\ddot{x} - \alpha\left(1 - x^2\right)\dot{x} + x = 0$, for $\alpha = 5$, represented in the Liénard plane, defined by the transformation of Eq. (56), for initial conditions: (a) $x(0) = 0.1$, $y(0) = -0.1$ (i.e., $\dot{x}(0) = 0$); and (b) $x(0) = 2.2$, $y(0) = -1.05$ (i.e., $\dot{x}(0) = -12$). The vertical isocline $y = -x + x^3/3$ is indicated by the dashed blue curve. The shaded region around it corresponds to values of (x, y) for which $|\dot{x}|$ and $|\dot{y}|$ are of similar order. Plot (c) is a close-up of (a) around the maximum of the oscillation, where the Liénard trajectory crosses the vertical isocline.

horizontally until it crosses the vertical isocline at point B. The trajectory then approximately follows that isocline curve ($y = -x + x^3/3$) for a while, but the isocline has a maximum in y at $x = -1$, whereas $\dot{y}$ in Eq. (56) cannot change sign while $x < 0$. At C the system therefore re-enters the region of rapid horizontal flow and shoots off in the positive x direction, until at D it crosses the vertical isocline on the $x > 0$ side. The system will continue in a limit cycle $DEFC$: this corresponds to the succession of buildups and decays of the waveform that we had plotted in Fig. 12(a).

Figure 15(b) shows the trajectory of the same dynamical system, but now starting at $x(0) = 2.2$ and $y(0) = -12/5 - 2.2 + 2.2^3/3 \simeq -1.05$ (i.e., $\dot{x}(0) = -12$). This corresponds to the waveform that we had plotted in Fig. 12(b). The switching in Fig. 12(c) is seen here as the crossing of the vertical isocline, shown in close-up in Fig. 15(c).

We can now justify the result, quoted in Sec. IV C, that for the van der Pol equation Eq. (26) with $\alpha \ll \omega$ the period of the relaxation oscillation is approximately proportional to α/ω^2. The reason is that the Liénard trajectory for Eq. (56) spends most of its time near the vertical isocline (corresponding to what we have called the "decay" phases of the oscillation, represented by segments DE and FC in Fig. 15(a)), where $|\dot{x}|$ and $|\dot{y}|$ are $\mathcal{O}(1/\alpha)$. The length of one of those segments of the trajectory is $\mathcal{O}(1)$. In units in which $\omega = 1$, the time that it takes the system of execute this part of the trajectory is therefore $\sim \alpha$.

As $\alpha \to \infty$ the region around the vertical isocline where the trajectory is not horizontal shrinks to zero width. Therefore the limit cycle must be composed of two straight horizontal segments (the infinitely fast buildups, indicated by segments CD and EF in Fig. 16(a)) and two segments that run infinitesimally close to the vertical isocline between its local extrema at $y = \pm 2/3$ (i.e., the decays, which determine the period and are indicated in Fig. 16(a) by segments DE and FC). The overshooting of the thresholds $x = \pm 2$ (around D and F) thus shrinks to zero.

Figure 16(b) gives the waveform for y, which shows the steady decays interrupted by discontinuous switching, familiar from RC relaxation oscillators in electronics (see Sec. IV B). Note that, if the variable x is identified by the voltage $V_{\rm out}$ in Fig. 10(a) then, by Eq. (56), y is proportional to the current through the inductor. The behavior of y



(a)

(b)

FIG. 16: (a) Liénard trajectory for the equation $\ddot{x} - \alpha\left(1 - x^2\right)\dot{x} + x = 0$, for $x(0) = 0.1$, $y(0) = -0.1$ (i.e., $\dot{x}(0) = 0$), as $\alpha \to \infty$. In the limit cycle $DEFC$, the segments EF and CD have constant $y = \pm 2/3$ respectively, while segments DE and FC follow the vertical isocline curve, $y = -x + x^3/3$, indicated by the dashed blue curve. Plot (b) shows the value of $y \equiv \dot{x}/\alpha - x + x^3/3$, as a function of $t' \equiv t/\alpha$.

is therefore that of a simple RL relaxation oscillation in which the capacitance has become negligible and the resonant frequency has therefore effectively vanished. (This is similar to the "thermal flasher" mentioned in Sec. IV B.)

The period of the relaxation oscillation in the $\alpha \to \infty$ limit can be easily calculated by using Eq. (56), which gives

$$dt = \frac{dy}{\dot{y}} = -\alpha \frac{\left(\frac{dy}{dx}\right) dx}{x} \; . \tag{57}$$

For the segments DE and FC of the limit cycle in Fig. 16(a), $dy/dx = -1 + x^2$, while for segments EF and CD $dy/dx = 0$. The corresponding period is therefore

$$\tau = 2\alpha \int_2^1 dx \, \frac{1 - x^2}{x} = \alpha\left(3 - 2\log 2\right) \simeq 1.6\alpha \; , \tag{58}$$

(in units in which the resonant frequency ω is 1). Note that Eq. (58) implies that as α (the coefficient of negative damping) increases, the period τ of the oscillation *grows*, which might appear counterintuitive at first. A larger α speeds up the buildup phases (CD and EF in Fig. 16(a)) but these are already very brief in the relaxation regime. Meanwhile, the decay phases (DE and FC) become longer if α is increased.

In general, self-oscillators give a regular output *robustly*: they approach the same limit cycle regardless of initial conditions and transient perturbations. It is this, above all else, which accounts for their technological value, such as their use as motors and clocks.

2. *Asymmetric oscillations*

Relaxation oscillations in nature are often asymmetric: for instance, the heart's SAN potential spends more time near its lower threshold than near its upper one, as discussed in Sec. IV D. We can accommodate this asymmetry by adding a linear term to $f(x)$ in Eq. (48). Figure 17 shows the waveform and Liénard trajectory for such a system. The asymmetry reflects the displacement of the vertical isocline in the positive x direction. Since $\dot{y} \propto x$ (see Eq. (56)), the non-horizontal part of the Liénard trajectory is faster just after the switching at the upper threshold (when $|x|$ is large) than just after the switching at the lower threshold (when $|x|$ is small). In Fig. 17(b), these are segments DE and FC respectively.

So far we have only considered cases in which the function $F(x)$ in Eq. (49) is symmetric about its inflection point. In the corresponding oscillators, the mechanical energy moves up and down twice during each period (for instance, in Fig. 16(a) it spikes up sharply during the jumps at CD and EF). There is a class of self-oscillators in which $F(x)$ is asymmetric and the mechanical energy goes up and down only once during each period. These are called "two-stroke" oscillations and were first described in detail in [172].



(a) (b)

FIG. 17: Solution to $\ddot{x} - 5\left(1 + 2x - x^2\right)\dot{x} + x = 0$, for $x(0) = 0.1$, $\dot{x}(0) = 0$, represented: (a) as a function of time and (b) in the Liénard plane defined by Eq. (49), with the rescaling $y \to 5y$.



(a) (b)

FIG. 18: Solution to $\ddot{x} + 0.75\left(\exp(x) - 2\right)\dot{x} + x = 0$, for $x(0) = 0.1$, $\dot{x}(0) = 0$, represented: (a) as a function of time and (b) in the Liénard plane defined by Eq. (49). The vertical isocline $y = 0.75(\exp(x) - 2x)$ is shown as the dashed blue curve.

An instance of a two-stroke oscillation is given by the limit cycle of Eq. (49) with $g(x) = x$ and a characteristic function

$$F(x) = \rho\left(e^x - 2x\right) , \tag{59}$$

for $0 < \rho < 1$. The nonlinear positive damping $\exp(x)\dot{x}$ is only important for $x > 0$, while for $x < 0$ the oscillation is almost linear. For $\rho \ll 1$, the limit cycle is sinusoidal, but for $\rho \gtrsim 0.4$, the asymmetry becomes clear: the oscillator undergoes rapid switching only once per period, at a positive threshold, and this is the only time when the oscillator's energy peaks. Figure 18 illustrates this behavior for $\rho = 0.75$.

3. Forced self-oscillators

The Liénard transformation can also be applied to forced oscillations obeying an inhomogeneous equation of the form

$$\ddot{x} + f(x)\dot{x} + g(x) = \phi(t) , \tag{60}$$

giving

$$\begin{cases} \dot{x} = y - F(x) \\ \dot{y} = -g(x) + \phi(t) \end{cases} , \tag{61}$$



(a)

(b)

FIG. 19: Solution to $\ddot{x} - 0.25\left(1 - x^2\right)\dot{x} + x = 2\cos(1.4t)$, for $x(0) = 0.1$, $\dot{x}(0) = 0$, represented: (a) as a function of time (in red), with the forcing term $2\cos(1.4t)$ shown as a dashed blue curve, and (b) in the Liénard plane defined by Eq. (61), with the vertical isocline indicated by the dashed blue curve. This solution shows entrainment between the oscillator (with a resonant angular frequency of 1) and the forcing term (with angular frequency of 1.4).

where $dF/dx = f(x)$.

As an illustration of the entrainment behavior discussed in Sec. IV E, consider

$$\ddot{x} - \alpha\left(1 - x^2\right)\dot{x} + x = F_0\cos\left(\omega_d t\right) \tag{62}$$

for $\alpha = 0.25$, $\omega_d = 1.4$, and $F_0 = 2$. The plots in Fig. 19 show that the oscillation is entrained by the forcing term after two cycles, and that thereafter it moves precisely in antiphase with it, much as Huygens originally reported for the pair of pendulum clocks [123]. A self-oscillator can also be entrained at an integer multiple ("harmonic") of the driving frequency, as was mentioned in Sec. IV E.

Though the quantitative characterization of entrainment can be cumbersome (see [105, 124, 126, 144]), the qualitative explanation of the kind of entrainment shown in Fig. 19 is straightforward: when the relative phase ϕ between the (nearly) sinusoidal motion of the oscillator and the forcing term in Eq. (62) is such that $\sin\phi \neq 0$, the external force is doing net work on the oscillator (see Sec. III B) and therefore causing the amplitude to vary. Because of the nonlinearity, a change in the amplitude also changes its frequency, and for some range of parameters this means that the oscillation can adjust itself in response to the external driving force, until it reaches a steady, phase-locked motion.

In the relaxation regime ($\alpha \gg 1$) for Eq. (62), $x(t)$ can also be locked into a submultiple ω_d/n of the driving frequency ("frequency demultiplication") [133]. An instance of demultiplication is shown in Fig. 20. An interesting demonstration conducted by van der Pol and his collaborator van der Mark was to have a Pearson-Anson relaxation oscillator drive a loudspeaker, and in turn to drive that oscillator at a constant frequency ω_d [173]. As the capacitance in the Pearson-Anson circuit is dialed up, increasing its natural period, the output is locked at successive submultiples of ω_d, producing a series of discrete tones that sound much like a descending musical scale played on the bagpipes (see also [96]).

During their experiments on frequency demultiplication, van der Pol and van der Mark also noticed that under certain conditions the output of the loudspeaker became very noisy. The reason is that, for some values of the parameters in Eq. (62), the ratio of the period of the entrained motion to the period of the forcing term becomes irrational: this is called the *quasiperiodic* regime. For large α, the quasiperiodic and the periodic regimes may overlap, leading to solutions to Eq. (62) that are chaotic, as we mentioned at the end of Sec. IV E. This is the case, e.g., for $\alpha = 3$, $\omega_d = 1.788$, and $F_0 = 5$, as illustrated in Fig. 21.

The subject of the onset of chaos in driven nonlinear systems is treated in detail in modern textbooks on dynamical systems. See, e.g., the discussion of the Kolmogorov-Arnol'd-Moser (KAM) theorem in [174]. For an interesting discussion of such systems, with an emphasis on their possible use in macroeconomics, see [175].

4. FitzHugh-Nagumo model

As we mentioned in IV D, the FitzHugh-Nagumo model of neuronal action potentials [118, 119] is of considerable significance in modern neuroscience (see [121]). It was introduced by FitzHugh as a simplification of a four-variable



FIG. 20: The solution to $\ddot{x} - 5\left(1 - x^2\right)\dot{x} + x = 2\cos(1.6t)$, for $x(0) = 0.1$, $\dot{x}(0) = 0$, is shown in red. The forcing term $2\cos(1.6t)$ in shown in dashed blue. The waveform $x(t)$ is locked at a third of the forcing frequency.



(a)

(b)

FIG. 21: Solutions to $\ddot{x} - 3\left(1 - x^2\right)\dot{x} + x = 5\cos(1.788t)$ show sensitive dependence to initial conditions. In (a) the waveform in solid red starts at $x(0) = 0.1$, $\dot{x}(0) = 0$ and the one in dotted blue at $x(0) = 0.1$, $\dot{x}(0) = 0.01$. The chaotic Liénard trajectory (with $y \equiv \dot{x}/3 - x + x^3/3$) for the first of those solutions is shown in (b), for $0 \leq t \leq 100$. The vertical isocline is indicated by the dashed blue curve.

model proposed earlier by Alan Hodgkin and Andrew Huxley to account for their observations of the behavior of the squid giant axon [176]. (For that work, Hodgkin and Huxley shared the 1963 Nobel Prize in physiology or medicine with Sir John Eccles [177].)

Mathematically, the FitzHugh-Nagumo model is characterized by

$$\begin{cases} \dot{x} = y - F(x) + I(t) \\ \dot{y} = -x - cy \end{cases} , \tag{63}$$

which is equivalent to the second-order, inhomogeous equation

$$\ddot{x} + (f(x) + c)\,\dot{x} + (x + cF(x)) = cI(t) + \dot{I}(t) , \tag{64}$$

where $f(x) = F'(x)$. This can be easily implemented electrically by adding a resistor in parallel with the inductance L in the circuit of Fig. 10(a) and supplying a time-varying current $I_0 + I(t)$. Then x corresponds to the voltage V_{out} and y corresponds to the current flowing from ground through the inductor. As before, $F(x)$ is given by the characteristic I-V curve of the tunnel diode. Many authors use the same $F(x)$ as in the van der Pol oscillator:

$$F(x) = \alpha(-x + x^3/3) . \tag{65}$$

In modeling neuronal action potentials, $I(t)$ is usually interpreted as a slowly-varying stimulus current, so that $\dot{I}$ is negligible and the driving is not a significant effect. Rather, what is important is that a steady $I \neq 0$ displaces the point along the characteristic I-V curve of Fig. 10(b) about which the circuit operates.



(a)

(b)

FIG. 22: Solution to the FitzHugh-Nagumo equation (Eq. (63)) for $F(x) = x^3 - 3x$ and $c = 0.1$, as I is reduced by steps for size 5, starting from $I = 10$, at time intervals of 30. Plot (a) shows the waveform for $x(t)$. Plot (b) shows the Liénard trajectory, with the horizontal isocline and the successive vertical isoclines shown in dashed blue.

In Eq. (63), the equilibrium point $\dot{x} = \dot{y} = 0$ is given by the intersection of the vertical isocline $y = F(x) - I$ with the horizontal isocline $y = -x/c$. For $c > 0$, the stimulus current I displaces that equilibrium away from the inflection point (authors usually choose a c small enough so that the horizontal isocline can intersect the vertical isocline only once, always giving a single equilibrium). This displacement makes the oscillation asymmetric, for the same reason described in Sec. V B 2. For sufficiently large $|I|$, the equilibrium is displaced to a point along the characteristic curve where the slope is positive and self-oscillation therefore ceases, since the linear damping term is no longer negative and the corresponding equilibrium is therefore stable.

In this way, the model captures the ability of neuronal firing to be turned on and off. Note that the introduction of the term $-cy$ in the expression for $\dot{y}$ in Eq. (63), which corresponds to adding a resistor in parallel with the inductor in the circuit of Fig. 10(a), is what allows one to adjust the point of operation along the diode's characteristic curve by varying the current I_0 without having also to adjust the voltage V_0 of the battery.

Figure 22 illustrates how the relaxation oscillation turns on and off, and how the asymmetry of the oscillation changes, as the value of the stimulus current I is varied. In Fig. 22(a), the waveform for $x(t)$ is plotted as I is successively stepped down from 10 to 5 (at $t = 30$), from 5 to 0 (at $t = 60$), from 0 to -5 (at $t = 90$), and from -5 to -10 (at $t = 120$). The same oscillation is shown as a trajectory in the Liénard plane in Fig. 22(b), where the straight horizontal isocline $y = -10x$ and the successive vertical isoclines $y = x^3 - 3x - I$ are plotted as dashed lines. The points marked A and B are stable equilibria, corresponding to the non-oscillatory phases of the waveform for $x(t)$, when $I = \pm 10$ respectively.

5. *Poincaré-Lyapunov stability analysis*

Poincaré [178] and Lyapunov [179] formulated stability analysis —including the stability at a point and the stability of time-dependent trajectories such as limit cycles— in a more sophisticated mathematical language, based on Poincaré's phase space method for the study of nonlinear differential equations. It is this formulation which is most familiar to scientists today. See [170] for a brief summary of this work. Arnol'd gives a particularly readable presentation of this subject in his remarkable textbook on ordinary differential equations [180]. Other treatments written for physicists include [181, 182].

The physics involved is essentially the same as in the older Routh-Hurwitz analysis; it is even possible that the mathematical elegance and rigor introduced by Poincaré and Lyapunov might have helped divert the attention of physicists away from the energetic considerations that we stress in this article. Since the topic is well covered in the standard physics literature, we shall not comment on it further.

VI. MOTORS

Andronov, Vitt, and Khaĭkin, defined self-oscillation as the production of "a periodic process at the expense of a non-periodic source of energy" [183]. Only a regular periodic motion is technologically useful, but most of the sources of power provided by nature are steady or slowly varying with respect to the time scales relevant to human technology. Therefore self-oscillators, which turn a steady input into an alternating output, are essential to engineering.

A. Turbines

The oldest and still the most important motors are turbines, which use a steady flow to drive a circular motion. This circular motion can then be transformed into the alternating linear movement of a piston or, if the turbine drives a generator, into an alternating electrical current. Turbines are self-oscillators, since they produce a periodic motion without a periodic input.

The motion of a turbine is similar to a relaxation oscillation in that the amplitude is fixed but the frequency may vary depending on the speed of the flow and the friction on the turbine (the turbine's resonant frequency is zero, because there is no restoring force to move it back towards an equilibrium). However, unlike the relaxation oscillators described in Sec. IV B, the motion produced by a turbine is sinusoidal, because the wheel of the turbine is *circular*. The nonlinear switching is therefore gradual —being given the the circular turning— and does not occur suddenly at a threshold.

B. Heat engines

In practical steam engines, the feedback of the flow of steam on the turbine's motion is usually effected by a *valve*, which modulates the pressure of the steam in phase with the linear velocity of the piston attached to the turbine. The operation of such a steam engine is characterized mathematically as a self-oscillation in [184]. Note that the action of the valve in such engines is not, strictly speaking, thermodynamical. For instance, the setup analyzed in [184] would work equally well if the working substance were a fluid moved by a mechanical pump, instead of steam generated in a boiler.

It is also possible to achieve the feedback necessary for self-oscillation by controlling the release of heat, rather than the mechanical motion of the working substance. This is the case of a Diesel engine, in which the compression of the working gas by the piston causes the fuel to ignite, injecting a large amount of heat into the gas. In an Otto engine (such as the one in a gasoline-powered automobile), the injection of heat into the working gas at the phase of maximum compression is triggered by a spark-plug, whose action is timed accordingly. (On the Diesel and Otto thermodynamic cycles, see, e.g., [185].)

There is also a class of "thermoacoustic self-oscillators," which we shall describe in detail in Sec. VII B, in which a positive feedback is naturally established by the flow of heat between the working substance and its surroundings. A particularly fascinating and scientifically relevant instance of such a heat engine is seen in Cepheid variable stars (see Sec. VII B 4).



FIG. 23: Overshot water wheel. The power in the "tail" flow is an essential loss, making the efficiency of the wheel strictly less than 1. The illustration is by Daniel M. Short, available at `http://commons.wikimedia.org/wiki/File:Overshot_water_wheel_schematic.svg`

C. Limit efficiency

Philippe Le Corbeiller[44] labeled self-oscillators as "motors," and passive devices (including forced resonators) as "transformers" [96, 187]. Le Corbeiller also noted that the efficiency of a "transformer" (i.e., the ratio of the power received to the power used to drive the output) can be taken to unity —if nonessential losses are eliminated— because the power is delivered at the same frequency with which the output moves. But when the power is inputed at a frequency different from that of the movement of the output, there is an *essential* loss of power that cannot be eliminated. This is the case for "motors" in general, for which the input is steady and the output periodic.

In the van der Pol circuit of Fig. 10, the current that passes through the tunnel diode oscillates about I_0, while the voltage drop across the diode oscillates about V_0. Thus there is an average power loss

$$\langle P_{\rm diode} \rangle > V_0 I_0 > 0 \; , \tag{66}$$

in addition to any power dissipated in the resistance R. This essential loss $\langle P_{\rm diode} \rangle$ cannot be eliminated: no device can have a characteristic I-V curve with negative slope at the origin ($V_0 I_0 = 0$), since it would require the electrons to move against the electric field.

The same principle is illustrated by the operation of the simplest turbine: the overshot water wheel, shown in Fig. 23. The water flow provides kinetic and gravitational potential energy, which are converted into the wheel's rotation. But some of the gravitational potential energy *must* be wasted, even if the wheel turned without friction, because water begins to spill out of the buckets before they reach the bottom. This "tail" flow is an essential power loss. That loss vanishes only in the limit of infinite wheel radius, in which case the motion ceases to be periodic. In an undershot wheel, the paddles must move out of the flow as the wheel turns, and the maximum effiency is therefore also strictly less than unity for a wheel of finite radius.

Notice that the fact that water spills out of the buckets of the wheel before they reach the bottom also accounts for the modulation of the force of the water in phase with the horizontal velocity of the buckets: the force is large when the buckets are moving leftwards and downwards, smaller when the buckets are moving rightwards or upwards. Thus, the loss of power in the tail is necessary to set up the negative damping that causes the wheel to self-oscillate.[45]

---

[44] Philippe Emmanuel Le Corbeiller (1891–1980), was a French-American electrical engineer, mathematician, and physicist, whose intellectual interests were remarkably broad. He was educated at the École Polytechnique, worked on telegraph and radio systems, and earned a doctorate in mathematics from the Sorbonne. Le Corbeiller emigrated to the United States during World War II and became a professor of applied physics and general education at Harvard [186].

Modern designs attain about 85% and 75% efficiencies for over- and undershot wheels, respectively [189]. The most common type of hydraulic turbine used today for industrial applications is the radial inflow (or "center-vent") turbine developed by James B. Francis in 1848, which spins on a horizontal plane and in which the tail flow leaves though the center of the wheel (see, e.g., [190]). The energy of this tail flow cannot be reduced beyond a certain limit, because the water must drain out at the same rate at which it enters the turbine. If gravity cannot cause the water at the center of the turbine to drain quickly enough, it will be pushed out by the flow, which implies a waste of kinetic energy.

Another hydraulic instance of this same general principle is seen in a cistern placed under a steady stream of water and connected to a siphon so that the water level in the cistern performs a relaxation oscillation.[46] It is easy to show that the maximum efficiency goes to unity only when the frequency of that oscillation vanishes [139].

In an electrical motor, an essential power loss is caused by the "slip" (i.e., the relative motion of the rotor with respect to the magnetic field), which induces an electromotive force (the "back emf") that opposes the input voltage. This slip can vanish only when the input voltage has the same frequency as the motion of the rotor. Similarly, the self-oscillation ("nutation") of a spinning top, as described in Sec. V A 2, must be accompanied by a steady precession, which also consumes energy if the tilt of the top's axis is varying.

Le Corbeiller suggested in [187] that Carnot's thermodynamic limit

$$\eta \leq 1 - \frac{T_2}{T_1} \tag{67}$$

for the efficiency η of a heat engine that absorbs heat from a reservoir at temperature T_1 and releases heat into a reservoir at a lower temperature T_2, might be an instance of this more general principle. Note that there is no fundamental obstruction to transforming heat completely into non-periodic motion (e.g., by having an expanding gas push out a piston, or by boiling water to generate a steady flow of steam). What the second law of thermodynamics forbids is turning the steady heat of a reservoir entirely into the mechanical power that drives a *periodic* motion (see [7, 8]).

Non-unit efficiency does not, of course, imply irreversibility: e.g., a reversible Carnot engine operating between reservoirs with finite temperatures $T_{1,2}$ has efficiency $\eta < 1$. But the fact that, in practice, self-oscillators robustly attain a unique limit cycle regardless of initial conditions and of previous transient perturbations *does* make them irreversible. This irreversibility results from the generation of entropy by the dissipation associated to the nonlinearity that determines the limiting cycle. Since all man-made clocks are nonlinear self-oscillators with a limiting cycle, this implies that they are themselves entropy generators.[47]

1. *Carnot's theorem revisited*

It was Sadi Carnot's uniquely brilliant contribution in [193] to show that no heat engine —operating between two heat reservoirs each with a constant temperature— can have greater efficiency than a reversible engine (which may be theoretically implemented as a cycle of isothermal and adiabatic changes to the volume of an ideal gas, thus allowing us to compute that limiting efficiency in terms of the reservoir temperatures), *assuming* that the laws of physics forbid any process that merely converts heat from a source at a single temperature into the mechanical energy of a periodic motion. This axiomatic approach, later formalized by Clausius and Kelvin, was necessitated at the time by the ignorance of the nature of heat (i.e., by the lack of a *microphysical* understanding of thermal processes). Carnot himself stressed that mechanical engines (such as water wheels) may be completely described by the rules of

---

[45] In [188], M. Denny proposes an overshot water wheel in which the buckets are attached by pivots to the rim of the wheel. Each bucket is tipped over and emptied at the bottom of the cycle, eliminating the tail flow. But this design cannot eliminate the power loss, even in principle, because the tipping of a bucket necessarily consumes energy. Even if each bucket were filled up to the maximum stable level, at which its center of mass coincides with the pivot, the center of mass descends relative to the pivot as the bucket starts to empty. It therefore would take finite energy to complete the emptying of each bucket, even if all friction and other forms of dissipation were eliminated.

[46] This setup was used by Le Corbeiller [96] and Herrenden-Harker [139] as a pedagogical model of relaxation oscillation in general; see also [191]. It is the same mechanism by which a toilet flushes: the water level rises until it reaches the same height as the elbow of the siphon tube, thereupon causing the cistern to "flush" until the water level falls below the siphon's intake.

[47] Schrödinger makes a similar observation in [192], where he explains that "if we remember that without a spring the clock is gradually slowed down by friction, we find that [its continued operation] can only be understood as a statistical phenomenon."

Newtonian mechanics, without further assumptions.[48]

Le Corbeiller's conjecture about the efficiency of frequency conversion is easy to show for mechanical systems, in which the input power can be expressed as

$$P_{\rm in} = \mathbf{F}_{\rm in} \cdot \mathbf{v}_{\rm in} \ , \tag{68}$$

where $\mathbf{F}_{\rm in}$ is an instantaneous force and $\mathbf{v}_{\rm in}$ the velocity of the flow that provides the power. The power delivered to the output is

$$P_{\rm out} = \dot{\mathbf{q}} \cdot \mathbf{F}_{\rm out} \ , \tag{69}$$

where $\mathbf{q}$ is the time-dependent coordinate vector that characterizes the output. By energy conservation, at any instant

$$P_{\rm out} \leq P_{\rm in} \ . \tag{70}$$

We may therefore normalize $\mathbf{v}_{\rm in}$ so that

$$|\mathbf{F}_{\rm out}| \leq |\mathbf{F}_{\rm in}| \ , \tag{71}$$

with the equality holding only when *all* of the flow is applied to the output $\mathbf{q}$. Then we see that unit efficiency ($P_{\rm in} = P_{\rm out}$) is possible only when $\mathbf{v}_{\rm in}$ moves in phase with $\dot{\mathbf{q}}$, which can only be maintained during a complete cycle if the frequency of $\mathbf{q}$ matches the frequency of the input.

In particular, if the input and output frequencies do not match, there must be a *slip* phase during which the output $\mathbf{q}$ moves against the input or away from it, so that $P_{\rm out} \leq 0$. During this slip phase, $P_{\rm out}$ is non-negative only if the flow is completely diverted away from the output (i.e., if $\mathbf{F}_{\rm out} = 0$).

If the input and output waveforms have the same form (whether sinusoidal or otherwise), but different periods $\tau_1 < \tau_2$, then the efficiency η is limited by

$$\eta \leq \frac{\tau_1}{\tau_2} \ . \tag{72}$$

This can be shown by imagining that the input and output oscillations start in phase at the origin, then letting them run for a sufficient number of cycles until they cross the origin in phase again (or infinitesimally close, if τ_1/τ_2 is irrational). The difference in the number of input and output cycles can then be equated with the loss of energy from slip. Equation (72) is familiar from the limiting efficiency of an AC motor in terms of the respective periods of the input voltage and of the rotor's motion (see [187]).

When the shapes of the input and output waveform are different (as they must be if the input is non-periodic) the efficiency limit is more difficult to express in generality, but it must still be strictly less than unity if the frequencies are not matched. For instance, in the case of the stick-slip motion of a violin string, illustrated in Fig. 6, during the stick phase AB the violin string moves with the bow ($\dot{q} = v_{\rm in}$), so that $P_{\rm out} = P_{\rm in}$ (if non-essential power losses are eliminated). But in order to describe a motion with a finite period, the string must eventually slip against the bow, giving $P_{\rm out} \leq 0$.

Let v_s be the speed of the violin string as it crosses the origin during the slip phase (at point C in the plot of Fig. 6). Since the corresponding kinetic energy cannot exceed the potential energy at the maximum displacement (indicated by B in the plot), for an elastic string

$$v_s^2 \leq \omega_0^2 A^2 \ , \tag{73}$$

where ω_0 is the string's resonant frequency and A is the amplitude of the displacement. The time t_s during which the string slips is therefore bounded as:

$$t_s \geq \frac{2A}{v_s} \geq \frac{2}{\omega_0} \ . \tag{74}$$

---

[48] Some authors claim that Carnot's work on the efficiency of heat engines was inspired by an analogy between the flow that drives a water wheel —which his father had investigated in [194]— and the flow of heat in a steam engine. There is, however, very little evidence of this in his published essay [193]. Except for some obscurities associated with the fact that the nature of heat was then totally unknown, Carnot's argument is the same as that given by modern conceptual expositions of the second law of thermodynamics, such as [7] and [8]. According to Kelvin, "nothing in the whole range of Natural Philosophy is more remarkable than [Carnot's] establishment of general laws by such a process of reasoning." [195]


P_{in} ; ω_1
motor
P_{out} ; ω_2
"tail" ; ω_1

FIG. 24: Schematic representation of the operation of a motor, which takes a power input P_{in}, with frequency ω_1, and outputs a power P_{out} at frequency ω_2. For many motors, including clocks, $\omega_1 = 0$. The "tail" represents the loss of power in the conversion of the two frequencies.

Since the maximum efficiency during the stick phase (AB in the plot) is 1, and the maximum efficiency during the slip phase (BD in the plot) is 0, the total efficiency for the elastic string is limited by

$$\eta \leq \frac{2\pi - \omega_0 t_s}{2\pi} = 1 - \frac{1}{\pi} \simeq 0.68 \; . \tag{75}$$

Even for an inelastic string, the limit $t_s \to 0$ requires that the energy of the string (and therefore also its amplitude) diverge, which is impossible with finite power input, except in the limit in which the period of the string's motion also diverges.

Quite in general, we see that the energy wasted during the slip cannot be taken to zero in any system, even under ideal operating conditions, *except in a limit in which frequency conversion fails.* In the familiar case of the thermodynamic Carnot cycle, the slip appears as the phase of isothermal compression of the gas, during which heat is released into the colder reservoir at temperature T_2.

This result can then be used to show, by a straightforward generalization of Carnot's argument, that a motor that takes power at frequency ω_1 and outputs it at another frequency ω_2 cannot have greater efficiency than a reversible motor capable of the same conversion; otherwise the more efficient device could drive the other in reverse, making a composite engine capable of slipless frequency conversion.

Thus, we may formalize a *Carnot-Le Corbeiller theorem* for the efficiency of motors:

> The efficiency of any motor converting a power input with frequency ω_1 to an output with frequency ω_2 can approach unity only in the limit $\omega_2 \to \omega_1$. The maximal efficiency of a motor that converts an input at ω_1 to an output at ω_2 is that of the reversible operation of a given motor design.

In Fig. 24, this is schematically represented by the loss of power in the "tail" (which we have named by analogy to the tail flow in Fig. 23).

Note that there is no fundamental obstruction to converting the mechanical power in the tail completely and reversibly from one form to another (e.g., from a flow of water to the motion of buckets), as long as the frequency ω_1 is unchanged. The power in the tail can also be *irreversibly* converted into heat by friction.

Note as well that the $\omega_{1,2}$ in the Carnot-Le Corbeiller theorem are *not* analogous to the $T_{1,2}$ in Eq. (67). For heat engines, $\omega_1 = 0$ and $\omega_2 > 0$ is arbitrary. Furthermore, in phenomenological thermodynamics temperature is *defined* in terms of the limit efficiency, as given by the reversible Carnot cycle (see [7, 8]).

Recall that the second law of thermodynamics (in Kelvin's formulation) forbids a machine to return to an initial configuration (described by a coordinate vector $\mathbf{q}^{(0)}$) after merely having transformed a certain amount of heat into mechanical work. Similarly, it is clear from the Carnot-Le Corbeiller theorem that *no motor* can return to its initial configuration, having merely absorbed power at a frequency different from that of its own motion. For example, the "overbalanced" wheel in Fig. 1 fails because gravity is steady and therefore pulls down with the same force when the weights are moving down as when they are moving up, so that integrating over one period τ of the motion of any given weight gives

$$W_{\rm net} = \int_0^\tau dt\, \mathbf{F} \cdot \dot{\mathbf{q}} = -mg \int_0^\tau dt\, \dot{y} = mg\left[y(0) - y(\tau)\right] = 0 \ , \tag{76}$$

where $y(t)$ is the vertical coordinate for the weight and mg is the magnitude of the downward force exerted by gravity. The water wheel in Fig. 23 must waste some of the power of the water because it must be diverted into a tail flow to prevent it from acting on the buckets when they are moving in a direction contrary to that of the flow (i.e., either to the right or upward in the illustration).

Parametric resonance, discussed in Sec. III F, would seem to offer a counterexample to the Carnot-Le Corbeiller theorem, since small angular oscillations can be driven with unit efficiency when the driving frequency is *twice* the frequency of angular motion. Note, however, that it is actually the frequency of the vertical displacement y (which is twice the frequency of the angular motion θ) that should be interpreted as ω_2 when applying the Carnot-Le Corbeiller theorem to the parametrically driven pendulum of Fig. 8. In other words, the lossless conversion of frequencies is purely *geometrical*, not dynamical: even in a free pendulum, the frequency of $y(t)$ is twice the frequency of $\theta(t)$.

We do not know whether, by working in a multidimensional space, such a geometrical frequency conversion can give a ratio other than 2. Such conversion cannot, in any case, be applied to devices in which $\omega_1 = 0$ (such as heat engines and most other motors) or to any device in which ω_1/ω_2 can vary continuously.

2. Minimal friction in mechanisms

An instructive application of the Carnot-Le Corbeiller theorem is to the action of gears.[49] An angular velocity ω_1 can be converted to different angular velocity ω_2 by using gears of radii $r_{1,2}$ so that

$$\omega_1 r_1 = \omega_2 r_2 \ , \tag{77}$$

but this process cannot approach unit efficiency.

Consider a given tooth on the powered gear (the "driver"), which comes in contact with a tooth on the other gear (the "follower"), as shown in Fig. 25. If the driver tooth is powered by a tangential force $\mathbf{F}_{\rm in}$, then

$$P_{\rm in} = \mathbf{F}_{\rm in} \cdot \mathbf{v}_{\rm in} = F_{\rm in} \omega_1 r_1 \ . \tag{78}$$

For ω_1 to be constant, $\mathbf{F}_{\rm in}$ must be exactly cancelled by the reaction $-\mathbf{F}_{\rm out}$ from its pushing on the follower tooth. Let $\mathbf{v}_{\rm in}$ and $\mathbf{v}_{\rm out}$ be, respectively, the instantaneous velocities of the driver tooth and the follower tooth, which by Eq. (77) are of equal magnitude. In the steady state the power delivered to the follower tooth is therefore

$$P_{\rm out} = \mathbf{F}_{\rm out} \cdot \mathbf{v}_{\rm out} = F_{\rm in} \omega_1 r_1 \cos\theta \le P_{\rm in} \ , \tag{79}$$

where θ is the angle between $\mathbf{v}_{\rm in}$ and $\mathbf{v}_{\rm out}$. Thus, some power must be lost unless the motions of the teeth are aligned ($\theta = 0$), which occurs only at the configuration of Fig. 25(b). When the teeth are engaging, as in Fig. 25(a), or disengaging, as in Fig. 25(c), they are moving relative to each other along the direction of a line that joins the centers of the two wheels, and the teeth are therefore *slipping.*

In practice, the difference $P_{\rm in} - P_{\rm out}$ goes into heating the gears by the friction associated with the slipping of the teeth against each other, or with the turning of the follower's axle. If there were no friction at all, so that $P_{\rm out} = P_{\rm in}$, then for $\theta \neq 0$ we would have either $F_{\rm out} > F_{\rm in}$ or $\omega_2 r_2 > \omega_1 r_1$, so that slipping would make the follower gear *speed up* relative to the driver, causing the teeth to become misaligned and finally crush each other.

Note that there must be a loss from slippage even for $r_1 = r_2$, in which case the gears turn with the same angular velocity ω_1, but in opposite directions. The power loss can only be eliminated in the limit $r_{1,2} \to \infty$, in which case the teeth can be permanently engaged and there is no frequency conversion.

---

[49] I thank Charlie Bennett and Graeme Smith for calling my attention to this problem.



FIG. 25: At (a), a tooth on the driver gear (below) has begun to engage a tooth on the follower gear (above). At (b), the two teeth are fully engaged and there is no slippage between them. At (c), the teeth have begun to disengage. The label $\mathbf{v}_{\rm in}$ indicates the instantaneous velocity of the driver tooth, and $\mathbf{v}_{\rm out}$ that of the follower tooth. Image adapted from Fig. 8 in [196].

More intuitively, the point is that as the teeth in the driver disengage and move away from the follower, they carry kinetic energy that was not delivered to the follower. This is analogous to the "tail flow" away from the water wheel, shown in Fig. 23. Unlike in the case of the water wheel's tail flow, the teeth of the driver come back around and re-engage with the follower. But for the overall process to be lossless, the kinetic energy in the driver's teeth just after disengagement (the "tail") must be steadily decreasing relative to the kinetic energy of the follower, which implies that the driver must be decelerating relative to the follower. Not only would this mean that $\omega_{1,2}$ in Eq. (77) would not be constant, it could not be sustained because the gear teeth would become misaligned.

The claim that gears can operate frictionlessly if designed so that the point of contact of the teeth remains collinear with the centers of the two wheels —thus eliminating the slipping of the teeth against each other— dates back to Robert Hooke, who referred to it as "the perfection of Wheel-work; an invention which I made and produced before the Royal Society in 1666" [197]. Airy [198] and others argued that this was possible if the teeth were cut as logarithmic spirals. This was extended to a broad class of curves by Willis [199]. In such designs, however, the ratio r_1/r_2, which gives the mechanical advantage of the action of the driver on the follower, *increases* while a given pair of teeth is engaged, which in the absence of friction would imply that the follower would accelerate relative to the driver.

That steady gear action is impossible without finite friction was demonstrated, using geometrical techniques, in Willard Gibbs's 1863 doctoral dissertation [200], ten years before he turned his attention to thermodynamics. Remarkably, we have found no indication that Gibbs's result has ever been appreciated.[50]

If, instead of gears, we consider two smooth wheels rolling against each other without slipping, the reason why the driving of one by the other cannot be lossless is even clearer: For one wheel to turn the other, there must be a sufficient attraction between the material in the rims. Therefore, it costs finite energy to unstick the rims after their point of contact. It is not possible to get rid of that loss from unsticking without also eliminating the coupling that allows one wheel to turn the other.

A similar analysis can be made for gears connected to chains, or for shafts wrapped by belts. In the case of chains, there must be some loss as the links engage and disengage from the teeth in the gearing. Similarly, it must consume non-zero energy to unstick a belt from the surface of the shaft. Note that if one wheel turns another via a chain or a belt, there is a lossy conversion of power to and from zero frequency (the linear motion of the chain or belt), even if both wheels have the same radius and turn at the same rate.

In general, mechanisms can only convert the finite difference between input and output power (the "tail" of Fig. 24) into frictional heat. Thus we see that their operation is necessarily *irreversible*.

To quantify the limiting efficiency of the action of smooth wheels or belts, let λ be the linear density of the mass along the rims and ds be the infinitesimal length of the region of contact between the rims, as shown in Fig. 26. "Rim" is here defined as the finite-width annulus of solid material along the exterior of the wheel or belt that is in effective contact with the other device, and which is therefore involved in the interaction that causes static friction at the point of contact.

---

[50] Gibbs's thesis refers specifically to "spur gearing" in the title, but its results extend as well to what are now called helical gears. This brief and highly abstract dissertation remained unpublished until 1947, when it appeared with a commentary by Yale engineering professor E. O. Waters [201] that shows no interest in Gibbs's demonstration of the impossibility of frictionless gearing. It is true that this is more a question of geometry and theoretical physics than of practical engineering, because the action of the gear teeth is not usually the principal source of dissipation in real-world mechanisms, which are therefore far from their limit efficiency.



FIG. 26: The lower wheel (the driver) turns the upper one (the follower) by rolling without slipping at the point of contact, where the mass elements on the rim have a common velocity $\mathbf{v}$. Each element has mass $\lambda\, ds$, where λ is the linear density of the rims and ds is the tangential length of the region of contact. The thickness of the rims is determined by the depth of the layer of solid material involved in producing static friction at the point of contact.

.

For the driver to be able to move the follower at speed v without slipping, a mass element λds on the driver's rim must be able to come in from infinity with speed v, "collide" at the point of contact with the corresponding mass element —initially at rest— on the follower, and then have the two elements move together with speed v.[51] Thus, by energy conservation:

$$\frac{1}{2}(\lambda\, ds)v^2 = (\lambda\, ds)v^2 - dE \ , \tag{80}$$

where $-dE$ is the potential energy corresponding to the attraction of the rim elements when in close proximity. It must therefore cost energy dE to unstick the rim elements past their point of contact. If at least one of the wheels has finite radius, this unsticking occurs over an infinitesimal time

$$dt = \frac{ds}{v} \ . \tag{81}$$

By Eq. (80), the minimum power consumed by the rolling friction is therefore

$$P_{\text{in}} - P_{\text{out}} = \frac{dE}{dt} = \frac{\lambda v^3}{2} \ . \tag{82}$$

This cannot be taken to zero for $v > 0$, since λ must be finite, as otherwise there can be no action between the devices (just as gears cannot operate with massless teeth). The point is that, even in a conservative system, the energy involved in the unsticking of the rims cannot be transferred from the driver to the follower, because they are *moving apart.*

When the wheels are turning steadily, the force that powers the rim of the driving wheel is cancelled by the static friction f from the contact with the follower wheel. Thus, the input at the rim of the driving wheel is:

$$P_{\text{in}} = fv \tag{83}$$

so that the efficiency is constrained by

$$\eta \equiv \frac{P_{\text{out}}}{P_{\text{in}}} \leq 1 - \frac{\lambda v^2}{2 f_{\max}} \ , \tag{84}$$

where $f_{\max}$ is the maximal static friction for the materials on the rims. Clearly, $f_{\max}$ depends on λ, since

$$\lim_{\lambda \to 0} f_{\max} = 0 \ ; \qquad \lim_{f_{\max} \to \infty} \lambda = \infty \ . \tag{85}$$

---

[51] Of course, the rim of the follower is not at rest when the wheels are turning steadily. But this procedure allows us to calculate the condition such that all the energy of the follower comes entirely from the driver.

What the precise behavior of $\lambda/f_{\max}$ might be lies beyond our personal knowledge of tribology, but Eq. (84) suffices to establish that the efficiency of power transfer between wheels turning without slipping (or between a shaft and a belt) cannot be taken to zero, as required by the Carnot-Le Corbeiller theorem.

VII. OTHER APPLICATIONS

A. Servomechanisms

It is very common in engineering for a system to be driven by a self-oscillating motor, which in turn is controlled by negative feedback so that the motion follows some intended trajectory. This is called a *servomechanism*, and the simplest example is a steam engine whose rate is fixed by the action of a governor, as we mentioned in Sec. V A 1.

The onset of an unwanted self-oscillation about the servomechanism's intended trajectory is sometimes called "hunting" in mechanical systems, and "parasitic oscillation" in electronics. The presence of such oscillations can be diagnosed by applying the Routh-Hurwitz criterion to the linearized equation of motion for small perturbations about the intended trajectory. But for servomechanisms in particular it is usually more practical to use the stability criterion in a different form, proposed by Harry Nyquist in [202] and based on the form of the gain as a function of frequency. The Nyquist stability criterion, which is central to modern control theory, is reviewed from a physical point of view in [159]. For a more thorough mathematical treatment, see [203].

An important type of "hunting" is the swaying of a railway vehicle when it travels above a critical speed [204, 205]. Parasitic oscillations are a common problem in electronic amplifiers, as discussed in [206]. "Intention tremor" is a neurological disorder seen in patients with injuries to the cerebellum, such that if the patient, for example, tries to pick up a pencil, his hand will overshoot the position of the pencil and then go into an uncontrollable oscillation around it (see, e.g., [207]). Mathematician Norbert Wiener characterized voluntary human motion as a servomechanism and pointed to intention tremor as a parasitic oscillation of that system [208].

B. Thermoacoustic self-oscillators

A thermoacoustic self-oscillator is a device in which the flow of heat between the working substance and its surroundings sustains an oscillation of that working substance's volume and pressure. The resulting vibration can produce a sound of a well-defined frequency that propagates through a surrounding medium, though of course the generation of sound is incidental and for the most part we will only be interested in the oscillation of the working substance itself. A thermoacoustic self-oscillator differs from an ordinary heat engine in that a positive feedback is established *without any mechanical valve* (or other device) controlling the motion of the working substance (see Sec. VI B).

1. Putt-putt boat

An amusing and instructive instance of thermoacoustic self-oscillation is the putt-putt (or pop-pop) boat, a toy whose circulation dates back at least to the early 20th century, when it was being fabricated by Nuremberg toymaker Ernst Plank [209]. The design had been patented in 1891 by Desiré Thomas Piot, who described it as a "steam generator" well suited to "the case of toy boats" [210]. The putt-putt was once very popular but is no longer easily bought, partly because it must be made of metal, while most toys today are plastic.[52]

The putt-putt works by heating (usually with a flame) an internal tank partly filled with water and connected to submerged exhausts, as shown in Fig. 27. It is usually easy to adjust the heat so that the water level will self-oscillate. As water is alternately blown out and sucked in through the exhausts, the boat moves forward with a noisy vibration that gives the toy its name.[53]

---

[52] Iain Finnie relates how, after becoming a professor of mechanical engineering at UC Berkeley in 1961, he began conducting popular lectures on the operation of various toys, at which the putt-putt (a favorite toy from his own childhood) always attracted the most attention [211]. The putt-putt featured prominently in the animated Japanese feature film *Ponyo*, released in 2008 [212]. Toy boats were sold as tie-ins when that movie came out.

[53] There has been a remarkably enduring confusion in both the research and the popular literature about why the boat does not move backwards when water is drawn into the exhausts, a confusion dating to the first published scientific discussion of the putt-putt boat by J. G. Baker in [162, 213]. The correct explanation is very straightforward: water flowing out of the boat carries momentum away with it. By Newton's third law, the boat must pick up an opposite momentum, propelling it forward. When water is aspirated, there's



FIG. 27: Schematic of the putt-putt boat: y measures the displacement of the liquid level away from equilibrium, A is the cross-section of the tank, and h the distance between the top of the tank and the level $y = 0$, so that the volume of gas in equilibrium within the tank is $V_0 = hA$.

According to the law of ideal gases, for a small displacement y of the liquid level away from its equilibrium, the pressure of the gas inside the tank, at a fixed temperature, is

$$P = \frac{CN_0}{V_0 - Ay} \simeq P_0 + k_1 y \ , \tag{86}$$

where N_0 is the quantity of gas inside the tank (measured in moles), while $P_0 \equiv CN_0/V_0$ and $k_1 \equiv CN_0 A/V_0^2$ are constants. The force $A(P_0 - P)$ that acts to restore y to its equilibrium is therefore proportional to y. Thus, small oscillations behave like a damped harmonic oscillator

$$\ddot{y} + \gamma \dot{y} + \omega^2 y = 0 \tag{87}$$

(which is what Boyle memorably called the "spring of the air" [217]).

Through the heating of the tank, the pressure inside acquires a dependence on S, the quantity of steam:

$$P = \frac{C(N_0 + S)}{V_0 - Ay} \simeq P_0(1 + S) + k_1 y \ . \tag{88}$$

As explained in [218, 219], S increases by a constant evaporation rate and decreases by a condensation rate proportional to the surface area inside the tank that is not covered by liquid. In equilibrium (which we define as $y = 0$) the condensation rate balances the evaporation rate,[54] so that

$$\dot{S} = k_2 \cdot y \ . \tag{89}$$

Thus there is a back-reaction of the oscillation of the water level y on the pressure difference $P_0 - P$ that drives it. This back-reaction is such that a positive feedback, and therefore a self-oscillation, can be established, as we will see.[55]

By Eqs. (88, 89), the equation of motion for small oscillation of y is

$$\ddot{y} + \gamma \dot{y} + \omega^2 y = -C_2 P_0 \int_0^t dt' \, y \ , \tag{90}$$

where C_2 is proportional to the value of k_2 in Eq. (89). For sinusoidal motion, the term on the right-hand side of Eq. (90) will be in phase with $\dot{y}$ and therefore can feed energy from the candle into the self-oscillation of y, whose

---

initially a reaction on the boat that would pull it backwards, but the incoming water soon impinges on the inner walls of the tubes and imparts its forward momentum to the boat. The initial backwards reaction on the boat is therefore cancelled by the forward pushing of the water on the boat's insides. This is discussed in detail in [214]. In the French engineering literature, the fact that a tank will recoil if water pours out of it but not if water pours steadily *into* the tank is sometimes called the "paradox of Bergeron," after mechanical engineer Paul Bergeron [215, 216].

[54] If there is no such equilibrium, the water will be pushed out completely and the putt-putt boat will not run.

[55] The schematic in Fig. 27 and the treatment in terms of the level y are somewhat idealized. Experimentally, it seems that the liquid leaves the tank completely during the high-pressure phase and that the steam only begins to condense when it reaches the tubes that connect to the exhausts [220]. This is because the walls of the tank are too near the flame and therefore too hot for effective condensation.



FIG. 28: A Rijke tube is open on both ends and has a heated metal mesh near the bottom. The movement of the air through the pipe is a combination of a steady upward convection flow and an oscillation given by the periodic variation of the pressure inside the tube. This acoustic oscillation will produce a loud tone as long as the mesh stays hot.

amplitude increases until nonlinear effects stabilize it [219].[56] Evidently, the criterion for self-oscillation is

$$C_2 P_0 > \omega^2 \gamma \ , \tag{91}$$

in which case the term on the right-hand side of Eq. (90) overwhelms the second term of the left-hand side, effectively giving y a negative damping.[57]

The putt-putt, like any other heat engine, must absorb heat from a region with temperature T_1 (the evaporating water warmed by the candle) and reject a lesser amount of heat into a region with lower temperature T_2 (the tank walls on which the steam condenses), with the difference available as work to move the liquid. Since steam is generated and re-condensed in the same chamber and therefore at nearly the same temperature, Eq. (67) implies that the maximum thermodynamic efficiency of the putt-putt is very low. On top of that, Finnie and Curl found that in the toys they examined only about a tenth of the work on the water was converted into propulsion of the boat, the rest being dissipated by the damping of the motion of the liquid in the tubes [218, 219]. Nonetheless, the putt-putt's mechanism is interesting as an instance of a valveless pulse jet engine. Furthermore, Finnie and Curl point out in [218] that if the tank were substituted by a large bellows, driven up and down by the oscillation of the internal pressure, the result would be a valveless version of the first steam engine patented by Watt in 1769 (see [221]).

2. Rijke tube

An even simpler (and perhaps more striking) demonstration of a thermally-driven self-oscillation is the Rijke tube [222], shown schematically in Fig. 28. If a wire mesh is attached near the bottom of large tube that is open at both ends and if the mesh is heated with a flame until it glows red, then after the flame is withdrawn the tube will produce a very loud tone, like that of an organ pipe, which dies out when the mesh cools. The tone can be sustained at will by heating the mesh with an electrical current, rather than a flame.

---

[56] An important nonlinearity is the dissipative pressure loss of the liquid during inflow, described in detail in Sec. 5 of [214]. This adds to Eq. (90) a damping term proportional to $(\dot{y} + |\dot{y}|)^2$. Since this acts only during the inflow phase ($\dot{y} > 0$), it can result in an asymmetric limiting cycle for y, as reported in [218, 219].

[57] In one of the more popular putt-putt boat designs, the top of the tank is a flexible diaphragm that reverses its concavity during the cycle of the gas pressure. This is not essential to the operation of the device: its primary function appears to be to reduce the value of ω so as to make it easier to fulfill the self-oscillation condition of Eq. (91) [219]. The diaphragm also makes the oscillation noisier, an attractive feature in a child's toy.

The operation of the Rijke tube is explained in [223, 224]. Due to convection, there will be a constant upward flow of air through the tube. Meanwhile, an oscillation of the pressure within the tube causes a periodic airflow that is superimposed on the steady upward convection. That oscillation causes air to pass through the hot mesh in alternate directions. When the velocity of the oscillation is at its maximum, it adds to the steady convection and maximizes the amount of fresh air that is being heated as it passes *up* though the mesh. This air then exerts a further upward push. After half a period of the oscillation, air is pushed *down* through the mesh, but this air is already hot and therefore causes little upward pushing. Thus the pushing of the newly-heated air is modulated in phase with the velocity of the acoustic oscillation inside the tube, establishing positive feedback.

It should now be clear that the tube can self-oscillate only if the hot mesh is in the bottom half of the tube, and also that the reason why the tube will not ring until the flame is removed is that the flame heats the air *before* it reaches the mesh. The Rijke tube is the simplest thermoacoustic self-oscillator; see [225] for some recent investigations on the subject. It can provide a simple and impressive lecture demonstration of self-oscillation in general, since it should be obvious to students that the loud ringing is not being driven by any periodic forcing term external to the system.

3. Rayleigh criterion

The Rijke tube illustrates a general principle known in mechanical engineering as the Rayleigh criterion:[58] the acoustic oscillation of a gas is encouraged if heat is injected as the gas is warmed by adiabatic compression, and/or heat is removed as the gas is cooled by adiabatic expansion [226, 227] (see also [224, 228]). An acoustic oscillation is most encouraged if the transfer of heat *out* of the gas varies in phase with the volume, so that the maximum heat is injected when the the gas is most compressed and therefore hottest, while the maximum heat is removed when the gas is most rarefied and therefore coldest.

This can also be understood by analogy to parametric resonance: when heat is injected, the "spring of the air" is stiffened, whereas when heat is removed the spring is slackened. If the stiffening aids the motion towards equilibrium and the slackening aids the motion away from equilibrium, then the overall oscillation is encouraged. But unlike in the parametrically resonant systems described in Sec. III F, in self-oscillators the variation of the elasticity is controlled by the acoustic vibration itself.

Ordinarily, sound waves are thermally *damped* because the air loses heat most quickly when its temperature is highest due to compression, while it absorbs the most heat when its temperature is lowest due to expansion. Newton famously computed a speed of sound [229] which turned out to be too low (by about 20%) in light of subsequent experimental tests. In effect, he treated the acoustic oscillation as isothermal. His expression is correct in the limit in which the frequency of sound is so low that the vibrating air remains in thermal equilibrium with its surroundings. Laplace obtained a value more compatible with measurements [230] by approximating the oscillation as adiabatic, which is valid in the limit in which the oscillation is very fast compared to the rate of damping by thermal radiation.[59]

Note that the putt-putt boat (Sec. VII B 1), unlike the Rijke tube, optimizes the Rayleigh criterion, since Eq. (89) implies that the heat removed by the condensation of steam varies in phase with the volume of the working gas inside the tank. Diesel and gasoline engines —though not usually conceptualized as thermoacoustic oscillators— also optimize the Rayleigh criterion, by igniting the fuel (and therefore maximizing the injection of heat) when the working gas is most compressed (see Sec. VI B).

Another interesting thermoacoustic self-oscillator is the "singing flame:" if a small flame, produced by hydrogen burning as it leaves a narrow tube, is inserted into a larger tube —which may be either open or closed at the top— the air inside the larger tube can in some circumstances ring audibly in a sustained way. This phenomenon was first described in [232] and is discussed by Rayleigh in [233], though his treatment was later found to be somewhat incomplete (see [228, 234, 235]).

4. Cepheid variables

Cepheid variable stars are a very important instance of natural thermodynamic self-oscillation. Their name derives from John Goodricke's observation, in 1784, that the brightness of the star δ Cephei varied regularly with a period of about five days. Goodricke and his colleague Edward Pigott then discovered other stars whose brightness also

---

[58] This is not to be confused with the better-known "Rayleigh criterion" in optics.

[59] On the relevance of Rayleigh's criterion to understanding the difference between Newton's and Laplace's computation, see [226, 227]. On the historic controversy regarding the speed of sound, see [231].



FIG. 29: The waveform above represents the variation in the brightness of a typical Cepheid variable star, which increases rapidly and then fades gradually, with a period of a few days. The circles below schematically represent the corresponding variations in the size and color of the star, which have been exaggerated for clarity. The oscillation in brightness leads the oscillation in the volume of the star by a quarter of a period. This illustration is adapted from [243].

pulsates, usually with a period of a few days. In the early 20th century, Henrietta Swan Leavitt discovered that the period of a Cepheid's pulsation is tightly related to the star's intrinsic brightness [236]. This made Cepheid variables the first reliable "standard candle" by which astronomers could measure distances to other galaxies, leading eventually to Edwin Hubble's discovery that the Universe is expanding [237]. See [238] for a review of the history and the science of this subject.

When a yellow supergiant star is running out of hydrogen fuel, it may begin to collapse. The compression causes an increase in temperature and pressure that slows down the collapse and eventually causes the star to expand and cool. The resulting cycle of the volume of the star would be damped away relatively quickly if it were not for a mechanism that injects heat into the core of the star during the compression phase and removes it during the expansion phase, in accordance with the Rayleigh criterion (see Sec. VII B 3).

As the core is compressed, the rate of nuclear fusion increases (much like the fuel ignites during compression in a Diesel engine). The excess heat produced is not radiated away because the core of a Cepheid is surrounded by a layer of ionized helium (He^+) and the radiation from the heated core causes that layer of helium to become doubly ionized (He^{++}), making it more opaque and preventing the heat from escaping. During the expansion, the helium layer cools and goes back to being singly ionized, which decreases the opacity and allows heat to escape.

In 1916, Arthur Eddington became interested in the thermodynamics of stars when he realized that the pulsation of the Cepheids presented a theoretical puzzle, namely,

> to find if possible some cause maintaining the mechanical energy of pulsation against the loss by dissipative forces—some method by which the mechanical energy could be automatically extracted from the abundant supplies of heat at different temperatures in the star without violating the second law of thermodynamics. [239]

Eddington's first paper on the subject [240] rediscovered the Rayleigh criterion and proposed applying it to the Cepheid problem. In his 1926 book, *The internal constitution of the stars*, he explained that "we must make the star more heat-tight when compressed than when expanded" [241], and he drew an analogy between the corresponding mechanism and the action of the valve in a heat engine. The realization that this heat-tightening is due to the double ionization of a thin, outer helium layer was due, many years later, to S. A. Zhevakin [242]. This mechanism is now called the "Eddington valve," which might be something of a misnomer, because the helium layer controls the flow of heat, rather than the mechanical motion of the stellar material (see Sec. VI B).

Figure 29 shows a schematic plot for the brightness and the radius of a typical Cepheid variable, as functions of time. The brightness (which is directly related to the flow of heat *out* of the star's core) is in phase with the radial velocity of the star's surface (which gives the rate of the change of the star's volume). The oscillation of the brightness therefore *leads* the oscillation of the volume by a phase of $\pi/2$, which is sub-optimal from the point of view the Rayleigh criterion, but adequate to maintain the pulsation. In this respect Cepheid variables are most akin to the Rijke tube, described in Sec. VII B 2.

C. Lasers

Masers and lasers may be described as electromagnetic cavities in which the dielectric loss (i.e., the damping) is negative because the molecules or atoms of the dielectric medium have undergone a *population inversion*: more of them are in a higher-energy quantum state than in a lower-energy state to which transition via photon emission is possible. The electromagnetic oscillation within the cavity therefore causes the dielectric medium to feed energy into the oscillation by stimulated emission: the medium is therefore called "active." For introductory discussions of stimulated emission in two-state quantum systems, see, e.g., [244, 245].

A laser is therefore an electromagnetic self-oscillator, even though the mechanism responsible for the negative damping is quantum-mechanical and —unlike in a classical self-oscillator— requires a precise tuning of the energy separation ΔE of the quantum states involved in the stimulated emission, so that the photons emitted have an angular frequency $\omega = \Delta E/\hbar$ (where $\hbar$ is the reduced Planck constant) that is very close to the cavity's resonance (see [246]).

On the other hand, the population inversion that sustains the negative damping is achieved *without* tuning the frequency of the external power supplied to the active medium. The ratio of the laser's power output (in the forms of photons of energy $E = \hbar\omega$) to the total power input is therefore subject to limitations analogous to those discussed in Sec. VI C 1 for classical self-oscillators. See [247] for a basic discussion of the way in which population inversion is accomplished; essential power losses are seen in the production of photons or phonons with energies different from $\hbar\omega$.[60]

Charles Townes, the inventor of the first maser, explained the principle of its operation to laypeople by a simple mechanical analogy: Imagine a swimming pool, at one end of which a platform has been raised on a wobbly pillar. The platform is loaded with rocks (by analogy to population inversion). When a rock falls into the water, it produces a wave that travels to the other end of the pool, is reflected, and then hits the wobbly pillar, causing another rock to fall. If the wobbling of the pillar absorbs negligible energy from the wave, this serves as an analogy of stimulated emission. The falling rock then produces a new wave, which interferes constructively with the previous one. The process can continue as long as there are rocks on the platform, giving what Townes called a *waser*: water amplification by stimulated emission of rocks; see [248].

Townes's analogy nicely captures the nature of the laser as a self-oscillator in which the negative damping comes as quanta of energy quanta. The only important element that the waser lacks is an analog of the tuning of the energy of the rocks to the frequency of standing waves in the pool, which is substituted in the waser by the need to time the fall of the rocks so as to produce a new wave precisely in phase with the previous reflected wave. (This feature of the analogy is inevitable, since in the classical limit $\hbar \to 0$.)

Borenstein and Lamb showed in detail that a self-oscillating electromagnetic cavity may be built using only the laws of classical electrodynamics [249]. They avoid the need to tune the phases of the oscillators in the active medium by making them nonlinear, so that they can be entrained (see Secs. IV E and V B 3). On the (wholly academic) possibility of describing classical self-oscillators as quantum lasers, see [250].

The applications of the concept of self-oscillation to the semi-classical theory of lasers are treated in detail in [105, 251], including the relaxation oscillation seen in ruby lasers. The relevance of entrainment to the description of the operation of lasers is discussed in [252–254]. On chaotic behavior in laser systems, see [255].

An important and instructive kind of macroscopic quantum oscillation is the alternating Josephson current between two superconductors separated by a thin insulator and held at a constant voltage difference by a battery [256]. Since this is conceptually quite distinct from the operation of a laser, and since its description requires a longer excursion into quantum mechanics, we treat it separately in Appendix A.

D. Business cycle

Pippard mentions geysers and the egg-laying cycle of domestic fowl as naturally-ocurring relaxation oscillations [257]. Sargent, Scully, and Lamb [105] mention also the business cycle in macroeconomics, i.e., the familiar fluctuation of production and economic activity that has often led to periods of rapid growth followed by recessions.

---

[60] In quantum physics, the origin of the Carnot-Le Corbeiller efficiency limit is very clear, perhaps even clearer than in the classical case. The probability of photon absorption by the medium goes to 1 only when the frequency of the photon approaches $\Delta E/\hbar$ for a transition. In practice, the population inversion mechanism involves a variety of transitions, only one of which corresponds to the frequency of the laser light outputted. The other transitions generate photons and phonons which bounce around the cavity and eventually exit it or else thermalize, heating the dielectric medium.

In fact, interest in modeling the business cycle as a relaxation oscillation was sparked in the 1930s, largely through the influence of Le Corbeiller, who explained to economists that

> if statistical observation leads us to believe that a given magnitude varies periodically, and if we look for the *cause* of those oscillations, we may suppose that that magnitude executes either (a) forced oscillations, or (b) self-oscillations,[61] which may be either (bα) sinusoidal or (bβ) of relaxation type. [258]

Le Corbeiller also had a great direct influence on the work of Harvard economist Richard M. Goodwin [259].[62] Goodwin's self-oscillatory model of the business cycle is similar to those proposed by Michał Kalecki [260], Alvin Hansen and Paul Samuelson [261], Lord Kaldor [262], Sir John Hicks [263], and others (see [264]). Chang and Smyth [265] and Varian [266] reformulated Kaldor's nonlinear model so that the business cycle corresponds to a relaxation limit cycle on the Liénard plane, like that represented in Fig. 15, with the coordinates x and y interpreted as the total income and the capital stock, respectively. This is briefly reviewed in [267]; for a complete treatment, see [268].

These theories relied on Keynesian macroeconomic constructs —the IS/LM and "multiplier-accelerator" models— which fell out of favor in the late 20th century because they lack adequate microeconomic foundations (i.e., an explanation in terms of the choices made by individuals) and therefore came to be seen as insufficiently explanatory and as being vulnerable to the "Lucas critique" [269] that if individuals incorporated the cycle into their expectations then it should disappear. In [265], Chang and Smyth also emphasize that self-oscillation in Kaldor's model occurs only for certain choices of the macroeconomic parameters.

That the business cycle may be due, at least in part, to a relaxation oscillation seems plausible in light of John Geanakoplos's recent work on the theory of the financial "leverage cycle" [270]. In Geanakoplos's theory, the leverage (i.e., the ratio of the value of an asset bought on credit to the down-payment by the buyer) is not necessarily stabilized by the equilibrium of supply and demand, and may therefore be subject to positive feedback effects that lead to relaxation-type oscillations in asset prices, which in turn can drive the economy as a whole into recurring booms and busts (for commentary on this theory see, e.g., [271–274]).

This leverage cycle might provide the microeconomic foundation that has been missing from models of the business cycle as a self-oscillation. See also, e.g., the work by Minksy on the "financial instability hypothesis" [275], and by Gjerstad and Smith on the role of credit expansion and leverage in the late 2000's financial crisis [276]. What principally seems to be lacking at the moment from the theory of the leverage cycle is a solid understanding of just how financial markets evade the Arrow-Debreu welfare theorems [277, 278], thus failing to give consistently efficient outcomes.

It should be stressed that the attempt to use control theory and the theory of dynamical systems in economics has a very long history, but has so far yielded few fruitful results. Åström and Murray suggest that this is in part because in economics "there are no conservation laws" [279]. This hardly seems to us a satisfactory explanation, since none of the other systems treated in this article obey conservation laws either. It is also commonly argued that economic systems are too complex and have too many variables, but this seems equally true of biological systems, in which the theory of dynamical systems has been used more profitably (see Secs. IV D, IV E, and V B 4). Sometimes it is also pointed out that controlled experiments are not possible in macroeconomics, but the mathematical theory of dynamical systems largely grew out of research in another science without controlled laboratory experiments, namely astronomy.

It seems to us, rather, that the principal complication is that the economic order results from the actions of sentient individuals, whose response depends on the information available to them at any given time. This information is constantly changing and includes even some awareness of economic theory itself and its predictions.

The Arrow-Debreu theorems establish that under conditions of perfect information and complete markets, the economic system will always be at an equilibrium state in which every individual enjoys the greatest satisfaction that can be obtained without making another individual worse off (what economists call an "efficient" outcome). But most of the interesting, real-world economic phenomena probably take place away from that equilibrium[63] and, in practice, the approach to equilibrium occurs under conditions in which information is far from perfect and markets are far from complete. From this economists have drawn strikingly divergent conclusions about policy (cf. [280, 281]).

---

[61] Le Corbeiller writes *oscillations autoentretenues*, which would be more faithfully rendered in English as "self-maintained oscillations." On the many names of self-oscillation, see the first footnote in Sec. I.

[62] Le Corbeiller, for his part, credits Goodwin with the original insight that two-stroke self-oscillators are possible [172].

[63] This is not so different from physics after all!

VIII. SUMMARY AND DISCUSSION

Like the mythical perpetual motion machine, self-oscillation succeeds in driving itself, but does so in a way compatible with the known laws of physics.[64] Instances of self-oscillation, both useful and destructive, abound in mechanical engineering, music, biology, electronics, and medicine. Indeed, all technology ultimately depends on self-oscillation, since only a self-oscillator can turn a steady source of power into a regular cyclical motion.

Self-oscillators, as distinct from forced and parametric resonators, can be readily identified by the fact that they sustain large, regular oscillations without an external rate having to be tuned to that frequency: *the motion itself* sets the phase of the driving force. We reviewed, for instance, how a violin string works as a self-oscillator, since increasing the velocity of the bow simply causes the same note to play more loudly, while the æolian harp, on the other hand, is a forced resonator, which rings loudly only when the wind speed happens to give a Strouhal frequency of vortex shedding close to the fundamental tone of the string (or to one of its harmonics).

In his early mathematical modeling of the vocal chords, Airy obtained self-oscillation from a delayed component of the harmonic restoring force. More generally, self-oscillation can be understood as the result of a component of the driving force that is modulated in phase with the *velocity* of the displacement. This gives the device a negative damping, causing the amplitude to grow exponentially with time, until nonlinear effects become significant.

Clocks and other common self-oscillators work by amplifying the device's vibration and feeding it back in order to drive the oscillator in phase with its velocity. The amplitude is limited by nonlinearities, as we saw explicitly for the van der Pol equation. In the regime of large negative damping, the van der Pol oscillator exhibits *relaxation oscillation* —in which the amplitude is fixed and the period is determined, not by the resonant frequency, but rather by nonlinear switching at thresholds— and it serves as a model of the beating heart and of neuronal firing, among other important phenomena.

We showed that a linear system with more than one degree of freedom can self-oscillate, even if no single degree of freedom is negatively damped, as long as the couplings are not symmetric (which is possible only if the degrees of freedom describe perturbations about a non-stationary trajectory). We also characterized the limit cycles for the simplest nonlinear self-oscillator, the van der Pol equation, and illustrated the phenomena of entrainment, frequency demultiplication, and chaos when a periodic forcing term was added to that equation.

All motors, which take a steady power input and produce a regularly alternating ouput, are self-oscillators and must waste some of the power, even if they could operate frictionlessly. We showed how this results from a general Carnot-Le Corbeiller theorem for the limit efficiency of dynamical frequency conversion. We also showed how the lossless halving of the frequency seen in a parametric resonator is not a violation of this theorem, but rather an instance of a *geometric* conversion: in the parametrically-driven pendulum with unit efficiency, the motor pulls up and down in phase with the vertical velocity of the mass, whose frequency is twice that of the pendulum's angular displacement.

We then briefly reviewed the concept of a servomechanism, emphasizing both their intended operation, based on applying negative feedback to the action of a motor, as well as the possible unwanted self-oscillation about the intended trajectory. We worked out the Rayleigh criterion for thermoacoustic self-oscillators and applied it to several systems, including Cepheid variable stars. We discussed how lasers can be described as self-oscillating electromagnetic cavities, and discussed some ideas (both old and new) on describing the macroeconomic business cycle as a relaxation oscillation.

Self-oscillation is both theoretically interesting and practically useful. Furthermore, it naturally connects with the mathematics and the history of control theory, since self-oscillation corresponds to the presence of positive feedback (and therefore of a dynamical instability). We see no excuse for the fact that the subject is hardly taught to physics students and that it remains, for most physicists, in the shadow of the notions of forced and parametric resonance.

Three major open theoretical problems raised in this article obviously call for further investigation as well: the full characterization of the operation of self-oscillators (including clocks) from the point of view of the arrow of time in statistical mechanics, a general theory of the limits on the efficiency of frequency conversion that incorporates geometrical conversion and extends to both classical and quantum systems, and a better understanding of the mechanism of macroeconomic self-oscillations, including the business cycle. We also hope that greater conceptual clarity about the energetics of self-oscillation might motivate other useful investigations in both pure and applied physics.

---

[64] An amusing thought in this regard is that the cranks who insist on building overbalanced wheels and similar devices (see [17]) are simply pursuing what is possible —indeed, very commonplace— by means which are already known to be unworkable.



FIG. 30: In a Josephson junction [256], two superconductors are separated by a thin insulator and kept at a constant voltage difference V by a battery. For $V = 0$ a steady current J can tunnel across the insulator if the relative phase of the quantum states of the superconductors is neither 0 nor π. For a fixed $V > 0$ the current J alternates with angular frequency $2eV/\hbar$.

Acknowledgments

Despite many years first as a physics student and then as a researcher in theoretical physics, I owe my awareness of self-oscillation to a recent series of accidents too complicated to relate here, but which is reflected in the eccentricities of this exposition. I especially thank Giancarlo Reali for communicating his enthusiasm for the putt-putt boat, for sharing with me the correspondence on the putt-putt that he had received form the late Iain Finnie [211], and for pointing me to the discussion of the van der Pol oscillator in [105] and of the "paradox of Bergeron" in [215].

I thank Charlie Bennett, Tom Hayes (who also helped me to procure a copy of [96]), Tristan McLoughlin, Take Okui, and Graeme Smith for extended discussions of self-oscillation and related matters, and also Bob Jaffe and Carl Mungan for their critiques of early drafts of this manuscript. I thank Sharon and Viviana Zlochiver for their guidance on the cardiology of Sec. IV D, and Andrés Marroquín and Álvaro Ramos for commenting on the discussion of the business cycle in Sec. VII D.

I thank Sarah Stacey for permission to reproduce the drawing of Fig. 1, Paul Horowitz for providing the image for Fig. 3, and Olivier Doaré and Emmanuel de Langre for the photographs shown in Fig. 5. I also thank Prof. de Langre for assistance in comparing the editions of [215]. I thank Greg Miller, of the University of Washington's Department of Civil and Environmental Engineering, for permission to use the photograph in Fig. 4.

I thank Jenny Hoffman, Bob Jaffe, Howard Georgi, and Take Okui for their encouragement. I also thank Jonathan Betts, George Levin, Markus Luty, and John McGreevy for discussions, and Igor Bargatin, Mariano Echeverría, Paul O'Gorman, Nitin Rughoonauth, Wati Taylor, and Ricardo Trujillo for comments, questions, and other sundry contributions.

I thank the NBI Summer Institute, in Copenhagen, for hospitality while some of this work was being completed. This work was supported in part by the US Department of Energy under contract DE-FG02-97IR41022.

Appendix A: Josephson effect

If two superconductors are separated by a thin insulator (a "Josephson junction," shown schematically in Fig. 30), a current

$$J = J_0 \sin \delta \tag{A1}$$

tunnels across the insulator, where J_0 is the maximum current attainable (whose value characterizes the junction) and δ is the relative phase between the two wavefunctions that describe the collective quantum state of each superconductor. [256]

For a constant voltage difference V between the two superconductors, the relative phase varies at a fixed rate

$$\dot{\delta} = \frac{2eV}{\hbar} \ , \tag{A2}$$

where e is the electron's charge. Thus, when $V = 0$ there will be a non-zero, direct current (DC) as long as the relative phase is neither 0 nor π. For $V > 0$ the alternating current (AC) will oscillate with angular frequency $2eV/\hbar$.

Feynman beautifully reviews the Josephson effect in [282], where he shows that it is a general feature of the weak coupling of two coherent quantum states. Although the Josephson effect for $V > 0$ satisfies Andronov's definition of self-oscillation as a macroscopic periodic motion (the AC across the Josephson junction) generated at the expense of a non-periodic source of energy (the battery that maintains the voltage difference between the superconductors), it is qualitatively different from all other systems that we have discussed in this article, since its mechanism is strictly quantum-mechanical. This is obvious in the fact that the expression for the AC frequency as a function of V contains a factor of Planck's constant, $\hbar$.

Nonetheless, Pippard (who was Josephson's graduate advisor at the time of Josephson's discovery) offers a useful classical analogy in [283]: Consider two coupled linear oscillators (for instance, two pendula joined by a spring). If they have the same frequency ω, then no energy will flow between them when they move either in phase ($\delta = 0$) or antiphase ($\delta = \pi$), since those are normal modes of the coupled system (see [150]). But if the phase takes another value, then energy will slosh back and forth between the oscillators.

In the case of the Josephson effect, each superconductor is held at a constant energy by the battery, so for constant δ the flow of power between them is steady. If the oscillators have different frequencies $\omega_{1,2}$, then the relative phase δ increases at a constant rate $|\omega_1 - \omega_2|$, which by Eq. (A1) is also the angular frequency of the flow of power across the junction.

What quantum mechanics adds to this classical picture is the conversion between frequencies and energies. Indeed, one may think of the DC Josephson effect for $V = 0$ as an exchange of quanta of energy

$$E_0 = \hbar\omega \ , \tag{A3}$$

where ω is the frequency of the oscillators. For $V > 0$ the energies of the two superconductors are not matched and the exchange of E_0 requires another process in which the energy of the whole system is adjusted by the emission of a quantum

$$E' = \hbar\left(\omega_1 - \omega_2\right) = \hbar\dot{\delta} \ . \tag{A4}$$

Physically, this emission can only correspond to the change in energy of a superconducting Cooper pair (with charge $2e$) as it moves across the junction voltage, so that

$$E' = 2eV \ , \tag{A5}$$

leading to the result of Eq. (A2).

Thus we see that the AC Josephson effect is more akin to quantum emission (in which a constant energy splitting ΔE is turned into radiation of frequency $\Delta E/\hbar$) than it is like the other self-oscillations described in this article; on this point, see also [284]. The Josephson AC is a macroscopic effect because a superconductor is in a macroscopic, coherent quantum state. Note as well that the AC across the junction turns on immediately when the external V is applied, without the exponential growth of small oscillations followed by an approach to a non-linear limit cycle that we saw in classical self-oscillators.

On the other hand, the emission described by Eq. (A4) appears to be somewhat analogous to the "tail" loss that we argued had to accompany the classical interconversion of frequencies; see Sec. VI C 1. That fact that for $\omega_1 = 2\omega_2$ we have $\dot{\delta} = \omega_2$ suggests that lossless parametric down-conversion in quantum optics (see [285]) might not be forbidden if $\omega_1/\omega_2 = 2$. Whether this is so, and the possible connection to the classical arguments about "geometric conversion" made in Secs. III F and VI C 1, deserve further investigation.

Appendix B: Historical aperçu

The practical uses of self-oscillators are very ancient and, as we emphasized in Sec. VI, are an intrinsic aspect of human technology. But the theoretical question of how a steady source of power can produce and maintain a periodic motion seems not to have been posed in the context of Newtonian mechanics until the late 1820s, with the work of Robert Willis [25] and G. B. Airy [24] on the operation of the human voice.

Even though Airy went on to become a long-serving Astronomer Royal, and Willis the Jacksonian Professor of Natural Philosophy at Cambridge, this early work was totally ignored. As far as we have been able to discover, only the anatomical component of Willis's research on the operation of the larynx attracted any attention, while Airy's paper was cited only by Henry Dircks, a self-taught engineer, in the context of his exhaustive but eccentric investigation into the history of perpetual motion research [286], published in 1861.[65] Amusingly, in [151] Kelvin and Tait originally dismissed the possibility of linear self-oscillation as an unphysical perpetual motion (see Sec. V A).

The theory of self-oscillation begins anew with Maxwell's research into the stability of machines controlled by governors [152]. Maxwell posed the problem as a mathematical puzzle, which was later solved in generality by Routh [156] and Hurtwitz [157], leading to a criterion for the stability of linear systems (see Sec. V A 1). This line of investigation leads eventually to modern control theory, primarily via the work of engineers and mathematicians. Its focus has always been on the conditions for a servomechanism to keep to its intended trajectory. The connection to the problem of how the motor that drives such a mechanism can run in the first place was not pursued. If it had been, then perhaps the study of self-oscillation might have influenced the development of thermodynamics. As it was, the link was not made explicitly until 1936 by Le Corbeiller [187] and his tentative ideas were then left unexplored (see Sec. VI).[66]

The first edition of Lord Rayleigh's *Theory of Sound*, whose two volumes were published in 1877 and 1878 respectively, contains no discussion of self-oscillation, except for the brief comment on the role of delayed action in the operation of Helmholtz's "fork-interrupter" [30], and of velocity-dependent friction on the powering of the vibration of a violin string by the bow [67]. In his review of the second volume of Rayleigh's treatise, Helmholtz called attention to this deficiency:

> There is still an important chapter wanting, viz., that on the theory of reed-pipes, including the human voice [...] Altogether, the whole of this important class of motions, where oscillatory movements are kept up through a cause which acts constantly, deserves detailed theoretical consideration. [291]

It might well have been Helmholtz's urging that led Rayleigh to his investigations into self-oscillation [101, 226] and parametric resonance [82], which were eventually incorporated into the second edition of the *Theory of Sound* [292], published in 1894–1896.[67]

It is odd that Rayleigh's work on self-oscillation should have attracted so little attention for so long, even among acousticians, who have continued to cite Rayleigh's book even to this day, but not usually on that subject.[68] Van der Pol's first paper on electrical self-oscillation [98], published in 1920, cites Rayleigh in a surprisingly narrow context, considering that van der Pol's nonlinear equation of motion is equivalent to the one proposed by Rayleigh in [86, 101].

The work of van der Pol and his collaborators on self-oscillators attracted much attention, in the 1930s and beyond, from mathematicians, electrical engineers, physiologists, and even economists, but not from physicists. The research by Andronov (who coined the term "self-oscillation") and his associates in the Soviet Union was largely mathematical —in the tradition of Poincaré and Lyapunov— and had its greatest impact in the theory of ordinary differential equations and in control engineering (see, e.g., [4, 171, 293, 294]).

In particular, the issue of the flow of energy in self-oscillators seems to have received comparatively little attention. Initially, this might have been due to a widespread impression that the study of nonlinear equations of motion was a technically challenging problem unlikely to shed light of the sort of fundamental questions that might interest a theoretical physicist. What is perhaps more mysterious is that the explosion in interest in nonlinear dynamical systems that was engendered by the advent of fast and cheap digital computers and by the ascendance of chaos theory after the 1970s should have largely failed to call the attention of physicists back to these questions, except in the narrow context of the mathematical characterization of limit cycles and their entrainment (see Sec. V B).

---

[65] Dircks cited Airy as a last-minute addition to the manuscript and without evidence of understanding his argument; he dropped all reference to Airy from the "second series," published in 1870 [287]. It was presumably through Dircks's book that R. T. Gould learned of the existence of Airy's paper (see Sec. II C).

[66] It is intriguing that the young Willard Gibbs should have investigated the efficiency of power transfer in gears [200] (see Sec. VI C 2) and hydraulic turbines [288], as well as the stability of steam engine governors [289] (see Sec. V A), before turning his attention to thermodynamics in the 1870s. Gibbs's retiring personality and the highly abstract and parsimonious style of his writing make it difficult to determine to what extent his early work in engineering motivated or influenced his mature research on thermodynamics. See [290] for a discussion of this question.

[67] Even though Helmholtz [61] and Kelvin [62] had worked out the instability of the surface of separation between two fluid layers with a sufficient relative velocity (see Sec. III C), thus explaining the self-oscillation of the waves formed by the wind on the surface of the sea and other bodies of water, the connection was not made by either of them to "maintained oscillators" such as clocks and wind musical instruments.

[68] It is also telling that Eddington should have had to rediscover Rayleigh's criterion when he became interested in the thermodynamics of the pulsation of Cepheid variables (see Sec. VII B 4).

Appendix C: Note on sources

In this review of self-oscillation, we have made an effort to give all relevant references, both to the original research reports and to textbooks. For a physics student wishing to learn the subject systematically, further guidance is in order.

Lord Rayleigh's justly celebrated *Theory of Sound* [295] covers almost all topics of importance in mechanical vibrations and acoustics. Unfortunately, the age, length, and organization of Rayleigh's treatise may limit its usefulness for modern students. Note that, as explained in Appendix B, the theory of self-oscillation (which he calls "maintained vibration") is covered in the second edition, but not in the first.

At this time, there does not appear to be any textbook treatment of self-oscillation suitable for undergraduate physics students, and even leading contemporary textbooks in acoustics (e.g., [296, 297]) ignore the subject altogether. Perhaps the best introductory sources for physics students are the review of "self-sustaining oscillators" in [298], as well as the pedagogical articles by Billah and Scalan [51], and by Green and Unruh [33] on the Tacoma Narrows bridge collapse, all of which make a clear conceptual distinction between forced resonance and self-oscillation. Also, as noted in Sec. VII B 2, the Rijke tube provides an impressive demonstration of self-oscillation that can be easily conducted during a classroom lecture. (Pippard gives a clear and complete explanation of the operation of the Rijke tube in [224].)

Self-oscillation is covered by Sargent, Scully, and Lamb in [105] (where it is called "sustained" oscillation), by Pippard in [87, 124] (where it is called "maintained" oscillation), and by Fletcher and Rossing in [299] (where it is called "self-excited" oscillation). These treatments all use the method of slowly varying amplitude and phase (or "method of averaging"), developed by van der Pol [106] and by Krylov and Bogolyubov [300, 301] for the study of nonlinear vibrations; see also [302].

Selected Papers on Mathematical Trends in Control Theory [303] reproduces several important primary documents directly related to self-oscillation, including the work of Maxwell [152], Hurwitz [157], Nyquist [202], and van der Pol [122], each prefaced by a short explanation of its significance. It also includes Bateman's thorough historico-mathematical review of linear stability analysis [35], followed by a brief overview of the work of Poincaré and Lyapunov on the stability of the trajectories of nonlinear dynamical systems [170] (see Sec. V B 5). For a modern and thorough textbook treatment of control theory, see [304].

The review articles written in the 1930s by van de Pol [106] and Le Corbeiller [96, 187] are still worth reading. Also valuable is the brief overview presented by Le Corbeiller before the first meeting of the Econometric Society [258], convened at Lausanne in 1931, from which we quoted in Sec. VII D. (Unfortunately, [96] and [258] are only available in French.) Groszkowski compiled a very comprehensive bibliography of the research on self-oscillation published up to 1962, with emphasis on electrical engineering [305]. It is rather unfortunate that those works focus on electrical oscillators with vacuum tube amplifiers, which are now obsolete.

Soviet scientists A. A. Andronov, A. A. Vitt, and S. È. Khaĭkin produced one of the fullest available accounts of self-oscillation in the second edition of their monumental *Theory of oscillators*. This is available in English in an edition revised and abridged by Wilfred Fishwick in 1966 [1]. (The first edition appeared in Russian in 1937 without any acknowledgement of Vitt's contribution, as Vitt had been imprisoned and executed during Stalin's Great Purge [3, 4].) V. I. Arnol'd's *Ordinary Differential Equations* [293] admirably combines mathematical rigor with physical intuition and can serve as an excellent point of contact with the mathematical and engineering literature based on Poincaré's "qualitative theory of differential equations," Lyapunov stability, and differential topology (see Sec. V B 5). *Nonlinear Oscillations*, by Nayfeh and Mook, is a standard modern textbook on the subject for engineers [306], in which self-oscillators are identified as "self-sustaining systems."

Norbert Wiener's groundbreaking *Cybernetics* [307] offers a unique and fascinating perspective on some of the concepts covered in this article, though it is hardly a systematic treatment and appears to have been most influential in disciplines other than physics. A. B. Pippard presented another interesting and idiosyncratic treatment of these topics in *Response and stability* [308]. The description of lasers as self-oscillators by Lamb and his collaborators, cited in Sec. VII C, are also pedagogically valuable.

Many authors have written books for lay readers on aspects of the nonlinear theory of dynamical systems, especially chaos theory. Steven Strogatz's *Sync* [142] emphasizes some of the topics covered in this article, particularly about entrainment and chaos in relaxation oscillators (see Secs. IV E, IV F, and V B 3).

[1] A. A. Andronov, A. A. Vitt and S. È. Khaĭkin, *Theory of oscillators*, ed. W. Fishwick, (Mineola, NY: Dover, 1987 [1966]).

[2] N. V. Butenin, "Auto-oscillation," *Encyclopedia of Mathematics*, `http://www.encyclopediaofmath.org/index.php?title=Auto-oscillation&oldid=11682` (accessed 30 Apr. 2012).

[3] V. I. Arnol'd, *Ordinary Differential Equations*, (Berlin: Springer-Verlag, 1992), p. 151.

[4] C. Bissell, "A. A. Andronov and the Development of Soviet Control Engineering," IEEE Control Syst. Mag. **18**, 56–62 (1998).

[5] H. Goldstein, C. P. Poole and J. L. Safko, *Classical Mechanics*, 3rd ed., (San Francisco: Addison Wesley, 2002), sec. 2.7.

[6] S. W. Angrist, "Perpetual Motion Machines," Sci. Am. **218**(1), 115–122 (Jan. 1968).

[7] E. Fermi, *Thermodynamics*, (New York: Dover, 1956 [1937]), ch. III.

[8] R. P. Feynman, R. B. Leighton and M. Sands, *The Feynman Lectures on Physics*, vol. I, (Reading, MA: Addison-Wesley, 1964), lecture 44.

[9] R. P. Feynman, R. B. Leighton and M. Sands, *The Feynman Lectures on Physics*, vol. I, (Reading, MA: Addison-Wesley, 1964), lecture 4, p. 5.

[10] R. P. Feynman, R. B. Leighton and M. Sands, *The Feynman Lectures on Physics*, vol. I, (Reading, MA: Addison-Wesley, 1964), lecture 46.

[11] N. Wiener, *Cybernetics: or Control and Communication in the Animal and the Machine*, 2nd ed., (Cambridge, MA: MIT Press, 1965 [1961]), ch. I.

[12] E. Schrödinger, *What is Life? The Physical Aspect of the Living Cell* with *Mind and Matter* and *Autobiographical Sketches*, (Cambridge: Cambridge University Press, 1992 [1967]), pp. 149–152.

[13] S. Carroll, *From Eternity to Here: The Quest for the Ultimate Theory of Time*, (New York: Dutton, 2010).

[14] L. T. White, "Tibet, India, and Malaya as Sources of Western Medieval Technology," in *Medieval Religion and Technology*, (Berkeley: University of California Press, 1978), pp. 43–57.

[15] E. Somerset, Marquess of Worcester, *Century of Inventions*, ed. J. Buddle, (Newcastle: S. Hodgson, 1813 [1663]), no. LVI.

[16] M. B. Stewart, "The Marquess of Worcester's perpetual motion machine," Phys. Teach. **19**, 37 (1981).

[17] *A Machine to Die For: The Quest for Free Energy*, written and directed by Mark Eliot, narrated by Chris Wiggins, (Australia: ABC Television, 2003). See accompanying study guide at `http://www.abc.net.au/programsales/download/StGd%20Machine%20Die%20For.pdf` (accessed 30 Apr. 2012).

[18] D. Goldenberg, "Reinventing the Wheel," *Wired* **12**(12), 5 (Dec. 2004).

[19] R. T. Gould, *Oddities: A Book of Unexplained Facts*, revised ed., (London: Geoffrey Bles, 1944).

[20] D. Sobel, *Longitude: The True Story of a Lone Genius Who Solved the Greatest Scientific Problem of His Time*, (New York: Walker & Co., 2005 [1995]).

[21] *Longitude*, directed by Charles Sturridge, with Jeremy Irons, William Gambon, and Ian Hart, (UK: Granada Film Productions, 2000).

[22] J. Betts, *Time Restored: The Harrison Timekeepers and R. T. Gould, The Man Who Knew (Almost) Everything*, (Oxford: Oxford University Press, 2006).

[23] G. Orwell, "Charles Reade," in *The Collected essays, journalism, and letters of George Orwell*, vol. II, eds. S. Orwell and I. Angus, (Jaffrey, NH: David R. Godine, 2000 [1968]), pp. 34–37. This essay first appeared in *New Statesman and Nation*, 17 Aug. 1940.

[24] G. B. Airy, "On certain Conditions under which a Perpetual Motion is possible," Trans. Cambridge Phil. Soc. **3**, 369–372 (1830).

[25] R. Willis, "On the Mechanism of the Larynx," Trans. Cambridge Phil. Soc. **4**, 323–352 (1833). Willis had originally presented his work before the Society in May 1829. Airy refers to this investigation in [24].

[26] B. Marsden, "Willis, Robert (1800 – 1875)," *Oxford Dictionary of National Biography*, (Oxford: Oxford University Press, 2004).

[27] H. Babinksy, "How do wings work?" Phys. Educ. **38**, 497–503 (2003).

[28] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), pp. 306–311.

[29] H. Helmholtz, *Die Lehre von den Tonempfindungen als physiologische Grundlage für die Theorie der Musik*, 4th ed., (Braunschweig: F. Vieweg und Sohn, 1877), pp. 195–198. Available in English as *On the Sensations of Tone as a Physiological Basis for the Theory of Music*, 2nd English ed., (New York: Dover, 1954), pp. 121–122.

[30] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. I, (New York: Dover, 1945 [1894]), sec. 64.

[31] R. L. Wegel, "Theory of Vibration of the Larynx," Bell Syst. Tech. J. **9**, 207–227 (1930).

[32] J. Groszkowski, *Frequency of Self-Oscillations*, (New York: Macmillan Co., 1964), sec. 8.4.2.

[33] D. Green and W. G. Unruh, "The failure of the Tacoma Bridge: A physical model," Am. J. Phys. **74**, 706–716 (2006).

[34] N. Minorsky, "Self-excited Oscillations in Dynamical Systems Possessing Retarded Action," in *Selected Papers on Mathematical Trends in Control Theory*, eds. R. Bellmann and R. Kalaba, (New York: Dover, 1964), pp. 141–149. This is a reprinting of J. Appl. Mech. **9**, 65–71 (1942).

[35] H. Bateman, "The Control of an Elastic Fluid," in *Selected Papers on Mathematical Trends in Control Theory*, eds. R. Bellmann and R. Kalaba, (New York: Dover, 1964), pp. 18–64. This is a reprinting of Bull. Amer. Math. Soc. **51**, 601–646 (1945).

[36] M. F. Atiyah and G. W. Moore, "A Shifted View of Fundamental Physics," in *Perspectives in mathematics and physics: Essays dedicated to Isadore Singer's 85th birthday*, eds. T. Mrowka and S.-T. Yau, Surveys Diff. Geom. **15**, (Somerville, MA: International Press, 2011), pp. 1–17. [arXiv:1009.3176 [hep-th]]

[37] L. D. Landau and E. M. Lifshitz, *Mechanics*, 3rd ed., (Oxford: Elsevier, 1976), sec. 27.

[38] H. Goldstein, C. P. Poole and J. L. Safko, *Classical Mechanics*, 3rd ed., (Boston: Addison Wesley, 2001), sec. 11.7.

[39] J. V. José and E. J. Saletan, *Classical dynamics: A contemporary approach*, (Cambridge: Cambridge University Press, 1998), sec. 7.3.

[40] L. N. Hand and J. D. Finch, *Analytical Mechanics*, (Cambridge: Cambridge University Press, 1998), sec. 10.2.

[41] H. J. Pain, *The Physics of Vibrations and Waves*, 6th ed., (Chichester: John Wiley & Sons, 2005), ch. 14.

[42] H. Goldstein, C. P. Poole and J. L. Safko, *Classical Mechanics*, 3rd ed., (Boston: Addison Wesley, 2001), sec. 11.3.

[43] J. V. José and E. J. Saletan, *Classical dynamics: A contemporary approach*, (Cambridge: Cambridge University Press, 1998), sec. 7.1.3.

[44] L. D. Landau and E. M. Lifshitz, *Mechanics*, 3rd ed., (Oxford: Elsevier, 1976), sec. 22.

[45] P. Horowitz and W. Hill, *The Art of Electronics*, 2nd ed., (Cambridge: Cambridge University Press, 1989), sec. 1.22.

[46] H. Georgi, *The Physics of Waves*, (Englewood Cliffs, NJ: Prentice-Hall, 1993), ch. 2.

[47] H. Georgi, *The Physics of Waves*, (Englewood Cliffs, NJ: Prentice-Hall, 1993), ch. 1.

[48] Footage of the Tacoma Narrows bridge by the Tacoma Fire Department, from the Stillman Fires Collection and the Prelinger Archives (1941). Available at `http://www.archive.org/details/Pa2096Tacoma`

[49] "Tubby Trivia," *Tacoma Narrows Bridge: Extreme History*, Washington State Department of Transportation, `http://www.wsdot.wa.gov/tnbhistory/tubby.htm` (accessed 30 Apr. 2012).

[50] *Aerodynamic Stability of Suspension Bridges with Special Reference to the Tacoma Narrows Bridge*, ed. F. B. Farquharson, University of Washington Engineering Experimental Station Bulletin, no. 116, pts. 1–5, June 1949 – June 1954.

[51] K. Y. Billah and R. H. Scanlan, "Resonance, Tacoma Narrows bridge failure, and undergraduate physics textbooks," Am. J. Phys. **59**, 118–124 (1991).

[52] M. P. Païdoussis, S. Price and E. de Langre, *Fluid-Structure Interactions: Cross-Flow-Induced Instabilities*, (Cambridge: Cambridge University Press, 2011), ch. 2.

[53] J. W. Strutt, Baron Rayleigh, "Acoustical notes.—VII," Philos. Mag. (Ser. 6) **13**, 316–333 (1907).

[54] P. Dallard et al., "The London Millennium Footbridge," Struct. Eng. **79**, 17–33 (2001).

[55] S. H. Strogatz, *Sync: The Emerging Science of Spontaneous Order*, (New York: Hyperion, 2003), pp. 171–176.

[56] S. H. Strogatz et al., "Theoretical mechanics: Crowd synchrony on the Millennium Bridge," Nature **438**, 43-44 (2005).

[57] M. P. Païdoussis, S. Price and E. de Langre, *Fluid-Structure Interactions: Cross-Flow-Induced Instabilities*, (Cambridge: Cambridge University Press, 2011), sec. 4.2.

[58] E. de Langre, *Fluides et Solides*, (Paris: École Polytechnique, 2001), p. 74.

[59] O. Doaré and E. de Langre, "The flow-induced instability of long hanging pipes," Eur. J. Mech. A Solids **21**, 857–867 (2002).

[60] M. P. Païdoussis, *Fluid-Structure Interactions: Slender Structures and Axial Flow*, vol. 1, (London: Academic Press, 1998).

[61] H. Helmholtz, "On Discontinuous Movements of Fluids," Philos. Mag. (Ser. 4) **36**, 337–346 (1868). This is a translation of an article published in German in Berl. Monatsber. **23**, 215–228 (1868).

[62] W. Thomson (later Baron Kelvin), "Hydrokinetic Solutions and Observations," Philos. Mag. (Ser. 4) **42**, 362–377 (1871).

[63] H. Lamb, *Hydrodynamics*, 6th ed., (New York: Dover, 1945 [1932]), sec. 232.

[64] H. Jeffreys, "On the Formation of Water Waves by Wind," Proc. R. Soc. Lond. A **107**, 189–206 (1925).

[65] P. Horowitz and W. Hill, *The Art of Electronics*, 2nd ed., (Cambridge: Cambridge University Press, 1989), p. 61.

[66] H. Helmholtz, *On the Sensations of Tone as a Physiological Basis for the Theory of Music*, 2nd English ed., (New York: Dover, 1954), pp. 80–88, 384–388.

[67] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. I, (New York: Dover, 1945 [1894]), sec. 138.

[68] D. Terwagne and J. W. M. Bush, "Tibetan singing bowls," *Nonlinearity* **24**, R51–R66 (2011). [arXiv:1106.5657 [physics.flu-dyn]]

[69] V. Strouhal, "Über eine besondere Art der Tonerregung," Annalen Phys. **241**, 216–251 (1878).

[70] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. II, (New York: Dover, 1945 [1896]), sec. 372.

[71] J. W. Strutt, Baron Rayleigh, "Æolian Tones," Philos. Mag. (Ser. 6) **29**, 433–444 (1915).

[72] G. K. Batchelor, *An Introduction to Fluid Mechanics*, (Cambridge: Cambridge University Press, 2000 [1967]), sec. 4.7.

[73] M. P. Païdoussis, S. Price and E. de Langre, *Fluid-Structure Interactions: Cross-Flow-Induced Instabilities*, (Cambridge: Cambridge University Press, 2011), sec. 3.2.1.

[74] M. P. Païdoussis, S. Price and E. de Langre, *Fluid-Structure Interactions: Cross-Flow-Induced Instabilities*, (Cambridge: Cambridge University Press, 2011), secs. 2.10, 3.4.3.

[75] T. von Kármán, *Aerodynamics: Selected Topics in the Light of their Historical Development*, (Mineola, NY: Dover, 2004 [1954]), ch. III.

[76] J. Jeans, *Science & Music*, (Mineola, NY: Dover, 1968 [1937]), pp. 130–133.

[77] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), pp. 42–43.

[78] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. II, (New York: Dover, 1945 [1896]), secs. 322a–322c.

[79] N. H. Fletcher and T. D. Rossing, *The Physics of Musical Instruments*, 2nd ed., (New York: Springer-Verlag, 1998), ch. 17.

[80] G. W. Hill, "Memoir No. 29: On the Part of the Motion of the Lunar Perigee which is a Function of the Mean Motions of the Sun and Moon," in *The collected mathematical works of George William Hill*, vol. I, (Washington, D.C.: Carnegie Institution, 1906), pp. 243–270. This memoir was first published by John Wilson & Son, of Cambridge, MA, in 1877. It was reprinted in Acta Math. **8**, 1–36 (1886).

[81] E. Mathieu, "Mémoire sur le mouvement vibratoire d'une membrane de forme elliptique," J. Math. Pures Appl. **13**, 137–203 (1868).

[82] J. W. Strutt, Baron Rayleigh, "On the Maintenance of Vibrations by Forces of Double Frequency, and on the Propagation

of Waves through a Medium endowed with a Periodic Structure," Philos. Mag. (Ser. 5) **24**, 145–159 (1887).

[83] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. I, (New York: Dover, 1945 [1894]), sec. 68b.

[84] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), ch. 10.

[85] A. B. Pippard, *Response and stability: An introduction to the physical theory*, (Cambridge: Cambridge University Press, 2009 [1985]), p. 145.

[86] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. I, (New York: Dover, 1945 [1894]), sec. 68a.

[87] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), ch. 11.

[88] P. Horowitz and W. Hill, *The Art of Electronics*, 2nd ed., (Cambridge: Cambridge University Press, 1989), secs. 5.12–5.19.

[89] Bureau International des Poids et Mesures, *The International System of Units*, 8th ed., (Paris: Organisation Intergouvernementale de la Convention du Mètre, 2006), ch. 2.

[90] D. D. McCarthy and P. K. Seidelmann, *Time: From Earth Rotation to Atomic Physics*, (Weinheim: Wiley-VCH, 2009), ch. 10.

[91] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1983]), pp. 600–602.

[92] O. H. Schmitt, "A thermonic trigger," J. Sci. Instrum. **15**, 24–26 (1938).

[93] P. Horowitz and W. Hill, *The Art of Electronics*, 2nd ed., (Cambridge: Cambridge University Press, 1989), sec. 4.24.

[94] S. O. Pearson and H. St. G. Anson "Demonstration of Some Electrical Properties of Neon-filled Lamps," Proc. Phys. Soc. Lond. **34**, 175–176 (1921); "The Neon Tube as a Means of Producing Intermittent Currents," Proc. Phys. Soc. Lond. **34**, 204–212 (1921).

[95] C. Huygens, *Horologium oscillatorium, sive, De motu pendulorum ad horologia aptato demostrationes geometricæ*, (Paris: F. Muguet, 1673). Available in English at `http://www.17centurymaths.com/contents/huygenscontents.html` (accessed 30 Apr. 2012).

[96] P. Le Corbeiller, *Les systèmes autoentretenus et les oscillations de relaxation*, Conférences d'actualités scientifiques et industrielles **27**, (Paris: Hermann et Cie., 1931).

[97] M. V. Headrick, "Origin and evolution of the anchor clock escapement," IEEE Control Syst. Mag. **22**(2), 41–52 (2002).

[98] B. van der Pol, "A Theory of the Amplitude of Free and Forced Triode Vibrations," Radio Rev. **1**, 701–710, 754–762 (1920).

[99] E. V. Appleton and B. van der Pol, "On the form of free triode vibrations," Philos. Mag. (Ser. 6) **42**, 201–220 (1921).

[100] B. van der Pol, "On 'relaxation-oscillations,'" Philos. Mag. (Ser. 7) **2**, 978–992 (1926).

[101] J. W. Strutt, Baron Rayleigh, "On maintained vibrations," Philos. Mag. (Ser. 5) **15**, 229-235 (1883).

[102] T. Kanamaru, "Van der Pol oscillator," *Scholarpedia* **2**(1), 2202 (2007). `http://www.scholarpedia.org/article/Van_der_Pol_oscillator` (accessed 30 Apr. 2012).

[103] J. Groszkowski, *Frequency of Self-Oscillations*, (New York: Macmillan Co., 1964), sec. 3.9.

[104] P. Horowitz and W. Hill, *The Art of Electronics*, 2nd ed., (Cambridge: Cambridge University Press, 1989), secs. 4.04–4.06.

[105] M. Sargent III, M. O. Scully and W. E. Lamb, Jr., *Laser Physics*, (Boulder, CO and Oxford, UK: Advanced Book Program, Westview Press, 1977 [1974]), ch. IV.

[106] B. van der Pol, "The Nonlinear Theory of Electric Oscillations," Proc. Inst. Radio Engrs. **22**, 1051–1086 (1934).

[107] R. M. Goodwin, *Chaotic Economic Dynamics*, (Oxford: Oxford University Press, 1990), pp. 10, 111.

[108] S. Gradstein, "Relaxation Oscillations," Philips Tech. Rev. **1**, 39–45 (1936).

[109] E. Friedländer, "Über Kippschwingungen, insbesondere bei Elektronenröhren," Arch. f. Elektrotech. **16** 273–279 (1926); Arch. f. Elektrotech. **17**, 1–16, 103–142 (1926).

[110] Galen, *On Anatomical Procedures*, trans. Charles Singer, (Oxford: Oxford University Press, 1999 [1956]), book VII, sec. viii K II.

[111] L. da Vinci, *I manoscritti di Leonardo da Vinci della Reale biblioteca di Windsor: Dell'anatomia, fogli B*, eds. F. V. Sabashnikov and G. Piumati, (Turin: Roux e Viarengo, 1901), folio 13 – recto.

[112] B. van der Pol and J. van der Mark, "The heartbeat considered as a relaxation oscillation, and an electrical model of the heart," Philos. Mag. (Ser. 7) **6**, 763–775 (1928); Onde électr. **7** 365–392 (1928); Arch. Neerl. Physiol. **14**, 418–443 (1929).

[113] K. Grudziński, J. J. Żebrowski and R. Baranowski, "Nonlinear Oscillations in the Conduction System of the Heart – A Model," in *Complex Dynamics in Physiological Systems: From Heart to Brain*, eds. S. K. Dana, P. K. Roy and J. Kurths, (Berlin: Springer-Verlag, 2009), pp. 127–136.

[114] E. R. Kandel, J. H. Schwartz and T. M. Jessell, *Principles of Neural Science*, 4th ed., (New York: McGraw-Hill, 2000), part II.

[115] D. DiFrancesco, "Pacemaker Mechanisms in Cardiac Tissue," Annu. Rev. Physiol. **55**, 455–472 (1993).

[116] D. DiFrancesco, "The Role of the Funny Current in Pacemaker Activity," Circ Res. **106**, 434–446 (2010).

[117] H. F. Brown, D. DiFrancesco and S. J. Noble, "How does adrenaline accelerate the heart?" Nature **280**, 235–236 (1979).

[118] R. FitzHugh, "Impulses and Physiological States in Theoretical Models of Nerve Membrane," Biophys. J. **1**, 445–466 (1961).

[119] J. Nagumo, S. Arimoto and S. Yoshizawa, "An Active Pulse Transmission Line Simulating Nerve Axon," Proc. Inst. Radio Engrs. **50**, 2061–2070 (1962).

[120] E. M. Izhikevich and R. FitzHugh, "FitzHugh-Nagumo model," *Scholarpedia* **1**(9), 1349 (2006). `http://www.scholarpedia.org/article/FitzHugh-Nagumo_model` (accessed 30 Apr. 2012).

[121] E. M. Izhikevich, *Dynamical Systems in Neuroscience: The Geometry of Excitability and Bursting*, (Cambridge, MA: MIT Press, 2007), ch. 4.

[122] B. van der Pol, "Forced Oscillations in a Circuit with non-linear Resistance (Reception with reactive Triode)," in *Selected*

Papers on Mathematical Trends in Control Theory, eds. R. Bellmann and R. Kalaba, (New York: Dover, 1964), pp. 124–140. This is a reprinting of Philos. Mag. (Ser. 7) **3**, 65–80 (1927).

[123] C. Huygens, letter to his father, 26 Feb. 1665, no. 1335, in *Œuvres complètes de Christiaan Huygens*, vol. 5, (La Haye: Martinus Nijhoff, 1893), pp. 243–244. An English translation is given in A. Pikovsky, M. Rosenblum and J. Kurths, *Synchronization: A universal concept in nonlinear sciences*, (Cambridge: Cambridge University Press, 2001), appendix A1.

[124] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), ch. 12.

[125] R. P. Feynman, R. B. Leighton and M. Sands, *The Feynman Lectures on Physics*, vol. I, (Reading, MA: Addison-Wesley, 1964), lecture 45, sec. 6.

[126] N. H. Fletcher and T. D. Rossing, *The Physics of Musical Instruments*, 2nd ed., (New York: Springer-Verlag, 1998), sec. 5.5.

[127] J. Jeans, *Science & Music*, (Mineola, NY: Dover, 1968 [1937]), ch. III.

[128] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. II, (New York: Dover, 1945 [1896]), sec. 322b.

[129] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. II, (New York: Dover, 1945 [1896]), sec. 397.

[130] S. A. Fulop, *Speech Spectrum Analysis*, (Berlin: Springer-Verlag, 2011), sec. 3.2.

[131] R. Willis, "On the Vowel Sounds, and on Reed Organ-Pipes," Trans. Cambridge Phil. Soc. **3**, 231–268 (1829).

[132] S. A. Fulop, *Speech Spectrum Analysis*, (Berlin: Springer-Verlag, 2011), sec. 3.2.1.

[133] B. van der Pol and J. van der Mark, "Frequency Demultiplication," Nature **120**, 363–364 (1927).

[134] R. E. Mirollo and S. H. Strogatz, "Synchronization of Pulse-Coupled Biological Oscillators," SIAM J. Appl. Math. **50**, 1645–1662 (1990).

[135] B. van der Pol, "On oscillation hysteresis in a triode generator with two degrees of freedom," Philos. Mag. (Ser. 6) **43**, 700–719 (1922).

[136] A. J. Lotka, *Elements of Physical Biology*, (Baltimore: Williams and Wilkins, 1925).

[137] V. Volterra, "Variazioni e fluttuazioni del numero d'individui in specie animali conviventi," Mem. R. Accad. Naz. dei Lincei **2**, 31–113 (1926); *Leçons sur la Théorie Mathématique de la Lutte pour la Vie*, (Paris: Jacques Gabay, 1990 [1931]).

[138] V. I. Arnol'd, *Ordinary Differential Equations*, (Berlin: Springer-Verlag, 1992), sec. 2.7.

[139] G. F. Herrenden-Harker, "Relaxation Oscillations," Am. J. Phys. **8**, 1–22 (1940).

[140] N. S. Goel, S. C. Maitra and E. W. Montroll, "On the Volterra and Other Nonlinear Models of Interacting Populations," Rev. Mod. Phys. **43**, 231–276 (1971).

[141] F. Hoppensteadt, "Predator-prey model," *Scholarpedia* **1**(10), 1563 (2006). `http://www.scholarpedia.org/article/Predator-prey_model` (accessed 30 Apr. 2012).

[142] S. H. Strogatz, *Sync: The Emerging Science of Spontaneous Order*, (New York: Hyperion, 2003).

[143] R. G. Foster and L. Kreitzman, *Rhythms of Life: The Biological Clocks that Control the Daily Lives of Every Living Thing*, (New Haven: Yale University Press, 2004).

[144] A. Pikovsky, M. Rosenblum and J. Kurths, *Synchronization: A universal concept in nonlinear sciences*, (Cambridge: Cambridge University Press, 2001).

[145] M. L. Cartwright and J. E. Littlewood, "On non-linear differential equations of the second order: I. The equation $\ddot{y} - k\left(1 - y^2\right)\dot{y} + y = b\lambda k \cos\left(\lambda t + a\right)$, k large," J. London Math. Soc. **20**, 180–189 (1945).

[146] M. L. Cartwright, "Forced Oscillations in Nonlinear Systems," in *Contributions to the Theory of Nonlinear Oscillations*, Ann. Math. Studies **20**, (Princeton: Princeton University Press, 1950), pp. 149–241.

[147] S. L. McMurran and J. J. Tattersall, "Cartwright and Littlewood on van der Pol's equation," in *Harmonic Analysis and Nonlinear Differential Equations*, Contemp. Math. **208**, (Providence, RI: Am. Math. Soc., 1997), pp. 265–276.

[148] J. M. T. Thompson and H. B. Stewart, *Nonlinear Dynamics and Chaos*, 2nd ed., (Chichester: John Wiley & Sons, 2002).

[149] E. Lorenz, "Deterministic Nonperiodic Flow," J. Atmos. Sci. **20**, 130–141 (1963).

[150] H. Georgi, *The Physics of Waves*, (Englewood Cliffs, NJ: Prentice-Hall, 1993), sec. 3.3.

[151] W. Thomson (later Baron Kelvin) and P. G. Tait, *Treatise on Natural Philosophy*, (Oxford: Clarendon Press, 1867), sec. 343.

[152] J. C. Maxwell, "On Governors," in *Selected Papers on Mathematical Trends in Control Theory*, eds. R. Bellmann and R. Kalaba, (New York: Dover, 1964), pp. 3–17. This is a reprinting of Proc. R. Soc. Lond. **16**, 270–283 (1868).

[153] C. Huygens, *Horologium oscillatorium, sive, De motu pendulorum ad horologia aptato demostrationes geometricæ*, (Paris: F. Muguet, 1673), part 5. Available in English at `http://www.17centurymaths.com/contents/huygenscontents.html` (accessed 30 Apr. 2012).

[154] H. W. Dickinson, *James Watt: Craftsman and Engineer*, (Cambridge: Cambridge University Press, 2010 [1936]), ch. VI.

[155] N. Wiener, *Cybernetics: or Control and Communication in the Animal and the Machine*, 2nd ed., (Cambridge, MA: MIT Press, 1965 [1961]), pp. 11–12.

[156] E. J. Routh, *A Treatise on the Stability of a Given State of Motion, Particularly Steady Motion*, (London: Macmillan and Co., 1877).

[157] A. Hurwitz, "On the Conditions under which an Equation has only Roots with Negative Real Parts," in *Selected Papers on Mathematical Trends in Control Theory*, eds. R. Bellmann and R. Kalaba, (New York: Dover, 1964), pp. 70–82. This is a translation of a paper first published in German in Math. Ann. **46**, 273–284 (1895).

[158] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. I, (New York: Dover, 1945 [1894]), ch. V.

[159] A. B. Pippard, *Response and stability: An introduction to the physical theory*, (Cambridge: Cambridge University Press, 2009 [1985]), ch. 2.

[160] P. Bamberg and S. Sternberg, *A course in mathematics for students of physics*, vol. 1, (Cambridge: Cambridge University

Press, 1988), ch. 4.

[161] M. Stone, "Non-unilateral oscillations: Governor-controlled engine-driven generators," J. Franklin Inst. **214**, 633–646 (1932).

[162] J. G. Baker, "Self-Induced Vibrations," Trans. Am. Soc. Mech. Eng., APM-55-2, **55**, 5–13 (1933).

[163] L. D. Landau and E. M. Lifshitz, *Mechanics*, 3rd ed., (Oxford: Elsevier, 1976), sec. 41.

[164] E. T. Whittaker *A Treatise on the Analytical Dynamics of Particles and Rigid Bodies*, 4th ed., (Cambridge: Cambridge University Press, 1988 [1947]), secs. 83–85.

[165] H. W. Nichols, "Theory of Variable Dynamical-Electrical Systems," Phys. Rev. **10**, 171–193 (1917).

[166] W. Thomson (later Baron Kelvin) and P. G. Tait, *Treatise on Natural Philosophy*, 2nd ed., (Cambridge: Cambridge University Press, 1888), sec. 345x.

[167] L. D. Landau and E. M. Lifshitz, *Mechanics*, 3rd ed., (Oxford: Elsevier, 1976), pp. 112–113.

[168] A. Liénard, "Étude des oscillations entretenues," Rev. Gén. Élect. **23**, 901–912, 946–954 (1928).

[169] H. Poincaré, "Mémoire sur les courbes définies par une équation différentielle," and "Sur les courbes définies par les équations différentielles," in *Œuvres de Henri Poincaré*, vol. I, eds. P. Appel and J. Drach, (Paris: Gauthier-Villars et Cie., 1928), pp. 3–84, 90–161, 167–221. These are reprintings of J. Math. Pures Appl. (Ser. 3) **7**, 375–422 (1881); J. Math. Pures Appl. (Ser. 3) **8**, 251–296 (1882); J. Math. Pures Appl. (Ser. 4) **1**, 167–244 (1885); J. Math. Pures Appl. (Ser. 4) **2**, 155–217 (1886).

[170] R. Bellman and R. Kalaba, "The work of Lyapunov and Poincaré," in *Selected Papers on Mathematical Trends in Control Theory*, (New York: Dover, 1964), pp. 65–69.

[171] Y.-Q. Ye et al., *Theory of Limit Cycles*, Translations of Mathematical Monographs **66** (Providence, RI: Am. Math. Soc., 1986).

[172] P. Le Corbeiller, "Two-Stroke Oscillators," IRE Trans. Circ. Theory **7**, 387–398 (1960).

[173] B. van der Pol and J. van der Mark, "Quelques expériences avec des triodes et les oscillations de relaxation," Onde électr. **6** 461–464 (1927).

[174] J. V. José and E. J. Saletan, *Classical dynamics: A contemporary approach*, (Cambridge: Cambridge University Press, 1998), sec. 7.5.

[175] R. M. Goodwin, *Chaotic Economic Dynamics*, (Oxford: Oxford University Press, 1990), ch. 10.

[176] A. L. Hodgkin and A. F. Huxley, "A quantitative description of membrane current and its application to conduction and excitation in nerve," J. Physiol. **117**, 500–544 (1952).

[177] "The Nobel Prize in Physiology or Medicine 1963," `http://www.nobelprize.org/nobel_prizes/medicine/laureates/1963/` (accessed 30 Apr. 2012).

[178] H. Poincaré, *Les méthodes nouvelles de la mécanique céleste*, vols. I, II, and III, (New York: Dover, 1957 [1899]).

[179] A. M. Lyapunov, "The general problem of the stability of motion," Int. J. Control **55**, 531-773 (1992). This is a translation of a book first published in Russian as *Obshchaya zadacha ob ustoichivosti dvizheniya*, (Kharkov: Mathematical Society, 1892).

[180] V. I. Arnol'd, *Ordinary Differential Equations*, (Berlin: Springer-Verlag, 1992), sec. 23.

[181] A. A. Andronov, A. A. Vitt and S. È. Khaĭkin, *Theory of oscillators*, ed. W. Fishwick, (Mineola, NY: Dover, 1987 [1966]), ch. V, sec. 4.

[182] J. V. José and E. J. Saletan, *Classical dynamics: A contemporary approach*, (Cambridge: Cambridge University Press, 1998), sec. 7.2.

[183] A. A. Andronov, A. A. Vitt and S. È. Khaĭkin, *Theory of oscillators*, ed. W. Fishwick, (Mineola, NY: Dover, 1987 [1966]), p. 200.

[184] A. A. Andronov, A. A. Vitt and S. È. Khaĭkin, *Theory of oscillators*, ed. W. Fishwick, (Mineola, NY: Dover, 1987 [1966]), ch. VIII, sec. 10.

[185] M. J. Moran et al., *Fundamentals of Engineering Thermodynamics*, 7th ed., (Hoboken, NJ: John Wiley & Sons, 2011), secs. 9.2–9.3.

[186] R. B. Lindsay, "Philippe Le Corbeiller (1891-1980)," J. Acoust. Soc. Am. **69**, 1524 (1981).

[187] P. Le Corbeiller, "The non-linear theory of the maintenance of oscillations," J. Inst. Electr. Engrs. **79**, 361–378 (1936). Reprinted in Proc. Inst. Electr. Engrs. **11**, 292–309 (1936).

[188] M. Denny, "The efficiency of overshot and undershot waterwheels," Eur. J. Phys. **25**, 193–202 (2004).

[189] G. Müller and K. Kauppert, "Performance characteristics of water wheels," J. Hydraul. Res. **42**, 451–460 (2004).

[190] S. L. Dixon and C. A. Hall, *Fluid Mechanics and Thermodynamics of Turbomachinery*, 6th ed., (Burlington, MA and Oxford, UK: Butterworth-Heinemann, 2010), sec. 9.5.

[191] A. Pikovsky, M. Rosenblum and J. Kurths, *Synchronization: A universal concept in nonlinear sciences*, (Cambridge: Cambridge University Press, 2001), sec. 2.4.2.

[192] E. Schrödinger, *What is Life? The Physical Aspect of the Living Cell* with *Mind and Matter* and *Autobiographical Sketches*, (Cambridge: Cambridge University Press, 1992 [1967]), pp. 82–84.

[193] N. L. S. Carnot, *Réflexions sur la puissance motrice du feu, et sur les machines propres à développer cette puissance*, (Paris: Gauthier-Villars, 1878 [1824]). Available in English as *Reflexions on the Motive Power of Fire*, ed. R. Fox, (New York: Lilian Barber, 1986).

[194] L. N. M. Carnot, *Principes fondamentaux de l'équilibre et du mouvement*, (Paris: Deterville, 1803).

[195] W. Thomson (later Baron Kelvin), "An account of Carnot's Theory of the Motive Power of Heat; with Numerical Results deduced from Regnault's Experiments on Steam," Trans. Roy. Soc. Edinburgh **16**, 541–574 (1849). Reprinted

in *Mathematical and Physical Papers by Sir William Thomson*, vol. I, (Cambridge: Cambridge University Press, 1882), pp. 113–155.

[196] D. Walton and A. J. Goodwin, "The wear of unlubricated metallic spur gears," Wear **222**, 103–113 (1998).

[197] R. Hooke, "Animadversions on the first part of the *Machina Cœlestis*," in *Lectiones Cutlerianæ*, (London: John Martyn, 1679), p. 70. Available at `http://quod.lib.umich.edu/e/eebo/A44313.0001.001` (accessed 30 Apr. 2012).

[198] G. B. Airy, "On the Forms of the Teeth of Wheels," Trans. Cambridge Phil. Soc. **2**, 277–286 (1827). Available in annotated form at `http://www.loria.fr/~roegel/articles/airy1825teeth-annotated.pdf` (accessed 30 Apr. 2012).

[199] R. Willis, *Principles of Mechanism*, 2nd ed., (London: Longmans, Green, and Co., 1870), art. 71 and ch. V.

[200] J. W. Gibbs, *On the Form of the Teeth of Wheels in Spur Gearing*, Ph.D. dissertation, Sheffield Scientific School, Yale University (1863), secs. 17, 41. The dissertation was first published in *The Early Work of Willard Gibbs in Applied Mechanics*, eds. L. P. Wheeler, E. O. Waters and S. W. Dudley, (New York: Henry Schuman, 1947), pp. 9–39.

[201] E. O. Waters, "Commentary upon the Gibbs monograph," in *The Early Work of Willard Gibbs in Applied Mechanics*, eds. L. P. Wheeler, E. O. Waters and S. W. Dudley, (New York: Henry Schuman, 1947), pp. 41–50.

[202] H. Nyquist, "Regeneration theory," in *Selected Papers on Mathematical Trends in Control Theory*, eds. R. Bellmann and R. Kalaba, (New York: Dover, 1964), pp. 83–105. This is a reprinting of Bell Syst. Tech. J. **11**, 126–147 (1932).

[203] K. J. Åström and R. M. Murray, *Feedback Systems: An Introduction for Scientists and Engineers*, (Princeton and Oxford: Princeton University Press, 2008), ch. 9.

[204] F. W. Carter, "On the Stability of Running of Locomotives," Proc. R. Soc. Lond. A **121**, 585–611 (1928).

[205] K. Knothe, "History of wheel/rail contact mechanics: from Redtenbacher to Kalker," Veh. Syst. Dyn. **46**, 9–26 (2008).

[206] P. Horowitz and W. Hill, *The Art of Electronics*, 2nd ed., (Cambridge: Cambridge University Press, 1989), sec. 5.18.

[207] K. Flowers, "Visual 'closed-loop' and 'open-loop' characteristics of voluntary movement in patients with parkinsonism and intention tremor," Brain **99**, 269–310 (1976).

[208] N. Wiener, *Cybernetics: or Control and Communication in the Animal and the Machine*, 2nd ed., (Cambridge, MA: MIT Press, 1965 [1961]), pp. 7–8, 95–97, 107–108.

[209] B. Harley, *Toyshop Steam*, (Watford, UK: Argus Books, 1978), pp. 45–47.

[210] D. T. Piot, "Improvements in Steam Generators," UK Patent No. 20,081, A.D. 1891, (London: Her Majesty's Stationary Office, 1892). Available online at `http://www.sciencetoymaker.org/boat/joelPDFs/Piot1891.pdf` (accessed 30 Apr. 2012)

[211] I. Finnie, personal communication with G. Reali, 12 August 1996.

[212] *Ponyo*, written and directed by Hayao Miyazaki, (Japan: Studio Ghibli, 2008).

[213] "Toys Help War Against Vibration," *Popular Mechanics* **61**(2), 218–221 (Feb. 1934).

[214] A. Jenkins, "Sprinkler head revisited: Momentum, forces, and flow in Machian propulsion", Eur. J. Phys. **32**, 1213–1226 (2011) [arXiv:0908.3190 [physics.flu-dyn]].

[215] R. Comolet, *Mécanique expérimentale des fluides*, 5th ed., vol. I, (Paris: Dunod, 2002), p. 138.

[216] M. Sédille, *Turbo-machines hydrauliques et thermiques*, vol. I, (Paris: Masson, 1966), pp. 62–63.

[217] R. Boyle, *New Experiments Physico-Mechanicall, Touching the Spring of the Air, and its Effects*, (Oxford: by H. Hall, for Tho. Robinson, 1660).

[218] I. Finnie and R. L. Curl, "On the functioning of a familiar nonlinear thermodynamic oscillator," Proc. Internat. Union of Theor. and Appl. Mech., Symposium on Nonlinear Vibration **3**, 486–497 (1963).

[219] I. Finnie and R. L. Curl, "Physics in a toy boat," Am. J. Phys. **31**, 289–293 (1963).

[220] J. Bindon, "The Secret Workings of a Transparent Pop-Pop Engine," Model Engineer **192**, 132–135 (2004).

[221] H. W. Dickinson, *James Watt: Craftsman and Engineer*, (Cambridge: Cambridge University Press, 2010 [1936]), ch. III.

[222] P. L. Rijke, "Notice of a New Method of causing a Vibration of the Air contained in a Tube open at both ends," Philos. Mag. (Ser. 4) **17**, 419–422 (1859).

[223] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. II, (New York: Dover, 1945 [1896]), sec. 322j.

[224] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), pp. 343–345.

[225] K. I. Matveev, *Thermoacoustic Instabilities in the Rijke Tube: Experiments and Modeling*, Ph.D. dissertation, California Institute of Technology (2003).

[226] J. W. Strutt, Baron Rayleigh, "The explanation of certain acoustical phenomena," Nature **18**, 319–321 (1878).

[227] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. II, (New York: Dover, 1945 [1896]), sec. 322g.

[228] M. S. Howe, *Acoustics of Fluid-Structure Interactions*, (Cambridge: Cambridge University Press, 2008 [1998]), sec. 6.4.

[229] I. Newton, *Philosophiæ Naturalis Principia Mathematica*, (London: Royal Society, 1687), book II, props. XLVII–L. A modern commentary and paraphrase of Newton's derivation appears in S. Chandrasekhar, *Newton's* Principia *for the Common Reader*, (Oxford: Clarendon Press, 1995), ch. 28.

[230] P.-S. de Laplace, "De la vitesse du son et du mouvement des fluides élastiques," in *Traité de mécanique céleste*, vol. 5, (Paris: Bachelier, 1825), book 12, ch. III.

[231] B. S. Finn, "Laplace and the Speed of Sound," Isis **55**, 7–19 (1964).

[232] B. Higgins, "On the Sound produced by a Current of Hidrogen Gas passing passing through a Tube," Journ. Nat. Phil. Chem. Arts **1**, 129–131 (1802).

[233] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vol. II, (New York: Dover, 1945 [1896]), sec. 322h.

[234] A. T. Jones, "Singing Flames," J. Acoust. Soc. Am. **16**, 254–266 (1945).

[235] A. A. Putnam and W. R. Dennis, "Survey of Organ-Pipe Oscillations in Combustion Systems," J. Acoust. Soc. Am. **28**, 246–259 (1956).

[236] H. S. Leavitt, "1777 Variables in the Magellanic Clouds," Ann. Harvard Coll. Obs. **60**, 87–108 (1908); H. S. Leavitt and

E. C. Pickering, "Periods of 25 Variable Stars in the Small Magellanic Cloud," Harvard Coll. Obs. Circular **173**, 1–3 (1912).

[237] E. Hubble, "A relation between distance and radial velocity among extra-galactic nebulae," P. Natl. Acad. Sci. USA **15**, 168–173 (1929).

[238] S. Webb, *Measuring the Universe: The Cosmological Distance Ladder*, (Berlin: Springer-Praxis, 1999), sec. 7.2.

[239] A. S. Eddington, *The internal constitution of the stars*, (Cambridge: Cambridge University Press, 1988 [1926]), p. 397.

[240] A. S. Eddington, "The Pulsation Theory of Cepheid Variables," Observatory **40**, 290–293 (1917).

[241] A. S. Eddington, *The internal constitution of the stars*, (Cambridge: Cambridge University Press, 1988 [1926]), sec. 137.

[242] S. A. Zhevakin, "Physical Basis of the Pulsation Theory of Variable Stars," Annu. Rev. Astro. Astrophys. **1**, 367–400 (1963).

[243] D. H. Smith, "Eddington's Valve and Cepheid Pulsations," *Sky & Telescope* **68**(6), 519 (Dec. 1984).

[244] D. J. Griffiths, *Introduction to Quantum Mechanics*, 2nd ed., (Upper Saddle River, NJ: Pearson Prentice Hall, 2005), sec. 9.2.2.

[245] R. P. Feynman, R. B. Leighton and M. Sands, *The Feynman Lectures on Physics*, vol. III, (Reading, MA: Addison-Wesley, 1964), lecture 9.

[246] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), pp. 345–348.

[247] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1983]), pp. 605–609.

[248] M. Gunther, "Lasers: The Light Fantastic," *Playboy* **15**(2), 73–74, 181–184 (Feb. 1968).

[249] M. Borenstein and W. E. Lamb, Jr., "Classical Laser," Phys. Rev. A **5**, 1298–1311 (1972).

[250] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1983]), p. 609.

[251] M. Sargent III, M. O. Scully and W. E. Lamb, Jr., *Laser Physics*, (Boulder, CO and Oxford, UK: Advanced Book Program, Westview Press, 1977 [1974]), ch. VIII.

[252] R. Lang, M. O. Scully and W. E. Lamb, Jr., "Why is the Laser Line So Narrow? A Theory of Single-Quasimode Laser Operation," Phys. Rev. A **7**, 1788–1797 (1973).

[253] M. Sargent III, "Mode Locking in Quantum Optics," Appl. Phys. **1**, 133–139 (1973).

[254] M. Sargent III, M. O. Scully and W. E. Lamb, Jr., *Laser Physics*, (Boulder, CO and Oxford, UK: Advanced Book Program, Westview Press, 1977 [1974]), secs. 9-3, 12-3, 21-2.

[255] L. Mandel and E. Wolf, *Optical coherence and quantum optics*, (Cambridge: Cambridge University Press, 1995), sec. 18.8.4.

[256] B. D. Josephson, "Possible new effects in superconductive tunnelling," Phys. Lett. **1**, 251–253 (1962).

[257] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), pp. 359–361.

[258] P. Le Corbeiller, "Les systèmes autoentretenus et les oscillations de relaxation," Econometrica **1**, 328–332 (1933).

[259] R. M. Goodwin, "The Nonlinear Accelerator and the Persistence of Business Cycles," Econometrica **19**, 1–17 (1951).

[260] M. Kalecki, "A macrodynamic theory of business cycles," Econometrica **3**, 327–344 (1935).

[261] P. Samuelson, "Interactions between the Multiplier Analysis and the Principle of Acceleration," Rev. Econ. Statist. **21**, 75–78 (1939).

[262] N. Kaldor, "A Model of the Trade Cycle," Econ. J. **50**, 78–92 (1940).

[263] J. Hicks, *A Contribution to the Theory of the Trade Cycle*, (Oxford, UK: Claredon Press, 1950).

[264] T. Puu and I. Susko (eds.), *Business Cycle Dynamics: Models and Tools*, (Berlin: Springer-Verlag, 2006).

[265] W. W. Chang and D. J. Smyth, "The Existence and Persistence of Cycles in a Non-linear Model: Kaldor's 1940 Model Re-examined," Rev. Econ. Stud. **38**, 37–44 (1971).

[266] H. R. Varian, "Catastrophe Theory and the Business Cycle", Econ. Inquiry **17**, 14–28 (1979).

[267] G. L. Fonseca, "Kaldor's Non-Linear Cycle," in *The History of Economic Thought Website*, (New York: New School for Social Research), `http://homepage.newschool.edu/~het/essays/multacc/kaldcyc.htm` (accessed 30 Apr. 2012).

[268] G. Gandolfo, *Economic Dynamics*, 4th ed., (Berlin: Springer-Verlag, 2010), ch. 24.

[269] R. E. Lucas, Jr., "Econometric policy evaluation: A critique," in *Studies in Business-Cycle Theory*, (Cambridge, MA: MIT Press, 1983), pp. 104–130. This is a reprinting of an article that first appeared in *The Phillips Curve and Labor Markets*, eds. K. Brunner and A. H. Meltzer, Carnegie-Rochester Conference Series on Public Policy **1** (New York: American Elsevier, 1976), pp. 19–46.

[270] J. Geanakoplos, "The Leverage Cycle," in *NBER Macroeconomics Annual* **24**, eds. D. Acemoglu, K. Rogoff and M. Woodford, pp. 1–66 (2010).

[271] M. Whitehouse, "Crisis Compels Economists To Reach for New Paradigm," *Wall Street Journal*, 4 Nov., 2009.

[272] F. Allen, "Comment on 'The Leverage Cycle'," *NBER Macroeconomics Annual* **24**, eds. D. Acemoglu, K. Rogoff and M. Woodford, pp. 67–74 (2010).

[273] H. S. Shin, "Comment on 'The Leverage Cycle'," *NBER Macroeconomics Annual* **24**, eds. D. Acemoglu, K. Rogoff and M. Woodford, pp. 75–84 (2010).

[274] "Summary of Discussion on the 'Leverage Cycle'," *NBER Macroeconomics Annual* **24**, eds. D. Acemoglu, K. Rogoff and M. Woodford, pp. 85–87 (2010).

[275] H. Minsky, *Stabilizing an Unstable Economy*, (New York: Mc-Graw Hill, 2008 [1986]); "The financial instability hypothesis: a clarification," in *Risk of Economic Crisis*, ed. M. Feldstein, (Chicago: University of Chicago Press, 1991), pp. 158–170.

[276] S. Gjerstad and V. L. Smith, "Monetary Policy, Credit Extension, and Housing Bubbles: 2008 and 1929," Critical Rev. **29**, 269–300 (2009).

[277] K. J. Arrow, "An Extension of the Basic Theorems of Classical Welfare Economics," Proc. Second Berkeley Symp. on Math. Statist. and Prob., (Berkeley: University of California Press, 1951), pp. 507–532.

[278] G. Debreu, *Theory of Value: An Axiomatic Analysis of Economic Equilibrium*, (New Haven and London: Yale University Press, 1987 [1959]).

[279] K. J. Åström and R. M. Murray, *Feedback Systems: An Introduction for Scientists and Engineers*, (Princeton and Oxford: Princeton University Press, 2008), p. 14.

[280] J. E. Stiglitz, "The Invisible Hand and Modern Welfare Economics," NBER Working Paper No. 3641, (1991).

[281] V. L. Smith, *Rationality in Economics: Constructivist and Ecological Forms*, (Cambridge: Cambridge University Press, 2007).

[282] R. P. Feynman, R. B. Leighton and M. Sands, *The Feynman Lectures on Physics*, vol. III, (Reading, MA: Addison-Wesley, 1964), lecture 21, sec. 9.

[283] A. B. Pippard, *The physics of vibration*, omnibus ed., (Cambridge: Cambridge University Press, 1989 [1979]), pp. 416–424.

[284] M. Sargent III, M. O. Scully and W. E. Lamb, Jr., *Laser Physics*, (Boulder, CO and Oxford, UK: Advanced Book Program, Westview Press, 1977 [1974]), sec. 21-4.

[285] L. Mandel and E. Wolf, *Optical coherence and quantum optics*, (Cambridge: Cambridge University Press, 1995), sec. 22.4.

[286] H. Dircks, *Perpetuum mobile; or, Search for self-motive power, during the 17th, 18th, and 19th centuries*, (London: E. & F. N. Spon, 1861), pp. xli, 203, 537–539.

[287] H. Dircks, *Perpetuum mobile; or, Search for self-motive power, during the 17th, 18th, and 19th centuries*, second series, (London: E. & F. N. Spon, 1870).

[288] L. P. Wheeler, *Josiah Willard Gibbs: The History of a Great Mind*, (Woodbridge, CT: Ox Bow Press, 1998 [1951]), pp. 34–35.

[289] L. P. Wheeler, "The Gibbs Governor for Steam Engines," in *The Early Work of Willard Gibbs in Applied Mechanics*, eds. L. P. Wheeler, E. O. Waters and S. W. Dudley, (New York: Henry Schuman, 1947), pp. 63–78.

[290] L. P. Wheeler, *Josiah Willard Gibbs: The History of a Great Mind*, (Woodbridge, CT: Ox Bow Press, 1998 [1951]), chs. III–IV.

[291] H. Helmholtz, "Lord Rayleigh's 'Theory of Sound,' " Nature **19**, 117–118 (1878).

[292] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., vols. I and II, (New York: Dover, 1945 [1896]), secs. 66a, 68a–68b, 103a–103b, 322a–322k, 397, appendix to ch. V.

[293] V. I. Arnol'd, *Ordinary Differential Equations*, (Berlin: Springer-Verlag, 1992).

[294] D. Aubin and A. D. Dalmedico, "Writing the History of Dynamical Systems and Chaos: *Longue Durée* and Revolution, Disciplines and Cultures," Hist. Math. **29**, 273–339 (2002).

[295] J. W. Strutt, Baron Rayleigh, *The Theory of Sound*, 2nd ed., in two volumes, (New York: Dover, 1945 [1894–1896]). This work can be downloaded from Google Books, see: `http://www.archive.org/details/theorysound07raylgoog` (vol. I) and `http://www.archive.org/details/theorysound05raylgoog` (vol. II).

[296] A. D. Pierce, *Acoustics: an Introduction to its Physical Principles and Applications*, (Melville, NY: Acoustic Society of America, 1989).

[297] T. D. Rossing, F. R. Moore, and P. A. Wheeler, *The Science of Sound*, 3rd ed., (San Francisco: Addison Wesley, 2002).

[298] A. Pikovsky, M. Rosenblum and J. Kurths, *Synchronization: A universal concept in nonlinear sciences*, (Cambridge: Cambridge University Press, 2001), ch. 2.

[299] N. H. Fletcher and T. D. Rossing, *The Physics of Musical Instruments*, 2nd ed., (New York: Springer-Verlag, 1998), ch. 5.

[300] N. M. Krylov and N. N. Bogolyubov, *Introduction to non-linear mechanics*, (Princeton: Princeton University Press, 1947 [1943]).

[301] N. N. Bogolyubov and Y. A. Mitropolsky, *Asymptotic Methods in the Theory of Nonlinear Oscillations*, (New York: Gordon and Breach, 1961).

[302] A. A. Andronov, A. A. Vitt and S. È. Khaĭkin, *Theory of oscillators*, ed. W. Fishwick, (Mineola, NY: Dover, 1987 [1966]), ch. IX.

[303] R. Bellmann and R. Kalaba (eds.), *Selected Papers on Mathematical Trends in Control Theory*, (New York: Dover, 1964).

[304] K. J. Åström and R. M. Murray, *Feedback Systems: An Introduction for Scientists and Engineers*, (Princeton and Oxford: Princeton University Press, 2008).

[305] J. Groszkowski, *Frequency of Self-Oscillations*, (New York: Macmillan Co., 1964), pp. 447–523.

[306] A. H. Nayfeh and D. T. Mook, *Nonlinear Oscillations*, (New York: John Wiley & Sons, 1995 [1979]).

[307] N. Wiener, *Cybernetics: or Control and Communication in the Animal and the Machine*, 2nd ed., (Cambridge, MA: MIT Press, 1965 [1961]).

[308] A. B. Pippard, *Response and stability: An introduction to the physical theory*, (Cambridge: Cambridge University Press, 2009 [1985]).